Dewcon, Inc. ▪ Post Office Box 439 ▪ Basking Ridge, NJ 07920
Tel: 908-296-0388 ▪ Fax: 908-766-8992 ▪ dewconinc@yahoo.com

November 3, 2026

Village of Croton-On-Hudson
Town of Cortlandt
Westchester County, New York

Attention: Bryan Healy, Village Manager

Reference: Proposal (Revised) – **Lounsbury Road – Cement Lining Project – Croton-On-Hudson Water Infrastructure Improvements – Village of Croton-On-Hudson, Town of Cortlandt, Westchester County, New York**

Dewcon, Inc. proposes to clean and cement mortar line 1,538 linear feet of 8" cast iron water main including all bypass piping, pipe work, excavation, shoring, materials, backfill, and paving as per the attached layout, 2026 work only, and the bid unit pricing shown on the schedule below.

Item	Croton-On-Hudson - Lining Project Description	Unit	Quantity Proposal	Bid Unit	Total Proposal
16	Temporary Water Supply (Bypass and Services)	ls.	1	$ 275,000.00	$ 275,000.00
18	6" D.I.P.	l.f.	59	$ 300.00	$ 17,700.00
19	8" D.I.P.	l.f.	14	$ 300.00	$ 4,200.00
22	8" C&L	l.f.	1,538	$ 125.00	$ 192,250.00
24	6"G.V	ea.	5	$ 6,000.00	$ 30,000.00
25	8"G.V	ea.	4	$ 10,000.00	$ 40,000.00
29	Fire Hydrant	ea.	4	$ 12,500.00	$ 50,000.00
30	Remove Fire Hydrant	ea.	4	$ 500.00	$ 2,000.00
31	Remove Exiting Valve	ea.	4	$ 100.00	$ 400.00
45	Mob. & Demobilization.	ls.	1	$ 15,000.00	$ 15,000.00
					$ 626,550.00

This work will be done in accordance with the AWWA C-602 specification. Our price is based on prevailing wages. All work to be done during regular business hours.

Work to be performed by Dewcon, Inc.:

1. We will excavate, shore, backfill, and pave all access pits (Pits only, no mill & overlay included). Excavations will be sheeted in accordance with OSHA Standard Specification. Preferred method of top paving is infrared paving.
2. We will supply all labor, equipment, and materials to mechanically clean and cement mortar line the cast iron water mains in accordance with the AWWA C602 Standard and the project specifications.

3. We will complete all piping work (valves, hydrants, nipples, fittings), as shown on the drawings.
4. Every crew member will have the ten hour OSHA Construction Safety and Health Certificate.
5. Furnish the labor, material, and equipment to install a 2" & 4" temporary by-pass system with rubber ramps.
6. Supply labor, material, and equipment to chlorinate the temporary by-pass. Dewcon will **NOT** collect and deliver the water samples to the lab for testing
7. Supply labor and materials to make all temporary connections to existing water services by means of a ¾" high-pressure hose (150 lbs. working pressure and 300 bursting pressure)
8. Provide temporary hydrants in close proximity to hydrants being taken out of service or as directed by the general contractor.
9. Supply all labor, equipment, and material to saw cut and bury the bypass at all roadway crossings.
10. Supply all labor, equipment, and material to temporary and permanent pave all bypass roadway crossings and associated work.
11. Assume responsibility for all maintenance and repair to the temporary by-pass system and appurtenances for the duration of the project 24 hours a day.
12. We have included two flag men per day in our pricing. If additional flaggers or police officers are required, it would be an additional cost. We don't anticipate this being an issue.

Village of Croton-On-Hudson Responsibilities:

1. Provide all pertinent permits required at no cost to Dewcon, Inc.
2. Provide a staging area for our equipment and materials at no cost to Dewcon, Inc.
3. Collect and deliver the water samples to the lab for testing.

This proposal is good for 30 days. Upon your acceptance, this proposal will become a part of the contract. Should you have any questions or require additional information do not hesitate to call.

Sincerely,

Ryan C. Dewey

Ryan Dewey
Vice President

This Proposal and Agreement is Accepted By:

_____

_____

Print Name

_____

Title

_____

Date