

NOTE (STAIRS):

- STAIR MANUFACTURER TO PROVIDE SHOP DRAWINGS TO ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION. SHOP DRAWINGS SHALL BE STAMPED BY ENGINEER WITH JURISDICTION AT PROJECT LOCATION.
- 2. COORDINATE STAIRS WITH GRADE.
- 3. PROVIDE 11" MIN. TREAD, 7" MAX. RISER PER 2015 INTERNATIONAL BUILDING CODE REQUIREMENTS.
- 4. PROVIDE METAL GRATE TREADS.
- 5. PROVIDE CLOSED RISERS PER 2015 INTERNATIONAL BUILDING CODE REQUIREMENTS.
- 6. PROVIDE 36" MIN. BETWEEN HANDRAILS.
- 7. PROVIDE 42" HIGH GUARDRAIL IN ADDITION TO 36" HIGH HANDRAIL (1 1/2" O.D.). GUARDRAIL SHALL NOT HAVE OPENINGS THAT ALLOW PASSAGE OF A 4" DIA. SPHERE.
- 8. PROVIDE POWDER-COATED HANDRAILS, GUARDRAILS, TREADS, RISERS AND STRINGERS. COORDINATE WITH OWNER.
- 9. EXTEND HANDRAILS 12" MIN. BEYOND RISER AT TOP AND BOTTOM OF STAIRS.
- 10. PROVIDE POST SUPPORTS AT INTERMEDIATE LANDING, POWDER-COAT TO MATCH STAIRS.
- 11. ALL WELDED CONNECTIONS TO BE ALL AROUND GROUND SMOOTH.

NOTES:

- 1. GC TO VERIFY WITH TRUSS MANUFACTURER ON ADDITIONAL LOAD OF OCCUPIED FLOOR ONTO THE GIRDER TRUSS.
- FLOOR JOISTS WILL NEED TO BE DOUBLED UP TO COMPLY WITH REQUIRED OCCUPIED LOAD FOR THE FLOOR.
- 3. G.C. TO VERIFY GLASS IS INSULATED AS PER CONSTRUCTION DOCUMENTS.









