



Village of
ESTERO

VILLAGE OF ESTERO
PLANNING ZONING AND DESIGN BOARD MEETING
PACKET
OCTOBER 12, 2021, 04:30 PM



COVID-19 NOTICE:

The Village Council Meeting will be conducted physically in Council Chambers at Village Hall, 9401 Corkscrew Palms Circle, with an opportunity to participate virtually. The meeting will be broadcasted live via the Village of Estero website <https://estero-fl.gov/council/watch-meetings-online/>. Access in Council Chambers will be limited in order to comply with the safety instructions relating to COVID-19. Please see the [bottom of this agenda](#) for further information and instructions for public participation.

AGENDA

PLANNING ZONING AND DESIGN BOARD MEETING

9401 Corkscrew Palms Circle, Estero, Florida
October 12, 2021, 04:30 pm

- 1. CALL TO ORDER**
- 2. PLEDGE OF ALLEGIANCE**
- 3. ROLL CALL**
- 4. APPROVAL OF AGENDA**
- 5. BUSINESS**

Items on the agenda are generally treated in sequential order, and due to the length of the agenda any or all of the items listed for discussion may be rescheduled to a later date for consideration.

The meeting will adjourn no later than 9:00 P.M. unless extended by the Board.

6. PUBLIC HEARINGS (Quasi-Judicial)

The public will have an opportunity to speak for five minutes per agenda item.

- a. Truist Bank Monument Sign (formerly BBT Bank) (District 7) 20280 Grand Oaks Shoppes Boulevard located north of Corkscrew Road, and just north of Dunkin Donuts on east side of Ben Hill Griffin Parkway.**
 - Request review and approval of the design for the monument and directional signs.
 - Public Information Meetings are optional for monument signs.

- Planning Zoning and Design Board will make a decision on the Truist Bank Monument Sign.

Attachment: [1. Application - Truist Bank Sign Package.pdf](#)

Attachment: [2. Truist Bank Monument Sign Presentation.pdf](#)

b. Christ Community Ministries Development Order (DOS2021-E001) (District 4) 20810 Highlands Avenue, located on the northwest corner of County Road and Highlands Avenue, immediately east of Estero Fire Rescue Station 41.

Development Order to expand the existing church by 2,972 square feet and to expand the parking on a 2.3-acre site.

- The Public Information Meeting was held February 24, 2021 before the Design Review Board.
- Planning Zoning and Design Board will make a decision on the Development Order.

Attachment: [1. Christ Community Ministries Staff Report DOS2021-E001.pdf](#)

Attachment: [2. Christ Community Ministries Site Construction Plans.pdf](#)

Attachment: [3. Christ Community Ministries Architectural Plans.pdf](#)

Attachment: [4. Christ Community Ministries Landscaping Plans.pdf](#)

Attachment: [5. Christ Community Ministries Presentation.pdf](#)

c. AAAA PreK-8 School Development Order (DOS2021-E004) (District 4) 20897 Three Oaks Parkway, 68.5-acre undeveloped parcel south of Copper Oaks, bounded by Three Oaks Parkway on the west and I-75 on the east.

Development Order for construction of elementary and middle school site, and monument sign.

- The Public Information Meeting was held September 14, 2021.
- Planning Zoning and Design Board will make a decision on the Development Order and Monument Sign.

Attachment: [1. Staff Report - AAAA PreK-8 School DOS2021-E004.pdf](#)

Attachment: [2. Staff Report - Attachment 1 Deviation Requests.pdf](#)

Attachment: [3. AAAA PreK-8 School Presentation.pdf](#)

Attachment: [Estero Final Animation-1.m4v](#)

7. PUBLIC INPUT

(Each individual will be given five minutes to speak)

8. BOARD COMMUNICATIONS

Next meeting -- November 9, 2021

9. ADJOURN

General Attachments

[- Transcript.pdf](#)

ESTERO PLANNING ZONING AND DESIGN BOARD
TUESDAY, OCTOBER 12, 2021, 4:30 P.M.

DISCLAIMER:

THIS FILE REPRESENTS AN UNEDITED VERSION OF REALTIME
CAPTIONING WHICH SHOULD NEITHER BE RELIED UPON FOR COMPLETE
ACCURACY NOR USED AS A VERBATIM TRANSCRIPT.
ANY PERSON WHO NEEDS A VERBATIM TRANSCRIPT OF THE
PROCEEDINGS MAY NEED TO HIRE A COURT REPORTER.

04:30:46 >>Howard Levitan: I'M GOING TO CALL THE MEETING TO ORDER
04:30:49 AND ASK THAT YOU STAND FOR THE PLEDGE OF ALLEGIANCE.
04:30:58 [PLEDGE OF ALLEGIANCE]
04:31:12 MADAM CLERK, WOULD YOU CALL THE ROLL, PLEASE?
04:31:16 >>Tammy Duran: BOARD MEMBER GARGANO?
04:31:18 >>Anthony Gargano: HERE.
04:31:18 >>Kristin Jeannin: HERE.
04:31:21 >>Barry Jones: HERE.
04:31:22 >>Marlene Naratil: HERE.
04:31:24 >>Michael Sheeley: HERE.
04:31:27 >>Tammy Duran: BOARD MEMBER TATOOLIS IS NOT HERE.
04:31:29 >>Jim Wallace: HERE.
04:31:30 >>Howard Levitan: HERE.
04:31:32 >>Scotty Wood: HERE.
04:31:34 >>Tammy Duran: AND NANCY IS IN ZOOM.
04:31:36 >>Howard Levitan: YES.
04:31:37 I WOULD LIKE TO ASK FOR A MOTION TO APPROVE THE AGENDA FOR
04:31:42 TONIGHT.

04:31:43 >> SO MOVED.
04:31:46 >>Howard Levitan: THAT WAS ANTHONY, AND WHO SECONDED IT?
04:31:50 MICHAEL.
04:31:52 TERRIFIC.
04:31:53 OKAY.
04:31:55 ALL IN FAVOR, PLEASE SIGNIFY BY SAYING AYE.
04:31:58 ANY OPPOSED?
04:32:03 MOTION IS APPROVED.
04:32:04 OKAY.
04:32:06 THE BUSINESS TONIGHT IS THREE PUBLIC QUASI-JUDICIAL
04:32:12 HEARINGS.
04:32:12 AND WHEN THIS BOARD IS SCHEDULED TO CONSIDER AND VOTE ON
04:32:15 EITHER A ZONING APPLICATION OR A DEVELOPMENT ORDER, IT SITS
04:32:19 IN A QUASI-JUDICIAL CAPACITY.
04:32:21 THIS MEETING'S AGENDA INCLUDES ITEMS SUBJECT TO THOSE KINDS
04:32:25 OF PROCEEDINGS.
04:32:26 IF YOU INTEND TO PROVIDE TESTIMONY ON THE QUASI-JUDICIAL
04:32:31 MATTER BEFORE THE MATTER IS CALLED, YOU MUST FILL OUT A

04:32:35 PUBLIC SPEAKER'S CARD, GIVE IT TO THE VILLAGE CLERK AND YOU
 04:32:39 MUST BE SWORN IN BY THE BOARD ATTORNEY.
 04:32:41 BEFORE THE MATTER BEGINS, ANY WRITTEN COMMUNICATIONS THAT
 04:32:43 HAVE BEEN RECEIVED BEFORE THE CUTOFF DATE WILL BE PLACED
 04:32:47 INTO THE PUBLIC RECORD.
 04:32:49 BOARD MEMBERS WILL BE ASKED TO DISCLOSE ANY EX PARTE
 04:32:51 COMMUNICATIONS.

04:32:53 BOARD MEMBERS WILL BE ASKED IF THEY HAVE A CONFLICT
 04:32:56 REGARDING THE MATTER AND MUST DECLARE IT.
 04:32:58 IF THEY DO, THEY WILL NOT BE ALLOWED TO PARTICIPATE IN BOARD
 04:33:01 DISCUSSION OR VOTE ON THE MATTER.
 04:33:03 THE VILLAGE DIRECTOR OF COMMUNITY DEVELOPMENT OR STAFF
 04:33:07 DESIGNEE WILL INTRODUCE THE MATTER AND THEN ASK THE
 04:33:10 APPLICANT TO MAKE A PRESENTATION AND SUMMARIZE ANY RELATED
 04:33:14 AFFIDAVITS FROM APPLICANT'S EXPERTS IN ATTENDANCE.
 04:33:18 FOLLOWING THIS, THE DIRECTOR OF COMMUNITY DEVELOPMENT, OR
 04:33:20 STAFF DESIGNEE, WILL MAKE A PRESENTATION PROVIDING THE STAFF
 04:33:25 REPORT FINDINGS AND RECOMMENDATIONS.
 04:33:28 AFTER THIS, THE PUBLIC HEARING WILL BE OPENED AND ANYONE WHO
 04:33:31 HAS BEEN SWORN IN MAY PROVIDE TESTIMONY.
 04:33:34 IT IS IMPORTANT TO BE CONCISE AND LIMIT TESTIMONY TO FIVE
 04:33:38 MINUTES OR LESS.
 04:33:38 THE APPLICANT HAS THE RIGHT TO CROSS-EXAMINE ANY WITNESS,
 04:33:42 INCLUDING THE PUBLIC, AND MAY PROVIDE REBUTTAL.
 04:33:45 THE PUBLIC MAY NOT CROSS-EXAMINE WITNESSES, BUT MAY REQUEST
 04:33:49 THE BOARD TO DIRECT QUESTIONS ON THEIR BEHALF TO EITHER THE
 04:33:53 APPLICANT OR THE COMMUNITY DEVELOPMENT STAFF.
 04:33:55 PERSONS WHO HAVE BEEN DETERMINED BY THE BOARD TO BE
 04:33:58 INTERESTED PARTIES MAY CROSS-EXAMINE WITNESSES.
 04:34:03 IF A PERSON REPRESENTS AN ORGANIZATION, EVIDENCE OF THEIR
 04:34:06 AUTHORITY TO SPEAK FOR THE ORGANIZATION MUST BE PROVIDED.
 04:34:10 WILL ALL THOSE WHO INTEND TO TESTIFY IN EACH OF THE MATTERS,

04:34:14 OR ANY OF THE MATTERS ON OUR AGENDA TONIGHT, PLEASE STAND
 04:34:18 AND RAISE YOUR RIGHT HAND.
 04:34:21 BOARD ATTORNEY, CAN YOU PLEASE ADMINISTER THE OATH?
 04:34:23 NANCY, YOU'RE MUTED.
 04:34:33 >>Nancy Stroud: DO YOU SWEAR OR AFFIRM THAT THE TESTIMONY
 04:34:35 THAT YOU ARE ABOUT TO GIVE WILL BE THE TRUTH, THE WHOLE
 04:34:38 TRUTH, AND NOTHING BUT THE TRUTH?
 04:34:39 THANK YOU.
 04:34:45 >>Howard Levitan: OKAY.
 04:34:46 LET'S CALL THE FIRST CASE, WHICH IS TRUIST BANK MONUMENT
 04:34:52 SIGN, FORMERLY BBT BANK.
 04:34:54 >>Tammy Duran: CHAIRMAN LEVITAN, I WANTED TO LET YOU KNOW
 04:34:57 THAT BOARD MEMBER TATOOLE IS HERE NOW.
 04:34:59 >>Howard Levitan: OKAY.

04:35:00 TERRIFIC.
 04:35:00 I'LL CHECK HIM OFF.
 04:35:01 SO WE ARE COMPLETELY FULL.
 04:35:06 MARY, WOULD YOU LIKE TO LEAD US OFF ON THIS?
 04:35:10 >>Mary Gibbs: DO WE NEED TO CHECK FOR CONFLICTS OF INTEREST?
 04:35:13 >>Howard Levitan: YES.
 04:35:15 LET'S DO THAT.
 04:35:15 HAS ANYONE ON THE BOARD HAD ANY EX PARTE COMMUNICATIONS?
 04:35:21 IF SO, PLEASE DISCLOSE THE NATURE OF THE COMMUNICATION.
 04:35:24 ANYBODY?
 04:35:25 >> NONE.

 04:35:25 >>Howard Levitan: NO.
 04:35:26 OKAY.
 04:35:27 ANYBODY ON THE BOARD HAVE ANY CONFLICT OF INTEREST REGARDING
 04:35:30 THIS MATTER?
 04:35:31 >> NO.
 04:35:32 >> NO.
 04:35:33 >>Howard Levitan: NO.
 04:35:33 OKAY.
 04:35:34 LET'S GO AHEAD, MARY.
 04:35:37 >>Mary Gibbs: ALL RIGHT.
 04:35:39 THIS IS A REQUEST FOR A MONUMENT SIGN FOR TRUIST BANK, WHICH
 04:35:43 WAS FORMERLY THE BBT BANK, WHICH IS LOCATED ON BEN HILL
 04:35:47 GRIFFIN AND CORKSCREW ROAD, IF YOU KNOW WHERE THE GRANDEZZA
 04:35:50 PUBLIX SHOPPING CENTER IS.
 04:35:52 THIS IS AT THE NORTH END OF THAT SHOPPING PLAZA.
 04:35:54 SO THEY WANT TO REPLACE THE SIGN WITH A NEW ONE.
 04:35:58 IT'S PRETTY AND STRAIGHTFORWARD AND FEW DIRECTIONAL SIGNS
 04:36:02 INTERNAL TO THE PROJECT.
 04:36:04 WE HAVE THE APPLICANT HERE WITH A COLOR BOARD AND A BRIEF
 04:36:09 PowerPoint TO EXPLAIN WHAT THEY ARE GOING TO DO.
 04:36:11 I'LL TURN IT OVER, IF YOU DON'T HAVE ANY QUESTIONS FOR ME,
 04:36:14 TO THE APPLICANT FROM THE SIGN COMPANY.
 04:36:19 >>Howard Levitan: GO AHEAD.
 04:36:21 >>Mary Gibbs: LANCE OIJ.
 04:36:29 >> I JUST HAVE A SAMPLE --

 04:36:34 >>Mary Gibbs: I THOUGHT IT WAS A PowerPoint.
 04:36:35 IT WAS ACTUALLY THE INFORMATION WE PUT IN THE PACKET WITH
 04:36:37 THE APPLICATION THAT SHOWS -- THERE'S A PICTURE THAT SHOWS
 04:36:39 THE OLD BANK COMPARED TO THE NEW BANK -- THE SIGN.
 04:36:46 >> YEAH, WHAT I DID IS I TOOK -- [INAUDIBLE]
 04:36:51 >>Mary Gibbs: YOU HAVE TO MOVE THAT CLOSER TO THE MICROPHONE
 04:36:54 AND THEN STAND -- BECAUSE WE HAVE TO PICK IT UP.
 04:36:57 YOU HAVE TO GET REALLY CLOSE TO THE MICROPHONE AND EXPLAIN
 04:36:59 IT.
 04:37:09 >>Lance Oij: I JUST BLEW UP THE TWO ITEMS THAT I THINK

04:37:13 YOU GUYS ARE CONCERNED WITH.
 04:37:15 THE MONUMENT SIGN AND SHOWING YOU THE COLORS OF THE MONUMENT
 04:37:18 SIGN WITH THE SAMPLES OF COLORS FOR THE MONUMENT, TRIM CAP
 04:37:23 ON THE VERY TOP.
 04:37:25 THIS IS THE SHERWIN WILLIAMS WHITE, WHICH IF YOU LOOK IN THE
 04:37:29 PACKET, YOU'LL SEE THERE'S A BUILDING ELEVATION FOR THE
 04:37:33 BUILDING SIGNAGE.
 04:37:34 AND IN THERE, YOU'LL SEE THAT THE BASE OF THE BUILDING IS
 04:37:38 THIS CONCRETE BLOCK AT THE BOTTOM, WHICH IS A KIND OF TAN
 04:37:41 CONCRETE BLOCK.
 04:37:43 AND THEN THERE'S SOME WHITE ACCENT STRIPES ABOVE THAT.
 04:37:47 THAT'S WHERE THIS IS THE SHERWIN WILLIAMS COLOR ON THE SIDE.
 04:37:51 THE GRAY CLAP, A SLIGHT GRAY, THE TRUIST GRAY.
 04:37:56 THE BACKGROUND, METAL BACKGROUND HAS INDIVIDUAL CHANNEL
 04:38:00 LETTERS MOUNTED TO THE THREE INCH CHANNEL LETTERS MOUNTED --

 04:38:05 THE BACKGROUND WILL NOT LIGHT.
 04:38:09 THE ONLY THING THAT WILL LIGHT ARE THE LETTERS.
 04:38:12 THAT IS THE EXISTING SIGN WHICH IS COMING OUT.
 04:38:16 THE SAME THING WITH THE DIRECTIONALS.
 04:38:18 GOING TO A MONUMENT TYPE SIGN ON THE DIRECTIONAL SIGNS FROM
 04:38:20 A POST SIGN.
 04:38:24 DO YOU HAVE ANY QUESTIONS?
 04:38:31 >>Howard Levitan: I HAVE A QUESTION.
 04:38:34 COULD YOU GO ON THE ELEVATIONS THAT YOU HAVE PRESENTED TO US
 04:38:38 TO THE PICTURE OF THE TRUIST SIGN THAT'S ON THE FACE OF THE
 04:38:45 BUILDING?
 04:38:45 YEAH, RIGHT THERE.
 04:38:53 >> IF YOU LOOK ON THE EXISTING BBT OVER TO THE RIGHT, YOU
 04:38:56 CAN SEE THE BEIGE COLOR ON THE BOTTOM WHICH IS BLOCK, AND
 04:39:00 THEN THERE IS A LIGHT TRIM.
 04:39:02 YOU CAN KIND OF SEE THAT IN BOTH THE OTHER PLACES AND THAT'S
 04:39:05 KIND OF THE BEIGE COLOR OF THE BUILDING.
 04:39:08 >>Howard Levitan: I WOULD LIKE TO ASK, WHAT IS THE RED
 04:39:15 SQUARE THAT SEEMS TO BE ANNOUNCING A TIME OF OPENING ALL
 04:39:21 ABOUT?
 04:39:22 >> THAT'S AN EXISTING BANNER THAT'S UP.
 04:39:25 THERE WILL COME DOWN.
 04:39:26 >>Howard Levitan: THAT WILL COME DOWN.
 04:39:28 >> YES.
 04:39:29 I WAS JUST AT THE SITE AND THE BANNER IS NOT UP THERE NOW.

 04:39:32 WHEN THEY DID THE INITIAL SURVEY, THAT BANNER WAS UP THERE
 04:39:36 FOR THE BB & T, BUT THE BB & T HAS NOW TAKEN THAT DOWN.
 04:39:45 >>Jim Wallace: I HAVE A QUICK QUESTION ON YOUR ELEVATION.
 04:39:47 IT SEEMS TO SHOW CONCRETE BLOCK BASE ON YOUR MONUMENT SIGN,
 04:39:51 BUT IT SHOWS IT JUST AN UNFINISHED CONCRETE BLOCK.
 04:39:56 THE BUILDING OBVIOUSLY IS NOT UNFINISHED CONCRETE BLOCK.

04:39:59 IS THIS GOING TO BE A STUCCO FINISH?
 04:40:04 >> THIS WILL BE LIKE A SPLIT BASED BLOCK -- [INAUDIBLE]
 04:40:14 >>Michael Sheeley: SAME BLOCK ON THE BASE OF THE BUILDING,
 04:40:16 BELOW THAT BASELINE THERE?
 04:40:18 >> YES.
 04:40:20 >>Jim Wallace: AND THE ADDRESS, IS THAT -- IS IT GOING TO
 04:40:25 HAVE LANDSCAPING COVERING?
 04:40:26 I'M CONCERNED THAT THE ADDRESS WILL BE COVERED BY
 04:40:29 LANDSCAPING.
 04:40:30 IT LOOKS LIKE THE ADDRESS IS IN THE BASE, NOT IN THE SIGNAGE
 04:40:36 AREA.
 04:40:38 >>Mary Gibbs: WE CAN'T HEAR.
 04:40:41 >>Tammy Duran: YOU GUYS HAVE TO GET CLOSER TO THE MIKE.
 04:40:45 WE'RE GETTING COMMENTS THAT THEY CAN'T HEAR THE PODIUM OR
 04:40:48 ANYONE.
 04:40:50 >>Mary Gibbs: THE APPLICANT NEEDS TO GET CLOSER.
 04:40:52 I THINK THE QUESTION WAS ABOUT THE HEIGHT OF THE BASE.
 04:40:54 AND ALSO THE STAFF NOTICED, I THINK THAT -- AND WE MENTIONED
 04:40:57 TO THE APPLICANT THE REQUIREMENT IS 24 INCHES FOR THE BASE.

 04:41:01 SO YOU MIGHT NEED TO MAKE THE BASE A LITTLE BIT TALLER.
 04:41:04 >> OKAY, YEAH.
 04:41:05 CURRENTLY, THE BASE OF THE SIGN IS 18 INCHES TALL.
 04:41:08 BASED ON WHAT WAS EXISTING.
 04:41:10 SO KIND OF DUPLICATED THE SAME SIZE AS WHAT WAS EXISTING.
 04:41:14 SO WE CAN INCREASE THE BASE TO 24 INCHES IF THAT'S --
 04:41:18 >>Jim Wallace: 24 INCHES IS A MINIMUM.
 04:41:21 24 TO 36 INCHES.
 04:41:22 MY QUESTION WAS REGARDING THE ADDRESS NUMBERS, I'M JUST
 04:41:27 CONCERNED THAT YOU'RE NOT SHOWING ANY LANDSCAPING THERE.
 04:41:31 I PRESUME THERE WILL BE LANDSCAPING THERE.
 04:41:33 WILL THE LETTERING BE ABOVE THE LANDSCAPING?
 04:41:37 >> YEAH.
 04:41:38 I MEAN, THIS IS THE EXISTING CONDITIONS AS IT SITS RIGHT
 04:41:41 NOW.
 04:41:41 THE LANDSCAPING IS ACTUALLY OVER TO THE LEFT.
 04:41:44 THERE'S LIKE A HEDGE RIGHT HERE.
 04:41:46 I WAS JUST AT THE JOB SITE.
 04:41:48 AND THERE IS A HEDGE RIGHT OVER HERE.
 04:41:49 BUT THIS IS WHERE THE LANDSCAPING IS CURRENTLY.
 04:41:51 IT'S ALL LIKE A -- IT'S ALL LIKE A LOW PROFILE.
 04:41:56 IF YOU WANT US TO MOVE THE ADDRESS TO THIS TOP LEFT-HAND
 04:42:04 CORNER, WE CAN DO THAT ALSO.
 04:42:07 >>Jim Wallace: I DON'T REMEMBER.
 04:42:09 MARY, MAYBE YOU CAN HELP ON THE LAND DEVELOPMENT CODE

 04:42:12 WHETHER IT SPECIFIES WHERE THE ADDRESS MUST BE.
 04:42:15 IS IT PART OF THE SIGNAGE AREA?

04:42:17 >>Mary Gibbs: THE LAND DEVELOPMENT CODE DOESN'T SPECIFY A
 04:42:20 PARTICULAR AREA.
 04:42:21 SO IT CAN BE AT THE BASE AS LONG AS IT'S NOT OBSCURED BY
 04:42:24 LANDSCAPING.
 04:42:26 >>Marlene Naratil: ARE YOU REPAINTING THE ENTIRE BUILDING?
 04:42:30 >> NO.
 04:42:31 WHAT WE'RE CHANGING TO THE BUILDING SIGNAGE FOR THE NEW BANK
 04:42:36 TO WHAT YOU SEE IN THE PICTURE.
 04:42:37 >>Marlene Naratil: YOU'RE ABLE TO GET BY WITH THE CURRENT
 04:42:41 PAINTING --
 04:42:42 >> NO, WE'RE NOT PAINTING THE BUILDING OR ANYTHING LIKE
 04:42:43 THAT.
 04:42:44 THEY TRIED THEIR BEST TO MATCH EVERYTHING THAT'S EXISTING ON
 04:42:47 THE BUILDING.
 04:42:49 >>Mary Gibbs: IF I COULD ADD SOMETHING, THIS IS REALLY HARD
 04:42:51 TO TELL.
 04:42:52 WHEN YOU LOOK AT THIS PICTURE IT LOOKS GRAY, BUT IT'S A
 04:42:55 LIGHT BEIGE.
 04:42:57 IT'S A LIGHT BEIGE.
 04:42:58 IT'S NOT A GRAY COLOR.
 04:42:59 >>Marlene Naratil: AND THE ONE FROM THE BBT LOOKS PURE
 04:43:03 WHITE.
 04:43:03 >>Mary Gibbs: BUT IT'S NOT.

 04:43:07 >>Lance Oij: THIS ONE ACTUALLY HAS A GREAT TRIM IF YOU
 04:43:10 NOTICE AROUND THE EXISTING SIGN, THE CABINET IS GRAY.
 04:43:14 ON THIS EXISTING BB & T SIGN.
 04:43:32 >>Tammy Duran: CHAIRMAN LEVITAN, WERE YOU TALKING?
 04:43:34 YOU WERE MUTED.
 04:43:35 >>Howard Levitan: SORRY.
 04:43:35 I WAS GOING TO ASK WHAT THE COLOR, THE EXACT COLOR.
 04:43:39 I CAN'T TELL FROM THE COLOR BOARD WHAT THE DARK COLOR IS.
 04:43:44 >>Mary Gibbs: RIGHT.
 04:43:44 CAN YOU READ --
 04:43:46 >>Lance Oij: THIS IS THE TRUIST.
 04:43:49 IS THAT THE COLOR YOU'RE LOOKING FOR?
 04:43:51 >>Howard Levitan: YES.
 04:43:54 >>Lance Oij: IT'S A DEEP PURPLE.
 04:43:58 >>Mary Gibbs: DOES IT HAVE A SHERWIN WILLIAMS NUMBER ON
 04:44:02 THERE?
 04:44:03 >>Lance Oij: NO, THIS DOESN'T.
 04:44:06 THAT IS A METAL BACKGROUND THAT WILL BE PAINTED.
 04:44:10 THAT'S WHY THIS IS A METAL BACKGROUND HERE.
 04:44:12 AND THEN THIS IS THE GRAY TOP.
 04:44:15 WHEN YOU PRINT STUFF, THIS SEEMS SO MUCH GRAYER THAN THAT.
 04:44:19 IT'S PRETTY LIGHT GRAY.
 04:44:21 >>Mary Gibbs: THE COLOR LOOKS IN PERSON LIKE A DEEP, DEEP
 04:44:24 ROYAL BLUE WITH A LITTLE BIT OF PURPLISH IN IT.

04:44:28 >>Howard Levitan: ANTHONY, YOU HAD ASKED TO SPEAK?

04:44:31 >>Anthony Gargano: YEAH, I HAD A QUESTION FOR STAFF.
 04:44:34 UNDER THE NEW CODE, IS THIS SOMETHING THAT COULD HAVE BEEN
 04:44:37 HANDLED ADMINISTRATIVELY?
 04:44:40 >>Mary Gibbs: NO.
 04:44:41 ON MONUMENT SIGNS, WHAT WE DID IN THE NEW CODE IS THAT THE
 04:44:44 BOARD STILL WANTED TO LOOK AT THE MONUMENT SIGNS, BUT WE CUT
 04:44:47 OUT -- BEFORE YOU HAD TO DO A PUBLIC INFORMATION MEETING.
 04:44:50 THEN YOU HAD TO COME BACK AND DO A PUBLIC HEARING.
 04:44:52 SO ANY MONUMENT SIGN NOW REQUIRES A PUBLIC HEARING, BUT IT'S
 04:44:58 JUST ONE INSTEAD OF TWO MEETINGS.
 04:45:00 WE STILL LEFT IT WITHIN THE PURVIEW OF THIS BOARD TO APPROVE
 04:45:02 IT.
 04:45:04 >>Anthony Gargano: OKAY.
 04:45:04 THANK YOU.
 04:45:09 >>Mary Gibbs: UNLESS YOU WANT TO GIVE US AUTHORITY TO DO
 04:45:10 THAT FROM NOW ON, WE CAN.
 04:45:13 >>Howard Levitan: I DON'T THINK WE CAN CHANGE THE LAND
 04:45:16 DEVELOPMENT CODE OURSELVES.
 04:45:19 >>Mary Gibbs: IT WAS A JOKE.
 04:45:20 I WANTED TO MAKE SURE NANCY WAS PAYING ATTENTION.
 04:45:24 >>Howard Levitan: I THINK SHE'S GOT IT.
 04:45:26 DOES ANYBODY ELSE HAVE ANY QUESTIONS OF THE APPLICANT?
 04:45:29 IS THERE -- DO YOU HAVE ANY CARDS, MADAM CLERK, ON THIS ONE?
 04:45:34 >>Tammy Duran: NO, I DO NOT.
 04:45:35 >>Howard Levitan: DOES ANYBODY FROM THE PUBLIC WISH TO SPEAK

04:45:39 ABOUT THE TRUIST MONUMENT SIGN -- TRUIST BANK MONUMENT SIGN?
 04:45:44 HEARING NONE, I WILL ACCEPT A MOTION TO APPROVE THIS SIGN.
 04:45:48 >>Marlene Naratil: I'LL MAKE THAT MOTION.
 04:45:51 >>James Tatoes: I'LL SECOND IT.
 04:45:52 >>Howard Levitan: ALL IN FAVOR?
 04:45:53 WHY DON'T YOU CALL THE ROLL, BECAUSE IT'S A QUASI-JUDICIAL
 04:45:58 HEARING.
 04:45:59 MADAM CLERK, CALL THE ROLL.
 04:46:02 >>Anthony Gargano: YES.
 04:46:03 >>Kristin Jeannin: YES.
 04:46:06 >>Barry Jones: YES.
 04:46:08 >>Marlene Naratil: YES.
 04:46:09 >>Michael Sheeley: YES.
 04:46:11 >>James Tatoes: YES.
 04:46:13 >>Jim Wallace: YES.
 04:46:16 >>Howard Levitan: YES.
 04:46:17 >>Scotty Wood: YES.
 04:46:22 >>Howard Levitan: OKAY.
 04:46:22 THANK YOU.
 04:46:23 WE'LL GO TO THE NEXT HEARING ON CHRIST COMMUNITY MINISTRIES

04:46:31 DEVELOPMENT ORDER.
 04:46:34 AND THE SAME RULES APPLY.
 04:46:38 HAS ANYBODY HAD ANY EX PARTE COMMUNICATION WITH RESPECT TO
 04:46:41 THIS MATTER?
 04:46:43 >> NO.

 04:46:44 >> NO.
 04:46:44 >>Howard Levitan: NO.
 04:46:45 AND DOES ANYBODY HAVE ANY CONFLICTS OF INTEREST THEY WOULD
 04:46:48 LIKE TO DECLARE?
 04:46:50 >> NO.
 04:46:51 >> NO.
 04:46:51 >>Howard Levitan: NO.
 04:46:52 OKAY.
 04:46:52 MARY, WOULD YOU LIKE TO INTRODUCE THE MATTER?
 04:46:57 >>Mary Gibbs: THIS IS A DEVELOPMENT ORDER FOR A CHURCH
 04:47:06 EXPANSION PROJECT, AND IT'S LOCATED ON HIGHLANDS AVENUE, SO
 04:47:09 IT'S OFF OF U.S. 41.
 04:47:11 IF YOU'RE DRIVING DOWN U.S. 41, YOU KNOW WHERE SUNNY GROVE
 04:47:15 MOBILE HOME PARK IS IT'S ACROSS THE STREET FROM THAT AND
 04:47:18 JUST SET BACK OFF THE ROAD.
 04:47:20 THE APPLICANT IS ASKING FOR A DEVELOPMENT ORDER.
 04:47:23 WHAT THEY WANT TO DO, THERE'S AN OLDER CHURCH THAT WAS BUILT
 04:47:27 SOME YEARS AGO.
 04:47:28 THEY WANT TO APPROXIMATELY DOUBLE THE SIZE BY ADDING 3,000
 04:47:31 SQUARE FEET.
 04:47:32 THEY ARE GOING TO REMOVE A COUPLE OF MODULARS AND THEN
 04:47:34 EXPAND THE CHURCH.
 04:47:37 THIS WAS ACQUIRED THROUGH A LAND EXCHANGE AND A PROPERTY
 04:47:44 TRANSACTION WITH THE VILLAGE OF ESTERO.
 04:47:45 THE VILLAGE PURCHASED 62 ACRES AT THE CORNER OF CORKSCREW

 04:47:48 AND 41 THAT EXTENDED UP TO THIS HIGHLANDS AVENUE PROPERTY.
 04:47:51 AND THIS PIECE OF PROPERTY WAS EXCHANGED WITH PASTOR
 04:47:54 GOODMAN, A TRANSACTION IN JANUARY.
 04:47:57 AS PART OF THAT TRANSACTION, THEY HAVE BEEN HOLDING SERVICES
 04:48:00 AT THE CHURCH.
 04:48:02 SO NOW THAT THEY OWN THE PROPERTY, THEY WANT TO EXPAND THE
 04:48:06 CHURCH.
 04:48:06 AND THERE WAS A PUBLIC INFORMATION MEETING THAT WAS HELD
 04:48:09 SOME TIME AGO, BUT IT WAS WITH THE OLD DESIGN REVIEW BOARD.
 04:48:12 SO SOME OF YOU HAVE SEEN THIS BEFORE IN THE INFORMATION
 04:48:16 MEETING.
 04:48:16 AT THE TIME, I DON'T THINK THERE WERE TOO MANY COMMENTS.
 04:48:19 THERE WERE A COUPLE ABOUT ARCHITECTURE, I THINK.
 04:48:22 SO TONIGHT, THEY ARE JUST GOING TO EXPLAIN WHAT THEY ARE
 04:48:27 DOING.
 04:48:28 THE STYLE IS OLD FLORIDA.

04:48:30 WHAT THIS IS EXISTING, PRETTY NONDESCRIPT, BASICALLY NO
 04:48:34 STYLE AT ALL.
 04:48:35 SO THEY HAVE DONE SOME WORK WITH THE ARCHITECTURE TO MAKE IT
 04:48:39 OLD FLORIDA.
 04:48:40 AND THEN THE OTHER ISSUE I WANTED TO BRING UP BEFORE I TURN
 04:48:42 IT OVER TO THE APPLICANT IS THAT THEY WILL BE USING A SEPTIC
 04:48:46 TANK, WHICH IS WHAT IS IN USE NOW AND IS ALLOWED BY THE
 04:48:49 HEALTH DEPARTMENT.
 04:48:49 AT SOME POINT -- AND THEY ARE AWARE OF THIS -- THERE WILL

 04:48:52 PROBABLY BE SOME TYPE OF SEWER SERVICE OUT IN THAT AREA,
 04:48:57 BECAUSE THE VILLAGE HAS LOOKED AT SEVERAL AREAS THEY WANT TO
 04:48:59 BRING SEWER INTO AT SOME POINT.
 04:49:01 SO WE MAY PUT A STIPULATION IN THE DEVELOPMENT ORDER THAT AT
 04:49:05 SOME TIME IN THE FUTURE THEY MAY NEED TO CONNECT.
 04:49:08 BUT AT THIS POINT, THERE IS NO SEWER SERVICE IN THIS AREA.
 04:49:11 SO THEY ARE NOT ABLE TO.
 04:49:12 SO I'M HAPPY -- IF YOU DON'T HAVE ANY QUESTIONS, I'LL TURN
 04:49:15 IT OVER TO THE APPLICANT ENGINEER.
 04:49:17 DEAN MARTIN IS GOING TO KICK IT OFF.
 04:49:24 >>Howard Levitan: I WOULD LIKE TO ASK THE BOARD TO HOLD
 04:49:26 THEIR QUESTIONS UNTIL THE APPLICANT HAS FINISHED THE
 04:49:29 PRESENTATION AND THEN WE WILL HAVE MARY'S PRESENTATION, AND
 04:49:32 THEN WE WILL OPEN IT UP TO THE PUBLIC, AND THEN THE BOARD
 04:49:36 CAN WEIGH IN.
 04:49:37 PLEASE GO AHEAD.
 04:50:20 >>Dean Martin: GOOD AFTERNOON.
 04:50:20 DEAN MARTIN WITH TDM CONSULTING.
 04:50:23 WE HAVE SOME OTHER TEAM MEMBERS HERE AS WELL.
 04:50:25 THE PASTOR IS HERE FOR THE CHURCH AND ROBERT MASSENGALE, THE
 04:50:29 ARCHITECT, AND DAVID KULSVEEN WITH LANDESCO, THE LANDSCAPE
 04:50:33 ARCHITECT.
 04:50:34 I WANT TO DIVE RIGHT INTO OUR PowerPoint.
 04:50:36 THE FIRST SLIDE IS THE VICINITY MAP WHICH SHOWS THE SITE
 04:50:59 ZOOMED OUT.

 04:51:00 IT'S NORTH OF CORKSCREW AND EAST OF U.S. 41.
 04:51:05 IT'S IN THE BLUE BOX THERE.
 04:51:11 ZOOMED IN, WE HAVE AN AREA LOCATION MAP.
 04:51:15 IT SHOWS EXISTING CHURCH AND THE TRAILERS AND THE PARKING
 04:51:19 LOT, AND THE NORTHERN END IS VACANT.
 04:51:23 THEN WE'VE GOT A FEW VIEWS OF THE EXISTING CHURCH.
 04:51:31 YOU CAN SEE THAT THE TRAILERS ARE BEHIND THE CHURCH ON THE
 04:51:36 WEST, AND THE CHURCH REALLY HAS NO ARCHITECTURAL DESIGN
 04:51:41 ELEMENTS CURRENTLY.
 04:51:42 DIFFERENT VIEW.
 04:51:46 IT DOES SHOW THE ACCESS ONTO THE COUNTY ROAD, WHICH WILL BE
 04:51:54 ELIMINATED DURING THIS PROCESS.

04:51:56 THE WEST VIEW.
 04:52:06 WE'VE GOT OUR BOUNDARY SURVEY.
 04:52:08 IT'S KIND OF CRISSCROSSED WITH EASEMENTS THAT HAVE BEEN
 04:52:12 VACATED.
 04:52:13 SO ALL THOSE EASEMENTS HAVE BEEN VACATED ON THE SURVEY.
 04:52:16 THIS IS OUR SITE PLAN.
 04:52:22 IT SHOWS THE EXPANDED BUILDING, EXPANDED PARKING WITH GRASS
 04:52:27 SPACES AND A SECOND DRIVEWAY OFF OF HIGHLANDS.
 04:52:31 IT ALSO SHOWS A DRIVEWAY OFF ESTERO COURT.
 04:52:34 SO WE HAVE THREE DRIVEWAYS PROPOSED.
 04:52:36 AND WE ALSO SHOW A PUBLIC AREA WITH BENCHES AND PLANTERS
 04:52:41 SOUTH OF THE BUILDING, WHICH, AGAIN, IS PER THE VILLAGE
 04:52:45 CODE.

04:52:49 THIS SLIDE SHOWS THE PRE- AND POST-DEVELOPMENT AREAS.
 04:52:57 OF COURSE, WE'RE ADDING IMPERVIOUS.
 04:53:01 IT'S REALLY ALL BUILDING AND GRASS PARK.
 04:53:05 EVERYTHING ELSE IS REMAINING THE SAME.
 04:53:08 THIS SHOWS OUR PARKING REQUIREMENTS THAT WE DO MEET THOSE.
 04:53:20 WE NEEDED 83.
 04:53:21 WE HAVE 84 PROPOSED AND 42 OF THOSE ARE GRASS.
 04:53:27 PAVING, GRADING, AND DRAINAGE.
 04:53:30 ALL THE STORMWATER RUNOFF IS COLLECTED IN CULVERTS CONVEYED
 04:53:35 TO THE DRY DETENTION AREA IN THE NORTH.
 04:53:39 IT'S ONE AND A HALF FOOT DEEP BUT IT'S DESIGNED TO BE DRY
 04:53:42 FOR 24 HOURS.
 04:53:43 STORMWATER CALCULATIONS, REQUIRED 8447 CUBIC FEET.
 04:53:57 WE PROVIDED ALMOST 32,000 CUBIC FEET.
 04:54:00 ALL THE EXTRA WAS AN ATTEMPT TO KEEP THE PEAK STAGES DOWN SO
 04:54:05 THE BUILDING AND THE PARKING LOT WON'T FLOOD BECAUSE WE HAD
 04:54:08 EXISTING CONDITIONS WE HAD TO WORK WITH.
 04:54:10 WE COULDN'T RAZE THE BUILDING.
 04:54:13 WE HAD TO KEEP THE BUILDING ELEVATIONS THE WAY THEY WERE.
 04:54:15 SO I WANTED TO GIVE AS MUCH DETENTION VOLUME I COULD IN AN
 04:54:20 ATTEMPT TO MAKE SURE IT DOESN'T FLOOD IN THE FUTURE.
 04:54:22 FIRE FLOW CALCULATIONS.
 04:54:29 WE ARE SPRINKLING THE BUILDING AT PROPOSED EXPANSION AND
 04:54:32 EXISTING BUILDING.
 04:54:33 WE'LL BRING IN A FIRE LINE OFF OF THE EXISTING WATER MAIN
 04:54:36 OFF OF ESTERO COURT.
 04:54:38 UTILITY PLAN, WE'RE USING EXISTING POTABLE WATER SERVICE OFF
 04:54:47 ESTERO COURT, WHICH IS UP HERE.
 04:54:49 AS MARY SAID BEFORE, WE'RE USING EXISTING SEPTIC SYSTEMS.
 04:54:53 THERE ARE THREE.
 04:54:54 TWO HERE ON THE SOUTHWEST CORNER AND ONE KIND OF IN THE
 04:54:58 SOUTH MIDDLE QUADRANT.
 04:54:59 EXISTING SYSTEMS.

04:55:01 LIGHTING PLAN.
 04:55:09 WE ARE PROPOSING THE UPGRADED LIGHT POLES AND FIXTURES AS
 04:55:12 REQUIRED BY THE VILLAGE, WHICH SHOWS ON THIS PLAN.
 04:55:16 AND THE TRAFFIC STUDY, AS YOU CAN SEE, WE'RE PROPOSING 133
 04:55:29 PEAK TRIPS ON SUNDAY, WHICH THIS IS A CHURCH.
 04:55:33 THAT'S WHERE THE PEAK TRIPS ARE.
 04:55:34 AND THEY ARE ALLOCATED TO EACH OF THE THREE DRIVEWAYS ON
 04:55:37 THIS SCREEN AND SHOWS THAT WE DON'T TRIP ANY TURN LANE
 04:55:42 THRESHOLDS.
 04:55:44 WITH THAT, I WILL TURN IT OVER TO ROBERT.
 04:55:56 >>Robert Massengale: GOOD AFTERNOON.
 04:56:01 MY NAME IS ROBERT MASSENGALE.
 04:56:04 I'M AN ARCHITECT.
 04:56:06 BEEN WORKING IN SOUTHWEST FLORIDA SINCE 1989, AND I'VE DONE
 04:56:09 A LOT OF CHURCH DESIGN.
 04:56:10 SO I WANT TO TALK ABOUT THIS PROJECT.
 04:56:16 THE UPPER DRAWING INDICATES THE EAST SIDE OF THE BUILDING,

 04:56:21 WHICH WOULD BE MAINLY THE MAIN ENTRANCE.
 04:56:25 THE PORTION TO THE LEFT IS THE EXISTING BUILDING.
 04:56:30 IT'S MARRIED TO THE NEW SANCTUARY WITH A LARGE OPEN FOYER,
 04:56:36 TWO-STORY SPACE, AND THEN THE NEW SANCTUARY WOULD THEN BE TO
 04:56:41 THE NORTH OR ON THE RIGHT SIDE OF THAT UPPER DRAWING.
 04:56:46 THE LOWER DRAWING IS THE WEST SIDE.
 04:56:52 THERE IS A SINGLE-STORY AREA OF OFFICES ON THE NORTH SIDE
 04:56:57 ADJACENT TO THE SANCTUARY.
 04:56:59 AGAIN, THE FOYER SPACE WITH ANOTHER ENTRANCE ON THE WEST
 04:57:04 SIDE, AND THEN THE EXISTING BUILDING THAT WE'RE TRYING TO
 04:57:10 MAKE LOOK MUCH BETTER THAN IT DOES NOW.
 04:57:13 SO THE EXISTING BUILDING IS VERY NONDESCRIPT, AND WE'RE NOT
 04:57:23 GOING TO KEEP ANY OF IT OTHER THAN MAYBE SOME OF THE
 04:57:28 WINDOWS.
 04:57:28 THIS IS THE FLOOR PLAN FOR THE BUILDING.
 04:57:33 AGAIN, THE AREA THAT SHOWS THE CLASSROOMS WOULD BE THE
 04:57:36 EXISTING BUILDING.
 04:57:37 THE FOYER IS SEPARATING CLASSROOMS FROM THE SANCTUARY, AND
 04:57:45 THEN THE OFFICES ARE TO THE WEST OR THE TOP SIDE OF THAT
 04:57:49 PLAN.
 04:57:49 USING AN OLD FLORIDA-STYLE, WE'LL BE USING HORIZONTAL HARDIE
 04:57:57 BOARD SIDING, METAL ROOFING, WINDOWS.
 04:58:05 WE'RE EVEN -- THE WINDOWS THAT ARE SHOWN AT THE SANCTUARY DO
 04:58:10 NOT TRANSMIT LIGHT INTO THE BUILDING.
 04:58:13 THEY WOULD BE FAUX WINDOWS AT THIS POINT.

 04:58:15 IT WAS SUGGESTED THAT WE ADD THOSE TO THIS RENDITION.
 04:58:24 AND THEN KEEPING THOSE GABLE ENDS AND CREATING SOME OTHER
 04:58:30 ELEMENTS THAT WOULD MIMIC THE ENTRY, OPEN TRUSS AREAS ON
 04:58:35 EITHER END, THE NORTH AND THE SOUTH, TO KIND OF TONE DOWN

04:58:39 THOSE LARGE GABLES THAT ARE EXISTING.
 04:58:46 WE CAN TALK ABOUT QUESTIONS LATER.
 04:59:07 >> HELLO.
 04:59:09 MY NAME IS DAVID KULSVEEN WITH LANDESCO LANDSCAPE
 04:59:12 ARCHITECTURE.
 04:59:12 WE TRIED TO GO ALONG WITH THE OLD FLORIDA THEME, KEEPING IT
 04:59:22 MOSTLY NATIVE WITH THE LANDSCAPING.
 04:59:27 A LOT OF THE PLANTS ARE NATIVE AND DROUGHT TOLERANT PLANTS.
 04:59:33 FIND THEM MOST PLACES, MOST LANDSCAPES HERE IN SOUTHWEST
 04:59:38 FLORIDA.
 04:59:38 AS FAR AS THE CODE REQUIREMENTS, IT'S PRETTY SPOT ON.
 04:59:45 103 TREES WE'RE REQUIRED.
 04:59:48 103 WERE PROVIDED.
 04:59:51 1,044 SHRUBS ARE REQUIRED.
 04:59:54 30 MORE SHRUBS WERE PROVIDED THAN REQUIRED, AND THE
 04:59:59 LANDSCAPE AREA WAS PRETTY MUCH SPOT ON.
 05:00:03 A COUPLE HUNDRED EXTRA SQUARE FEET.
 05:00:06 WE MET ALL THE BUFFER REQUIREMENTS ON THE NORTH.
 05:00:10 THERE IS A TYPE A THAT REQUIRES FIVE TREES PER HUNDRED
 05:00:16 LINEAR FEET.
 05:00:17 ACTUALLY, IT'S FIVE FOOT WIDE.

 05:00:19 THAT REQUIRES FOUR PER HUNDRED LINEAR FEET.
 05:00:22 AND ON THE EAST, WEST, AND SOUTH, IT IS A TYPE D BUFFER,
 05:00:29 20-FOOT WIDE.
 05:00:33 IT CALLS FOR TEN TREES AND DOUBLE STAGGERED HEDGEROW FOR
 05:00:36 HUNDRED LINEAR FEET.
 05:00:37 THE PARKING LOT REQUIREMENTS, WE'VE MET THOSE WITH THE
 05:00:44 PIGEON PLUMS AND SABAL PALMS AND A COUPLE OF OTHER NATIVES
 05:00:50 LIKE ORANGE GEIGER.
 05:00:53 AND AS FAR AS THE GENERAL TREE REQUIREMENTS, 28 TREES
 05:00:59 REQUIRED AND PROVIDED, AND THERE WAS ONE TREE THAT IS BEING
 05:01:03 RETAINED.
 05:01:04 IT'S A LIVE OAK.
 05:01:05 IT'S CONSIDERED A HERITAGE TREE.
 05:01:08 20-INCH CALIPER OR GREATER AT DBH, OR DIAMETER BREAST
 05:01:13 HEIGHT, MEASURED FOUR AND A HALF FEET UP THE TRUNK.
 05:01:16 HERE'S A LITTLE LOOK AT SOME SNAPSHOTS OF THE TREES.
 05:01:22 YOU HAVE THE ORANGE GEIGER.
 05:01:24 IT GIVES A NICE DEEP GREEN COLOR.
 05:01:26 IT IS A SMALLER STYLE TREE.
 05:01:28 IT'S GOT REALLY NICE ORANGE BLOOMS.
 05:01:32 YOU HAVE A SHADY LADY.
 05:01:33 IT PRODUCES A LOT OF SHADE.
 05:01:35 IT'S ALSO KIND OF CONSIDERED A MEDIUM TREE.
 05:01:37 THE PIGEON PLUM, THAT'S ANOTHER NATIVE, SMALLER MEDIUM-SIZED
 05:01:44 TREE.

05:01:44 ACTUALLY GETS KIND OF LARGE IN TIME, BUT TAKES A WHILE.
 05:01:48 THE SWEETBAY MAGNOLIA HAS NICE BLOOMS OCCASIONALLY.
 05:01:53 IT'S MORE -- WE'VE USED IT IN A WAY TO, IN THE WETTER AREAS,
 05:01:58 LIKE THE FRINGE OR EVEN DOWN THE BASE OR THE BOTTOM OF THE
 05:02:01 DRY DETENTION AREA.
 05:02:03 IT CAN TAKE OCCASIONAL FLOODING AND DOES WELL WITH THE
 05:02:08 ABILITY TO EXPAND ITS ROOTS.
 05:02:10 THE CABBAGE PALM OR SABAL PALM, YOU KNOW WHAT THOSE ARE.
 05:02:17 CRAPE MYRTLE HAS NICE BLOOMS LIKE THE NATCHEZ AND MUSKOGEE.
 05:02:23 IT'S A PURPLISH OR A FUCHSIA-COLORED FLOWER AND A WHITE ONE
 05:02:28 FOR THE NATCHEZ.
 05:02:30 SLASH PINE AND THEN THE LIVE OAK.
 05:02:34 WE DID PROPOSE, WE HAD THAT EXISTING, ACTUALLY.
 05:02:37 WE'LL MOVE ON TO THE SHRUBS.
 05:02:42 RED TIP COCOPLUM, WE USED A LOT OF THESE SHRUBS IN MASSINGS
 05:02:48 AND WE TRIED TO STAGGER THEM OR TIER THEM BASED ON THEIR
 05:02:53 SIZE, LIKE IN THE ENTRANCES.
 05:02:55 YOU'LL HAVE THE PARSON'S JUNIPER AND THE -- I DON'T SEE IT
 05:03:02 IN ON HERE.
 05:03:03 EMERALD BLANKET OR NETTLE PLUM.
 05:03:08 WE HAVE COLOR IN THERE, DIFFERENT TIMES OF THE YEAR.
 05:03:11 YOU HAVE THE ORANGE BIRD OF PARADISE PRODUCES THESE NICE
 05:03:16 BLOOMS.
 05:03:16 THEY SAY ARE ALSO USED IN MASSINGS, FLANKED BY SOME OF THE
 05:03:21 MUHLY GRASS WHICH WOULD GO NICE TOGETHER WITH THE ORANGE

 05:03:25 TONES OF THE ORANGES BIRD OF PARADISE.
 05:03:28 AND USED A LARGE MASSING OF THIS ON THE CORNER, THE
 05:03:31 SOUTHWEST CORNER RIGHT HERE.
 05:03:34 IT'S KIND OF OLD FLORIDA-STYLE LOOK BUT A LITTLE UPGRADED
 05:03:38 WITH THE SILVER.
 05:03:39 YOU CAN SEE IT HERE IN THE SOUTHWEST CORNER.
 05:03:41 AND THEN FLORATAM GRASS, WHICH YOU COULD ALSO GO WITH BAHIA.
 05:03:56 IT'S MORE DROUGHT TOLERANT.
 05:03:59 THE EXISTING TREE SURVEY WE DID, WE RAN INTO A LOT OF
 05:04:06 STRANGLER FIGS.
 05:04:07 THEY KIND OF GREW OVER SOME OLD SABAL PALMS, AND MOST OF
 05:04:12 THOSE YOU'LL SEE HERE IN YELLOW, IF YOU CAN SEE THAT, I
 05:04:16 DON'T KNOW IF I CAN ZOOM IN.
 05:04:19 YOU CAN SEE THERE'S QUITE A FEW OF THEM.
 05:04:22 THEN THE LIVE OAK WAS DOWN HERE AT THE CORNER, THE SOUTHWEST
 05:04:25 CORNER OF THIS EXISTING BUILDING TO BE REMOVED, WHICH WILL
 05:04:31 BE THE ONLY ONE THAT'S BEING RETAINED OR PROPOSED TO BE
 05:04:34 RETAINED BECAUSE MOST OF THIS -- MOST OF THESE TREE ROOT
 05:04:40 SYSTEMS WILL BE DESTROYED DURING THE DEVELOPMENT PROCESS,
 05:04:44 EITHER DUE TO THE PROPOSED BUILDING LOCATION OR THE PARKING
 05:04:49 OR THE CURBING AND SIDEWALKS THAT ARE NEARBY THAT ARE
 05:04:53 DEMOLITION, THAT WE'LL NEED TO REMOVE SOME OLD SIDEWALKS.

05:04:57 THAT MAY BE THE END OR IT MAY BE FROZEN.
 05:05:07 I'M NOT SURE.
 05:05:08 THAT'S THE END.

05:05:16 WITH THAT, I GUESS WE'LL TURN IT OVER TO QUESTIONS.
 05:05:19 ANYBODY HAVE ANY FOR ME WHILE I'M UP HERE?
 05:05:25 >>Howard Levitan: IS THE PRESENTATION DONE?
 05:05:29 >>David Kulsveen: YES, IT IS.
 05:05:31 >>Howard Levitan: I'LL ASK THE BOARD, DO YOU HAVE ANY
 05:05:33 QUESTIONS AT THIS POINT IN TIME OF THE APPLICANT?
 05:05:39 >>Michael Sheeley: I HAVE A QUESTION FOR THE ARCHITECT.
 05:05:42 >>Howard Levitan: GO AHEAD, MICHAEL.
 05:05:50 >>Robert Massengale: YES, SIR.
 05:05:53 >>Michael Sheeley: IF YOU CAN GO BACK TO YOUR 3D VIEW THERE.
 05:06:21 >>Robert Massengale: ARE YOU DOING IT OR AM I DOING IT?
 05:06:26 >>Michael Sheeley: CAN YOU TELL US WHERE YOU'RE USING THOSE
 05:06:28 PARTICULAR COLORS ON THE BUILDING?
 05:06:31 BECAUSE THEY ARE NOT SHOWN AS TO WHAT GOES WHERE.
 05:06:34 >>Robert Massengale: THE RELIABLE WHITE IS THE MAIN BODY OF
 05:06:37 THE WALLS.
 05:06:39 THE SAND DUNE WOULD BE THE BASE.
 05:06:50 AND THE NUTHATCH IS THE DARKEST PART, WHICH WOULD BE THE
 05:06:55 VERY BOTTOM OF THE BASE.
 05:06:59 SOME OF THE MAYBE WOOD TRIM.
 05:07:01 THE NORTH END BETWEEN THOSE FOUR COLUMNS WOULD BE THE DARK
 05:07:07 NUTHATCH.
 05:07:09 >>Michael Sheeley: SO THE BASE IS SAND DUNE OR NUTHATCH?
 05:07:13 >>Robert Massengale: I THINK IT'S BOTH WHEN I LOOK AT IT.
 05:07:16 >>Michael Sheeley: TWO DIFFERENT COLORS.

05:07:17 >>Robert Massengale: YEAH, THERE'S A SEPARATION, IF YOU LOOK
 05:07:19 AT THE ARCHITECTURAL ELEVATION.
 05:07:23 >>Michael Sheeley: OKAY.
 05:07:24 THE OTHER QUESTION I HAVE IS YOUR EXPOSED WOOD TRUSSES THAT
 05:07:28 YOU'RE DOING AT THE ENTRANCES, DO THOSE ALSO APPEAR THROUGH
 05:07:30 THE LENGTH OF YOUR FOYER?
 05:07:32 >>Robert Massengale: WE HAVEN'T MADE -- THEY REPEAT WITHIN
 05:07:38 THE EXTERIOR PART.
 05:07:39 WE HAVEN'T MADE THE DETERMINATION YET WHAT WE'RE GOING TO DO
 05:07:42 ON THE INTERIOR.
 05:07:42 >>Michael Sheeley: JUST A QUESTION.
 05:07:44 JUST A COMMENT.
 05:07:47 I THINK WE DISCUSSED THIS WHEN YOU WERE AT THE DESIGN REVIEW
 05:07:50 BOARD.
 05:07:50 TO TAKE THIS OLD BUILDING, KIND OF NONDESCRIPT BUILDING, AND
 05:07:56 ADD ON TO IT THE WAY YOU HAVE, I THINK YOU'VE DONE A REALLY
 05:08:01 EXCELLENT JOB IN THE WAY YOU HANDLED THE CIRCULATION WITH
 05:08:03 THE CROSS TRANSEPT OF, LET'S SAY, THAT FOYER CONNECTING BOTH

05:08:08 SIDES, ALLOWING YOU TO TIE INTO THE OLD BUILDING AND THEN
 05:08:10 PUT THE NEW BUILDING ON THE OTHER SIDE, AS WELL AS THE
 05:08:14 ENHANCEMENTS YOU DID ON THE EXTERIOR OF THE OLD BUILDING,
 05:08:20 WITH THE HEAVY COLUMNS AND THOSE LITTLE SHED ROOFS AND THEN
 05:08:22 REPEATING THOSE ELEMENTS ON THE NEW PORTIONS OF THE BUILDING
 05:08:25 REALLY HELPS TO TIE IT ALL TOGETHER.
 05:08:27 I THINK FOR THIS STYLE OF ARCHITECTURE, WHICH ALMOST GOES TO

 05:08:31 A PRAIRIE STYLE TO ME IN SOME WAYS, I THINK YOU'VE DONE A
 05:08:35 VERY NICE JOB.
 05:08:35 >>Robert Massengale: THANK YOU.
 05:08:36 ANY OTHER QUESTIONS?
 05:08:44 >>Marlene Naratil: I WAS WONDERING HOW MANY SERVICES THE
 05:08:46 CHURCH HOLDS ON A SUNDAY.
 05:08:49 >>Robert Massengale: THE SANCTUARY IS SET UP FOR ABOUT 200.
 05:08:54 AND THAT'S PROBABLY ABOUT WHERE THEY WILL STAY.
 05:08:57 SO THERE'S ONE SERVICE.
 05:08:59 >>Marlene Naratil: AND NOTHING IN THE EVENING ON SUNDAYS OR
 05:09:02 --
 05:09:05 >>Robert Massengale: COME ON, MARK.
 05:09:11 >> MARK GOODMAN, I'M THE PASTOR OF THE CHURCH.
 05:09:16 WE DO HAVE WEDNESDAY EVENING BIBLE STUDIES THROUGHOUT THE
 05:09:18 WEEK.
 05:09:18 THERE'S A WOMEN'S GROUP THAT MEETS, VARIOUS PRAYER GROUPS.
 05:09:22 USUALLY SMALLER GROUPS, BETWEEN 20 AND 30 PEOPLE.
 05:09:26 >>Marlene Naratil: DO YOU HAVE SUNDAY SCHOOL ON SUNDAY?
 05:09:30 >>Mark Goodman: CHILDREN'S CHURCH AND NURSERY, YES.
 05:09:34 >>Robert Massengale: THAT'S WHAT THE CLASSROOMS WOULD BE
 05:09:35 THAT WERE ON THE PLAN.
 05:09:37 THOSE WOULD BE THE -- THE CLASSROOMS ARE REALLY FOR THE
 05:09:40 YOUTH AND CHILDREN.
 05:09:42 THE AUDITORIUM.
 05:09:45 THE SANCTUARY WOULD BE FOR THE ADULTS.

 05:09:47 AND THEN, AS MARK INDICATED, DURING THE WEEK FOR SMALLER
 05:09:52 GROUPS, PROBABLY SOME OF THE CLASSROOMS WOULD BE USED OR
 05:09:55 OTHER AREAS.
 05:10:02 >>Jim Wallace: I HAD A QUESTION ON YOUR FLOOR PLAN.
 05:10:05 IT MAY BE JUST BECAUSE I'M LOOKING AT IT AT THIS SCALE.
 05:10:10 THERE AREN'T ANY MEASUREMENTS THERE, BUT THE DOOR SWING AND
 05:10:16 ACCESS SEEMS TO BE A CONFLICT IN YOUR CLASSROOM WASHROOMS,
 05:10:23 IN THE WOMEN'S AREA.
 05:10:25 IT SEEMS LIKE THE DOOR COMING IN --
 05:10:27 >>Robert Massengale: OKAY.
 05:10:28 THE SMALLER TOILET ROOMS THAT ARE AT THE VERY SOUTH END OF
 05:10:31 THE BUILDING ARE EXISTING, AND WE HAD NOT PLANNED TO MAKE
 05:10:34 ANY MODIFICATIONS.
 05:10:36 >>Jim Wallace: THAT WAS MEN?

05:10:39 >>Robert Massengale: THERE'S MEN AND WOMEN AT THE FAR
 05:10:43 LEFT-HAND SIDE OF THE PLAN.
 05:10:45 THOSE ARE EXISTING, AND WE WERE NOT GOING TO MODIFY THEM.
 05:10:48 >>Jim Wallace: ALL OF THOSE WASHROOMS ARE EXISTING?
 05:10:52 >>Robert Massengale: AT THAT SOUTH END OF THE BUILDING.
 05:10:54 THE NEW ONES THAT ARE ADJACENT TO THE FOYER --
 05:10:57 >>Jim Wallace: I SEE, OKAY.
 05:10:58 >>Robert Massengale: -- WOULD BE IN ADDITION TO THOSE.
 05:11:01 >>Jim Wallace: YOU'RE SAYING IN THE EXISTING, THERE IS --
 05:11:05 >>Robert Massengale: THERE COULD BE SOME CONFLICTS.
 05:11:06 THERE ARE, BUT THEY ARE EXISTING.

05:11:09 >>Jim Wallace: I GUESS I WOULD HAVE TO DEFER TO STAFF, BUT
 05:11:11 ARE THEY REQUIRED TO BRING THOSE TO NEW CODE IN THIS
 05:11:15 BUILDING OR CAN THEY JUST LEAVE THEM AS THEY ARE?
 05:11:22 >>Mary Gibbs: THAT'S A GOOD BUILDING CODE QUESTION FOR THE
 05:11:25 BUILDING OFFICIAL TO DECIDE.
 05:11:28 >>Robert Massengale: TYPICALLY CHURCHES ARE EXEMPT FROM THE
 05:11:30 ADA.
 05:11:33 WE PROVIDE AS BEST WE CAN WHEN WE'RE DEALING WITH EXISTING
 05:11:37 CONDITIONS, BUT, OBVIOUSLY, WHEN WE CREATE NEW TOILET ROOMS,
 05:11:40 THOSE WOULD BE COMPLIANT EVEN THOUGH THEY ARE NOT REQUIRED
 05:11:44 TO BE.
 05:11:47 >>Jim Wallace: WHEN YOU DO A MAJOR RENOVATION LIKE THIS, ARE
 05:11:50 YOU NOT REQUIRED TO MEET CODE?
 05:11:52 >>Robert Massengale: A CHURCH IS NOT REQUIRED TO MEET THE
 05:11:55 REQUIREMENTS OF THE ADA.
 05:11:59 >>Jim Wallace: WELL, THIS ISN'T JUST ADA WHEN I HAVE TWO
 05:12:02 DOORS THAT DO THIS.
 05:12:03 THAT'S MORE THAN ADA.
 05:12:04 MY SECOND QUESTION -- ANYWAY, JUST A NOTATION THAT SEEMED TO
 05:12:09 ME, IT MAY BE AN EXISTING CONDITION, BUT OBVIOUSLY IT'S A
 05:12:12 CONFLICT.
 05:12:12 THE OTHER THING WAS ON THE RESOURCE ROOM, WAS THAT A
 05:12:18 LIBRARY?
 05:12:18 WHAT IS THAT EXACTLY?
 05:12:20 >>Robert Massengale: ON THE WHERE?

05:12:22 >>Jim Wallace: THE RESOURCE ROOM.
 05:12:24 >>Robert Massengale: THE RESOURCE ROOM WOULD BE WHERE
 05:12:26 TEACHING MATERIALS WOULD BE KEPT TO BE PUT TO THE
 05:12:31 CLASSROOMS.
 05:12:34 THE TEACHERS ON SUNDAY MORNING WOULD KEEP THEIR MATERIALS
 05:12:37 THERE.
 05:12:37 >>Jim Wallace: -- FIRE EXIT THAT IT EXITS INTO ANOTHER ROOM
 05:12:40 WHICH EXITS INTO -- I BRING IT UP.
 05:12:43 >>Robert Massengale: AND IF THAT COMES UP IN BUILDING, THEN
 05:12:46 WE'LL ADD A DOORWAY TO THE HALLWAY.

05:12:48 I SAID IF THAT COMES UP, WE CAN ADD A DOORWAY TO THE
 05:12:52 HALLWAY.
 05:12:53 BUT ONCE AGAIN, WE'RE TRYING TO SECURE THAT INFORMATION SO
 05:12:58 IT'S NOT JUST ACCESSIBLE TO ANYBODY.
 05:13:02 YOU'RE TRYING TO CONTROL WHERE INFORMATION GOES AND WHERE IT
 05:13:05 COMES FROM.
 05:13:05 SO THAT'S WHY THAT'S DONE THAT WAY.
 05:13:08 >>Jim Wallace: I APPRECIATE IT.
 05:13:09 BUT IF IT'S A FIRE RESCUE ISSUE, IT'S LIFE SAFETY FIRST.
 05:13:12 >>Robert Massengale: SURE.
 05:13:14 I AGREE.
 05:13:19 >>Mark Goodman: IT COULD BE COPY MACHINES AND OTHER THINGS
 05:13:21 FOR TEACHER SUPPORT.
 05:13:23 I HAVE A LITTLE BIT OF FIRE CODE AND BUILDING CODE KNOWLEDGE
 05:13:26 BACKGROUND THAT THAT WOULD NOT BE A PROBLEM GOING THROUGH AN

 05:13:29 INTERVENING ROOM TO GET TO THAT CORRIDOR THERE.
 05:13:35 >>Mary Gibbs: I WAS GOING TO MENTION THAT PASTOR GOODMAN IN
 05:13:37 A PRIOR LIFE WAS THE FIRE PLANS EXAMINER FOR THE COUNTY FOR
 05:13:41 YEARS.
 05:13:42 I THINK HE IS THE PASTOR FOR THE FIRE DEPARTMENT NOW.
 05:13:47 HE'S GOT A LOT OF YEARS OF EXPERIENCE OF PICKING PEOPLE
 05:13:49 APART ON FIRE CODES.
 05:13:53 >>Michael Sheeley: I ASPIRED WITH MARK MANY, MANY TIMES 20
 05:13:56 OR 30 YEARS AGO ON PROJECTS.
 05:13:59 >>Robert Massengale: MARK WOULD HAVE POINTED THAT OUT TO ME
 05:14:02 MONTHS AGO IF THAT WERE AN ISSUE FOR HIM.
 05:14:05 >>Howard Levitan: I HAVE A QUESTION ON ZOOM.
 05:14:07 COULD SOMEONE PUT BACK THE COLORED ELEVATIONS?
 05:14:10 THANK YOU.
 05:14:26 IN THE STAFF REPORT, THERE WAS A MENTION OF A REQUEST TO
 05:14:32 CHANGE THE COLOR OF THE METAL ROOFS FROM GRAY TO AN OTHER
 05:14:39 EARTH TONE.
 05:14:40 WHERE ARE WE ON THAT ISSUE?
 05:14:42 >>Robert Massengale: WELL, I WOULD LIKE TO SAY THAT EVEN
 05:14:47 YOUR OWN EXAMPLES OF VERNACULAR ARCHITECTURE USE A
 05:14:51 LIGHT-COLORED ROOF AND WHITE COLOR FOR THE MAJORITY OF THE
 05:14:56 BUILDING.
 05:14:58 >>Mary Gibbs: I RAISED THAT QUESTION WHEN WE WERE REVIEWING
 05:15:01 IT, AND I ASKED JIM HART, WHO IS OUR ENGINEER, TO PASS IT ON
 05:15:05 TO THE APPLICANT.

 05:15:06 BECAUSE WHAT I COULDN'T TELL ALSO WHEN I'M LOOKING AT THIS
 05:15:09 PLAN BECAUSE IT'S SORT OF -- WHEN YOU DO THESE THINGS
 05:15:12 SOMETIMES ON AUTOCAD, IT MAKES THE ROOF LOOK VERY PROMINENT,
 05:15:15 BUT I COULDN'T REALLY TELL IF THE ROOF WAS THAT PROMINENT
 05:15:18 AND IF THIS GRAY WOULD BE LIKE A DOMINATING COLOR.
 05:15:22 >>Robert Massengale: WHAT WE HAD PLANNED WAS IT WAS JUST A

05:15:25 GALVANIZED ALUMINUM LIGHT COLOR LIKE THE MAJORITY OF OLD
 05:15:32 FLORIDA AND VERNACULAR ARCHITECTURE ARE.
 05:15:35 THAT WOULD BE A STANDING SEAM ROOF, NOT A V CRIMP.
 05:15:39 SO IT HAS A LITTLE MORE PROMINENCE TO IT.
 05:15:42 BUT WE PREFER THE LIGHTER COLOR.
 05:15:44 A DARKER COLOR IS GOING TO CREATE MORE ENERGY ISSUES, MAYBE
 05:15:51 CONSUMPTION ISSUES THAN A LIGHT COLOR.
 05:15:53 >>Michael Sheeley: ARE YOU PROPOSING THE GALVALUME OR A
 05:15:56 PAINTED ROOF?
 05:15:57 >>Robert Massengale: NO, A GALVALUME.
 05:15:59 THAT'S WHAT WE WOULD PREFER.
 05:16:00 >>Michael Sheeley: REALLY A SILVER ROOF, WHICH IS MORE
 05:16:02 APPROPRIATE TO THIS VERNACULAR.
 05:16:04 >>Robert Massengale: YES, YES.
 05:16:04 THAT IS OUR PREFERENCE.
 05:16:06 >>Marlene Naratil: ACTUALLY, SINCE YOU HAVE SO MUCH ROOF
 05:16:10 AREA, I THINK THAT WOULD LOOK THE BEST ANYWAY.
 05:16:12 >>Robert Massengale: IF WE DARKENED THE ROOF, IT MAKES IT
 05:16:15 VERY PROMINENT BECAUSE THERE IS QUITE A BIT OF ROOF AREA.

 05:16:20 SO OUR PREFERENCE IS TO REMAIN WITH THAT GALVALUME STANDING
 05:16:26 SEAM, SILVER-COLORED ROOFING.
 05:16:30 >>James Tatoes: WITH SUCH A GREAT AREA OF ROOF, TO GO INTO
 05:16:36 SOME KIND OF RED, I THINK WOULD MAKE THAT THING STANDING
 05:16:39 OUT, UNFORTUNATELY.
 05:16:42 >>Robert Massengale: RED IS NOT A COLOR WE WOULD CHOOSE
 05:16:44 ANYWAY.
 05:16:45 >> LITTLE SATANIC.
 05:16:47 >>Robert Massengale: I DON'T THINK A RED ROOF IS REALLY
 05:16:50 APPROPRIATE FOR A CHURCH MYSELF.
 05:16:54 >>Michael Sheeley: OR MUCH OF ANYTHING ELSE.
 05:16:56 >>Robert Massengale: YOU MAY BE RIGHT.
 05:16:57 >>Michael Sheeley: THE REFLECTIVE COLORS OF THE GALVALUME
 05:17:00 WOULD BE GOOD FOR ENERGY EFFICIENCY.
 05:17:01 >>Robert Massengale: I AGREE.
 05:17:03 >>Jim Wallace: IT MAY JUST BE ME.
 05:17:07 WHEN I LOOK AT THE ELEVATIONS, IT APPEARS A LOT OF THE
 05:17:10 BUILDING IS RELIABLE WHITE.
 05:17:12 AND THEN THERE APPEARS TO BE A CONTRASTING WHITE.
 05:17:15 IF I LOOK AT THE TOP ELEVATION.
 05:17:17 >>Robert Massengale: IT'S THE WAY THIS PROGRAM TRANSMITS
 05:17:21 COLOR.
 05:17:22 IT DOESN'T DO IT TRUE, BECAUSE IT TAKES INTO ACCOUNT SHADING
 05:17:27 AND SHADOWS AND THINGS LIKE THAT.
 05:17:28 THERE'S PROBABLY NOT AS MUCH WHITE AS YOU REALLY THINK THERE

 05:17:33 ARE.
 05:17:33 >>Jim Wallace: IF YOU WOULD LET ME FINISH MY QUESTION, WITH

05:17:36 ALL DUE RESPECT.
 05:17:38 ON THE UPPER ELEVATION, IT APPEARS THAT THE BODY COLOR IS
 05:17:40 THE RELIABLE WHITE.
 05:17:43 THE REASON I ASK THIS IS BECAUSE WE'RE NOT BIG ON PURE
 05:17:47 WHITES.
 05:17:48 WE, MEANING ESTERO.
 05:17:49 AND THE BODY COLOR ON THE UPPER ELEVATION LOOKS LIKE IT IS
 05:17:56 THE RELIABLE WHITE, AND THEN THE COLUMNS AND THE FEATURE ON
 05:18:00 THE MAIN ENTRANCES APPEARS TO BE A PURE WHITE.
 05:18:05 I'M JUST ASKING FOR CLARIFICATION THERE.
 05:18:07 I THINK THERE IS A CONTRAST THERE AND I'M ASKING FOR
 05:18:10 CLARIFICATION ON THE DRAWING.
 05:18:11 >>Robert Massengale: LET ME CLARIFY MY PREVIOUS STATEMENT
 05:18:13 ABOUT COLOR.
 05:18:14 THE SAND DUNE COLOR WOULD BE THE BODY COLOR.
 05:18:20 THE RELIABLE WHITE COLOR, WHICH IS REALLY THE LIGHTER COLOR,
 05:18:24 WOULD BE THAT ACCENT COLOR.
 05:18:26 AND THEN THE NUTHATCH IS THE BASE.
 05:18:30 >>Michael Sheeley: SO THE COLUMNS ARE IN THE RELIABLE WHITE.
 05:18:34 >>Robert Massengale: THE COLUMNS WOULD BE THE RELIABLE
 05:18:38 WHITE.
 05:18:39 >>Jim Wallace: THE BODY COLOR IS THE SAND DUNE.
 05:18:43 >>Robert Massengale: I MISSPOKE EARLIER.

 05:18:44 I WANT TO CLARIFY THAT NOW.
 05:18:49 >>Howard Levitan: REALLY HELPFUL IN FUTURE CASES IF WE HAD
 05:18:52 THESE KIND OF ELEVATIONS WITH NOTES ON THEM AS TO WHAT AREA
 05:18:57 IS WHAT COLOR.
 05:18:59 MARY, IF YOU COULD MAKE THAT HAPPEN.
 05:19:02 >>Mary Gibbs: I WILL.
 05:19:04 I THINK IT WAS ON THE PLANS, BUT IT DIDN'T TRANSPOSE INTO
 05:19:07 THIS.
 05:19:08 SO WE HAD THE SAME QUESTION.
 05:19:10 >>Robert Massengale: THE COLORS MAY NOT HAVE TRANSPOSED INTO
 05:19:14 THIS PRESENTATION, BUT I THINK WE DID DO THAT FOR WHAT WE
 05:19:17 PRESENTED FOR YOUR REVIEW.
 05:19:20 >>Mary Gibbs: WE'LL MAKE SURE WE DO THAT.
 05:19:22 >>Howard Levitan: DOES ANYBODY HAVE ANY OTHER QUESTIONS WITH
 05:19:25 RESPECT TO THE APPLICANT'S PRESENTATION?
 05:19:29 >>Kristin Jeannin: I DO.
 05:19:29 >>Howard Levitan: GO AHEAD.
 05:19:31 >>Kristin Jeannin: CAN YOU GO BACK ONE?
 05:19:33 FIRST, I HAVE A COMMENT AND THEN -- THAT IS THE EXISTING.
 05:19:44 THE NEW ELEVATIONS.
 05:19:45 JUST A COMMENT FOR YOU AND THEN I HAVE A COUPLE OF QUESTIONS
 05:19:52 FOR THE LANDSCAPE ARCHITECT.
 05:19:53 YES.
 05:19:54 SO I JUST WANTED TO SAY I REMEMBER THIS COMING THROUGH

05:19:57 DESIGN REVIEW BOARD, AND I THINK YOU'VE DONE A REALLY NICE

05:20:02 JOB OF ADDRESSING THIS BUILDING IN EVERY DIRECTION, EVEN

05:20:06 THOUGH WE KNOW LIKE PARTS OF IT ARE THE BACK.

05:20:10 YOU CAN'T REALLY TELL AS MUCH AS YOU COULD WHEN IT FIRST

05:20:12 CAME IN.

05:20:13 >>Robert Massengale: THERE'S REALLY NOT A BACK TO THE

05:20:15 BUILDING.

05:20:15 >>Kristin Jeannin: DRIVE AROUND FROM EVERY DIRECTION.

05:20:18 >>Robert Massengale: IT WILL BE SEEN FROM 41.

05:20:21 IT WILL BE SEEN FROM THE STREET TO THE EAST.

05:20:26 >>Kristin Jeannin: THEN I HAVE ONE QUESTION FOR KEVIN, IF HE

05:20:31 WANTS TO COME BACK UP.

05:20:41 >> I'LL ANSWER TO KEVIN.

05:20:43 >>Kristin Jeannin: IS IT NOT?

05:20:44 DAVID.

05:20:45 I'M SORRY.

05:20:45 DAVID.

05:20:46 I APOLOGIZE.

05:20:46 YOU HAVE SHOWN THAT THERE ARE THREE EXISTING LIVE OAKS

05:20:53 ON-SITE.

05:20:54 ARE THE TWO THAT ARE BEING REMOVED, THEY ARE NOT HERITAGE

05:20:59 OAKS?

05:21:03 >>David Kulsveen: THAT'S RIGHT.

05:21:06 >>Kristin Jeannin: A COUPLE OF OTHER MINOR COMMENTS.

05:21:08 I THINK YOU SHOULD TAKE A LOOK AT YOUR PLANT SCHEDULE AND

05:21:11 THE NATIVE STATUS.

05:21:13 I THINK THAT THE PLANT CHOICE, FOR THE MOST PART, ARE PRETTY

05:21:16 GOOD.

05:21:16 I THINK A COUPLE OF THE NATIVES AREN'T CORRECT.

05:21:19 LASTLY, I HAVE A LITTLE BIT OF A CONCERN ABOUT GEIGER TREES.

05:21:26 I JUST SEE THEM NOT PERFORM REAL WELL.

05:21:32 THEY OFTEN COME IN REALLY WEEK AND THEN THEY HAVE A GEIGER

05:21:35 BEETLE ISSUES.

05:21:36 >>David Kulsveen: RIGHT.

05:21:39 >>Kristin Jeannin: TAKE A LOOK AT THAT.

05:21:41 MAYBE NOT SO MANY.

05:21:42 MAYBE MORE OF THE OTHER OPTIONS YOU HAVE ON HERE OR SILVER

05:21:46 BUTTONWOOD IS A GOOD NATIVE TO USE IN PLACE.

05:21:49 THAT'S IT.

05:21:51 >>David Kulsveen: THANK YOU.

05:21:52 >>Howard Levitan: ANY OTHER COMMENTS OR QUESTIONS AT THIS

05:21:55 POINT IN TIME?

05:21:55 QUESTIONS?

05:21:56 IF NOT, MADAM CLERK, DO WE HAVE ANY CARDS ON THIS MATTER?

05:22:03 >>Tammy Duran: NO, WE DO NOT.

05:22:05 >>Howard Levitan: OKAY.

05:22:07 I'M GOING TO CALL ON MARY.
 05:22:11 DO YOU HAVE ANYTHING YOU'D LIKE TO ADD TO THIS?
 05:22:13 >>Mary Gibbs: NO.
 05:22:15 >>Howard Levitan: THANK YOU.
 05:22:15 I'M GOING TO ASK THE PUBLIC IF ANYBODY FROM THE PUBLIC WOULD

 05:22:20 LIKE TO SPEAK ON THIS MATTER.
 05:22:22 HEARING NONE, I'M GOING TO CLOSE THE PUBLIC HEARING AND ASK
 05:22:30 THE BOARD IF THEY WOULD HAVE ANY COMMENTS WITH RESPECT TO
 05:22:33 THIS THAT HAVEN'T ALREADY BEEN MADE.
 05:22:36 HEARING NONE, I WILL ACCEPT A MOTION TO APPROVE THE
 05:22:43 DEVELOPMENT ORDER.
 05:22:44 IS THERE A SECOND?
 05:22:50 >> SECOND.
 05:22:51 >>Howard Levitan: MADAM CLERK, WOULD YOU PLEASE CALL THE
 05:22:55 ROLL.
 05:22:56 >>Anthony Gargano: YES.
 05:22:57 >>Kristin Jeannin: YES.
 05:23:00 >>Barry Jones: YES.
 05:23:01 >>Marlene Naratil: YES.
 05:23:03 >>Michael Sheeley: YES.
 05:23:05 >>James Tatoes: YES.
 05:23:07 >>Jim Wallace: YES.
 05:23:08 >>Howard Levitan: YES.
 05:23:10 >>Scotty Wood: YES.
 05:23:14 >>Howard Levitan: THANK YOU VERY MUCH.
 05:23:15 OKAY.
 05:23:19 LET'S MOVE ON TO THE NEXT SUBJECT, AND I WILL ASK WITH
 05:23:26 RESPECT TO -- THIS IS THE SCHOOL PROJECT ON THREE OAKS, AND
 05:23:32 I WILL ASK THE BOARD IF ANYBODY HAD ANY EX PARTE
 05:23:37 COMMUNICATIONS WITH RESPECT TO THIS MATTER?

 05:23:43 >>Scotty Wood: I'VE HAD E-MAIL EXCHANGE WITH MARY GIBBS.
 05:23:46 >>Howard Levitan: I'VE ALSO HAD E-MAIL AND TELEPHONE CALLS
 05:23:49 WITH NANCY AND MARY.
 05:23:51 WITH RESPECT TO THIS MATTER.
 05:23:56 >>James Tatoes: E-MAILS.
 05:23:59 >>Howard Levitan: ALL THE E-MAILS THAT WE'VE RECEIVED HAVE
 05:24:03 BEEN MADE A PART OF THE RECORD.
 05:24:06 ANYBODY ELSE HAVE ANY EX PARTE COMMUNICATIONS?
 05:24:12 HAS ANYBODY GONE TO THE SITE?
 05:24:13 IF NOT -- GONE TO THE SITE IS PART OF THE EX PARTE
 05:24:20 COMMUNICATION.
 05:24:20 IF NOT, HAS -- DOES ANYBODY WANT TO CLEAR A CONFLICT OF
 05:24:26 INTEREST ON THIS MATTER?
 05:24:28 >> NO.
 05:24:29 >> NO.
 05:24:30 >>Howard Levitan: OKAY.

05:24:30 LET'S MOVE ON.
 05:24:32 MARY, IF YOU WOULD LEAD OFF.
 05:24:36 >>Mary Gibbs: ALL RIGHT.
 05:24:37 THIS IS OUR LAST CASE TONIGHT, AND THIS IS A DEVELOPMENT
 05:24:40 ORDER FOR THE SCHOOL SITE, ELEMENTARY AND MIDDLE COMBINED
 05:24:44 SCHOOL ON THREE OAKS PARKWAY ACROSS FROM COUNTRY CREEK.
 05:24:47 WE'VE BEEN WORKING ON THIS PROJECT FOR QUITE SOME TIME, AND
 05:24:54 SOME OF YOU WERE INVOLVED AT PLANNING AND ZONING BOARD WHEN
 05:24:57 WE HAD THE COMPREHENSIVE PLAN AMENDMENT WHEN WE FIRST

 05:24:59 BROUGHT IT FORWARD, AND THERE'S BEEN COUNCIL MEETINGS ON
 05:25:02 THIS.
 05:25:02 IT'S BEEN A FAIRLY LONG PROCESS.
 05:25:04 NOW THE NEW BOARD IS INVOLVED WITH THE SITE PLAN REVIEW.
 05:25:08 AND WE HAD A PUBLIC INFORMATION MEETING ON SEPTEMBER 14th.
 05:25:12 AT THAT TIME, THE PLANNING ZONING AND DESIGN BOARD HAD
 05:25:15 SEVERAL QUESTIONS AND SOME SUGGESTIONS FOR THE APPLICANT.
 05:25:18 THERE WERE QUESTIONS ABOUT LOOKING AT ENHANCING THE
 05:25:21 LANDSCAPING AND REFINING THE ARCHITECTURE AND ENHANCING IT A
 05:25:25 LITTLE BIT TO SEE IF THAT COULD BE DONE.
 05:25:31 ALSO, AT THE TIME IT WAS BROUGHT UP A QUESTION ABOUT WHETHER
 05:25:34 THIS SCHOOL HAD TO COMPLY WITH THE CODES IN EFFECT, THE LAND
 05:25:38 DEVELOPMENT CODE.
 05:25:39 SO IT WAS A LEGAL QUESTION.
 05:25:40 DO THEY HAVE TO COMPLY AND COULD THEY EXPLAIN WHAT THINGS
 05:25:45 THEY WEREN'T ABLE TO COMPLY WITH THE CODE FOR AND THE
 05:25:47 REASONS THEY MIGHT NEED A DEVIATION OR SOME VARIATION FROM
 05:25:50 THE CODE?
 05:25:53 THE APPLICANT HAS DONE THAT.
 05:25:55 YOU HAVE A STAFF REPORT.
 05:25:57 YOU'VE GOT THEIR LIST OF DEVIATIONS.
 05:25:59 THEY ARE GOING TO GO THROUGH AND EXPLAIN THAT.
 05:26:03 AND THEN NANCY STROUD IS GOING TO EXPLAIN A LITTLE BIT.
 05:26:08 SHE'S DONE SOME LEGAL RESEARCH AS WELL BECAUSE WHEN THAT
 05:26:12 BROUGHT UP THE QUESTION OF DOES THE SCHOOL SITE NEED TO

 05:26:15 COMPLY WITH THE CODE, BECAUSE TYPICALLY IN THE PAST IN THE
 05:26:19 COUNTY WE'VE HAD INTERLOCAL AGREEMENTS WITH THE SCHOOL BOARD
 05:26:21 THAT KIND OF LAYS OUT EXACTLY WHAT YOU REVIEW.
 05:26:24 WE DON'T HAVE AN INTERLOCAL WITH THE VILLAGE.
 05:26:25 SO WE'RE RELYING ON OUR CODE.
 05:26:27 SO NANCY HAS DONE SOME RESEARCH AND SHE WAS, I THINK, GOING
 05:26:31 TO EXPLAIN THAT A LITTLE BIT BEFORE WE TURN IT OVER TO THE
 05:26:34 APPLICANT.
 05:26:34 I DID WANT TO SAY THAT WE DID GET FOUR E-COMMENTS, WHICH I
 05:26:39 DID FORWARD TO YOU.
 05:26:40 THERE WERE THREE FROM COUNTRY CREEK THAT WERE BASICALLY IN
 05:26:44 OPPOSITION.

05:26:45 THERE WERE WORRIES ABOUT TRAFFIC, DRAINAGE, AND THEN ONE
 05:26:49 ACCESS IN AND OUT OF THE SITE.
 05:26:51 AND THEN THERE WAS ONE IN FAVOR FROM ANOTHER PERSON THAT
 05:26:55 JUST SAID THE SCHOOL WOULD BE GOOD.
 05:26:57 SO THAT'S A QUICK SUMMARY.
 05:26:58 BUT I THINK, NANCY, DID YOU WANT TO COMMENT AT THIS TIME
 05:27:01 BEFORE I TURN IT OVER TO THE APPLICANT?
 05:27:04 >>Nancy Stroud: MR. CHAIR, DO YOU WANT ME TO COMMENT NOW?
 05:27:08 >>Howard Levitan: YEAH, I WOULD LIKE YOU TO GO THROUGH YOUR
 05:27:11 COMMENTS, AND I WOULD LIKE TO MAKE THE E-MAIL THAT YOU GAVE
 05:27:15 TO MARY AND I WITH RESPECT TO THE SCHOOL LAWS A PART OF THE
 05:27:23 RECORD.
 05:27:24 >>Nancy Stroud: OKAY.

 05:27:25 I WILL JUST GO OVER THAT WITH THE BOARD BECAUSE AS WE ALL
 05:27:32 KNOW, I THINK, SCHOOLS HAVE THEIR OWN STATUTORY AUTHORITY
 05:27:37 THAT IS INDEPENDENT, IN MANY WAYS, FROM LOCAL GOVERNMENT.
 05:27:42 SO THERE'S ALWAYS A KIND OF BACK AND FORTH BETWEEN SCHOOLS
 05:27:47 AND LOCAL GOVERNMENT, ESPECIALLY ON THINGS LIKE SCHOOL SITE
 05:27:50 PLANNING.
 05:27:53 THERE IS A STATUTE THAT DESCRIBES THE SCHOOL BOARD
 05:27:59 AUTHORITY, WHICH REALLY COMES FROM THE STATE VERSUS LOCAL
 05:28:02 AUTHORITY IN RELATION TO SITE PLANNING ESPECIALLY.
 05:28:08 SO THIS IS ALL ABOUT WHAT LOCAL DEVELOPMENT ORDERS ARE,
 05:28:13 THEIR SITE PLANS.
 05:28:14 AND THE STATUTE SAYS THAT A LOCAL GOVERNMENT BODY MAY NOT
 05:28:22 DENY THE SITE PLAN APPLICANT BASED ON THE ADEQUACY OF THE
 05:28:27 SITE PLAN AS IT RELATES SOLELY TO THE NEEDS OF THE SCHOOL.
 05:28:31 IT ALSO SAYS THAT LOCAL GOVERNMENT MAY IMPOSE REASONABLE
 05:28:39 DEVELOPMENT STANDARDS AND CONDITIONS AND CONSIDER THE SITE
 05:28:43 PLAN AS IT RELATES TO ENVIRONMENTAL CONCERNS, HEALTH,
 05:28:48 SAFETY, AND WELFARE, AND EFFECTS ON ADJACENT PROPERTY.
 05:28:52 SO THAT'S VERY GENERAL LANGUAGE, AND THERE'S NOT A LOT OF
 05:28:59 INTERPRETATION OF THAT.
 05:29:02 I'LL GIVE YOU THE BEST THAT I CAN GLEAN FROM THE CASE LAW
 05:29:07 AND JUST FROM, I THINK, LOGIC.
 05:29:10 THIS REALLY IS A KIND OF BALANCING ACT IN THE END.
 05:29:15 WHAT THE NEEDS OF THE SCHOOL ARE, ARE NOT DEFINED.
 05:29:21 WE NEED TO LISTEN TO THE SCHOOL IN RELATION TO WHAT THEY

 05:29:27 THINK THE NEEDS OF THE SCHOOL ARE.
 05:29:29 AND ONE OF THE NEEDS THAT HAS COME UP IN THE LAST MEETING ON
 05:29:33 THIS WAS THE NEED FOR THE SCHOOL TO STAY WITHIN CERTAIN
 05:29:38 BUDGETARY PARAMETERS.
 05:29:40 AND THOSE PARAMETERS ARE VERY STRICT.
 05:29:42 THEY ARE SET FORWARD IN STATE STATUTE.
 05:29:45 AND I THINK, UNFORTUNATELY, THE STATE IS NOT VERY GENEROUS
 05:29:48 WHEN IT COMES TO SCHOOL CONSTRUCTION.

05:29:53 SO THAT'S ONE NEED OF THE SCHOOL.
 05:29:55 ANOTHER NEED OF THE SCHOOL IS MORE SPECIFICALLY ADDRESSED IN
 05:29:59 THE STATUTES, AND THAT IS THE NEED FOR SAFETY.
 05:30:02 AND THERE'S QUITE A BIT OF DETAIL IN THE FLORIDA
 05:30:08 ADMINISTRATIVE CODE REGARDING WHAT KINDS OF SECURITY AND
 05:30:14 SAFETY ISSUES THE SCHOOL NEEDS TO CONSIDER.
 05:30:19 AND THIS IS WHERE YOU GET INTO QUESTIONS OF SIGHT LINES,
 05:30:25 LANDSCAPING, THE ABILITY OF A SECURE WALL AND SECURE
 05:30:31 ENTRANCES.
 05:30:33 ALL OF THOSE ARE THE KINDS OF THINGS THAT THE SCHOOL NEEDS
 05:30:35 TO CONSIDER.
 05:30:38 THE LOCAL GOVERNMENT CAN CONSIDER WHAT IS GENERALLY
 05:30:44 DESCRIBED AS ENVIRONMENTAL CONCERNS, HEALTH, SAFETY, AND
 05:30:47 WELFARE, AND EFFECTS ON ADJACENT PROPERTY.
 05:30:50 I DO BELIEVE THAT BASED ON THE CASE LAW, WHEN THESE TWO
 05:30:58 AUTHORITIES COME INTO CONFLICT, POTENTIAL CONFLICT, THAT THE
 05:31:04 COURTS JUST REALLY TRY TO BALANCE THE IMPORTANCE OF WHAT THE

 05:31:09 SCHOOL NEEDS VERSUS WHAT THE LOCAL GOVERNMENT NEEDS.
 05:31:13 SO WHEN THERE'S A CRITICAL LOCAL GOVERNMENT ISSUE THAT THE
 05:31:21 COURT IS GOING TO WEIGH ON THE LOCAL GOVERNMENT, IF THE
 05:31:25 COURT DOESN'T CONSIDER IT SO CRITICAL, THEN IT MIGHT WEIGH
 05:31:29 MORE ON THE SCHOOL.
 05:31:32 SO I THINK JUST IN SUM, A LOT OF THE DEVIATIONS THAT ARE
 05:31:39 BEING CONSIDERED IN THIS SITE PLAN ARE ISSUES RELATED TO
 05:31:44 SECURITY, AND THAT IS SOMETHING THAT WE REALLY NEED TO, I
 05:31:50 THINK, DEFER TO THE SCHOOL BOARD ON.
 05:31:55 OTHER ISSUES MAY BE MORE AESTHETIC.
 05:32:03 AND IN THAT VIEW POINT, I'M NOT SURE THAT THE COURTS WOULD
 05:32:06 BE VERY SUPPORTIVE OF A LOCAL GOVERNMENT INSISTENCE ON A LOT
 05:32:13 OF STRICT AESTHETIC RULES.
 05:32:15 THAT'S JUST BASICALLY IT.
 05:32:17 I THINK THERE'S ONE OTHER THING THAT MARY MIGHT WANT TO
 05:32:21 ADDRESS, AND THAT IS LANDSCAPING VARIATIONS AND THE CODE'S
 05:32:27 ABILITY TO ALLOW FOR ADMINISTRATIVE LANDSCAPING DEVIATIONS
 05:32:35 THAT THE STAFF CAN DO AND ALTERNATIVE LANDSCAPING PLANS.
 05:32:41 THAT'S SOMETHING THAT I THINK MARY PROBABLY WILL ADDRESS.
 05:32:45 >>Howard Levitan: NANCY, BEFORE YOU GO, I WANTED TO ASK YOU
 05:32:48 ABOUT THE ISSUE OF -- I'M SORRY.
 05:32:54 I'D LIKE TO ASK NANCY A QUESTION, IF I COULD.
 05:32:59 WE'RE USING THE WORD "DEVIATION," AND I HAVE SOME CONCERNS
 05:33:08 ABOUT THAT.
 05:33:09 I KNOW I ASKED THAT QUESTION AT THE LAST ONE AND ASKED TO

 05:33:14 HAVE A LIST OF DEVIATIONS.
 05:33:16 BUT IN LOOKING CLOSER AT THE LAND DEVELOPMENT CODE, I'M
 05:33:21 CONCERNED ABOUT WHO HAS THE POWER TO GRANT DEVIATIONS.
 05:33:26 AND SO IT PROBABLY WOULD BE BETTER TO TALK IN TERMS OF WHAT

05:33:34 AREAS OF THE CODE THEY ARE NOT ABLE TO COMPLY WITH, AND THEN
 05:33:38 TO DETERMINE -- AND THEN WE THEN MAKE THE DETERMINATION
 05:33:41 WHETHER OR NOT THOSE AREAS ARE PREEMPTED BY THE STATE OR CAN
 05:33:45 BE DEALT WITH BY AN ADMINISTRATIVE DEVIATION, WHICH IS
 05:33:49 ALLOWED UNDER OUR CODE.
 05:33:50 THIS IS A UNIQUE SITUATION WHERE I DON'T BELIEVE THAT THE
 05:33:56 BOARD HAS THE POWER AND MAY NOT EVEN BE THE COUNCIL HAVING
 05:33:59 THE POWER TO GRANT DEVIATIONS, EXCEPT IN THE CONTEXT OF
 05:34:04 EITHER A REZONING OR A PLANNED DEVELOPMENT.
 05:34:10 WHICH WE DO NOT HAVE HERE.
 05:34:12 IF YOU COULD COMMENT ON THAT AS WELL.
 05:34:16 >>Nancy Stroud: I DO THINK THAT WHEN WE USE DEVIATIONS IN
 05:34:19 THIS REGARD, WE PROBABLY SHOULD BE SAYING VARIATIONS
 05:34:24 BECAUSE, IN FACT, IF WE LOOK CLOSELY AT THE CODE, THERE ARE,
 05:34:29 AT THIS POINT, UNLESS WE DO A GLITCH BILL IN THE FUTURE, AT
 05:34:33 THIS POINT, THE BOARD IS NOT ABLE TO GRANT DEVIATIONS FOR
 05:34:39 OTHER THAN LAND DEVELOPMENTS AND -- MARY KNOWS THE OTHER
 05:34:46 ONE.
 05:34:47 THERE ARE SUCH THINGS AS ADMINISTRATIVE DEVIATIONS THAT ARE
 05:34:55 MUCH SMALLER THAN WHAT THIS BOARD USUALLY LOOKS AT.
 05:34:59 BUT THERE MAY BE SOME ABILITY ON THIS SITE PLAN TO USE THAT

 05:35:06 ADMINISTRATIVE DEVIATION POWER.
 05:35:07 EVEN THE COUNCIL DOESN'T HAVE DEVIATION POWER IN THIS
 05:35:11 CIRCUMSTANCE, SO WE REALLY -- I THINK WE NEED A NEW TERM FOR
 05:35:16 VARIATIONS, MAYBE.
 05:35:18 >>Howard Levitan: OKAY.
 05:35:19 WITH THAT IN MIND, I'D LIKE TO TURN THIS OVER TO THE
 05:35:23 APPLICANT.
 05:35:26 AND I WOULD ASK THE BOARD TO HOLD THEIR QUESTIONS UNTIL THE
 05:35:29 APPLICANT HAS COMPLETED HIS DISCUSSION.
 05:35:32 >>Mary Gibbs: MAY I SAY ONE THING BEFORE WE TURN IT OVER TO
 05:35:35 THE APPLICANT?
 05:35:36 >>Howard Levitan: SURE.
 05:35:36 >>Mary Gibbs: I THINK WE CAN SIMPLIFY THIS.
 05:35:39 BECAUSE WHAT I ASKED THE APPLICANT DO IN THE PRESENTATION IS
 05:35:41 TALK ABOUT THE THINGS THAT THEY FELT WERE SAFETY AND
 05:35:45 SECURITY ISSUES.
 05:35:45 THAT WILL COVER A LOT OF THE ONCE THAT THEY HAVE ASKED FOR.
 05:35:50 THEN WE HAVE THE ARCHITECTURE WHICH YOU NEED TO DECIDE.
 05:35:52 I ASKED THEM TO ALSO FOCUS ON WHAT THEY'VE DONE SINCE THE
 05:35:56 LAST MEETING WHERE WE ASKED THEM TO ADD SOME ARCHITECTURAL
 05:35:59 REFINEMENTS.
 05:36:00 AND THEN THE LANDSCAPING, I THINK YOU ASKED THEM TO SEE IF
 05:36:03 THEY COULD ADD MORE TREES.
 05:36:04 SO THEY WANT TO TALK ABOUT THAT.
 05:36:06 AND THAT WE WOULD CONSIDER UNDER THE CODE TO BE AN

05:36:09 ALTERNATIVE LANDSCAPE BETTERMENT PLAN.
 05:36:12 SO WE THINK THAT CAN BE HANDLED THAT WAY.
 05:36:14 SO I THINK WHEN DANA EXPLAINS, IT WILL BE A LITTLE MORE
 05:36:18 SIMPLE THAN IT SOUNDS, I HOPE.
 05:36:24 >> GOOD EVENING.
 05:36:26 FOR THE RECORD, DANA HUME WITH JOHNSON ENGINEERING.
 05:36:33 I AM A SMALL PART OF A VERY LARGE TEAM THAT'S BEEN WORKING
 05:36:36 ON THIS PROJECT FOR QUITE A WHILE.
 05:36:39 >>Howard Levitan: WRONG BUILDING.
 05:36:42 >>Dana Hume: I WAS JUST GOING TO SAY THAT'S NOT OUR
 05:36:44 BUILDING.
 05:36:45 THAT'S OKAY.
 05:36:45 WE'RE GETTING THERE.
 05:37:09 THIS IS WHERE I STRUGGLED THE LAST TIME.
 05:37:13 SO THANK YOU, AGAIN, FOR THIS OPPORTUNITY TO COME BEFORE YOU
 05:37:17 TODAY.
 05:37:17 SO WE ARE HERE FOR THE PUBLIC HEARING FOR THE DEVELOPMENT
 05:37:20 ORDER DOS 2021-E004.
 05:37:25 THOSE MEMBERS OF THE TEAM THAT ARE WITH ME TONIGHT INCLUDE
 05:37:32 SCOTT RICKENBACKER, WHO IS THE DIRECTOR OF CONSTRUCTION
 05:37:35 PROJECTS.
 05:37:36 TINA SILCOX, WHO IS THE PROJECT MANAGER.
 05:37:39 KATHIE EBAUGH, WHO IS DIRECTOR OF FACILITY AND PLANNING.
 05:37:42 DAVE NEWLAN, WHO IS THE EXECUTIVE DIRECTOR OF SAFETY,
 05:37:45 SECURITY, AND EMERGENCY MANAGEMENT.

 05:37:48 ALL OF THOSE FOLKS ARE FROM THE SCHOOL DISTRICT.
 05:37:50 STEVE JOHNSON IS A PRINCIPAL VICE PRESIDENT AT HARVARD
 05:37:55 JOLLY.
 05:37:56 MIKE JOHNSON, NO RELATION, IS A VICE PRESIDENT AT HARVARD
 05:37:59 JOLLY.
 05:38:00 AND JEFF NAGLE, OUR LANDSCAPE ARCHITECT IS ALSO WITH US
 05:38:05 TONIGHT.
 05:38:05 LEAH HOLMES, WHO WAS WITH US THE LAST TIME, UNFORTUNATELY
 05:38:08 HAD A MEDICAL EMERGENCY TODAY.
 05:38:10 SO SHE COULD NOT BE WITH US TONIGHT.
 05:38:12 SO WITH THAT, I KNOW LAST TIME I STARTED OUT WITH A BRIEF
 05:38:17 HISTORY OF HOW WE GOT HERE.
 05:38:20 IF IT IS OKAY WITH THE BOARD, I AM GOING TO PASS ON THAT.
 05:38:23 AND IF YOU'VE GOT ANY QUESTIONS ABOUT THE HISTORY, WE CAN
 05:38:26 BRING IT UP AT THAT TIME.
 05:38:28 SO WITH THAT, WHAT WE'RE GOING TO TALK ABOUT TONIGHT, WE'RE
 05:38:34 GOING TO TALK ABOUT THE LANDSCAPE DESIGN AND THE DISCUSSIONS
 05:38:38 THAT WE HAD AT THE LAST MEETING.
 05:38:40 THEN WE'LL WORK OUR WAY INTO THE ARCHITECTURAL DISCUSSION.
 05:38:44 THEN WE'LL TOUCH ON TRAFFIC.
 05:38:47 THEN WE'LL TOUCH ON VARIATION DISCUSSIONS INSTEAD OF
 05:38:51 DEVIATIONS.

05:38:51 AND THEN ONE OF THE THINGS THE CHAIRMAN ASKED FOR AT THE
 05:38:57 LAST MEETING WAS FOR US TO SHOW THE COST DIFFERENCES THAT
 05:39:06 IT'S COSTING THE SCHOOL DISTRICT TO GO FROM THEIR TYPICAL

 05:39:10 PROTOTYPE THAT THEY WOULD DO ANYWHERE ELSE IN THE COUNTY
 05:39:12 VERSUS WHAT IT'S COSTING THEM TO PUT THE SCHOOL IN THE
 05:39:17 VILLAGE.
 05:39:18 SO WE PUT TOGETHER SOME COSTS ASSOCIATED WITH THAT.
 05:39:20 SO WITH THAT -- WRONG WAY.
 05:39:24 LET ME START WITH THE LANDSCAPE PLAN.
 05:39:26 WE CERTAINLY HEARD YOU AT THE LAST MEETING, SO WE WENT BACK
 05:39:34 IN TO THE LANDSCAPE DESIGN OF THE PROJECT.
 05:39:36 AND LET ME FIRST CLARIFY, AT THE LAST MEETING, IT WAS
 05:39:40 BROUGHT UP THAT WE DO HAVE LANDSCAPE BUFFERS THAT WE HAVE TO
 05:39:47 MEET.
 05:39:47 THE SCHOOL DISTRICT, PER CODE, DOES NOT HAVE TO MEET ANY
 05:39:50 BUFFERS.
 05:39:51 AND SO ALTHOUGH WE ARE SHOWING THE BUFFER ALONG THE
 05:39:55 RESIDENTIAL COMMUNITY AND ALONG THREE OAKS, WE ARE
 05:39:59 PRESERVING THE AREA ALSO ALONG THE RESIDENTIAL COMMUNITY.
 05:40:04 WE HAVE ADDED A LOT OF LANDSCAPING IN STRATEGIC AREAS THAT
 05:40:11 IN REVIEWING THE SITE WITH THE SECURITY, MAKING SURE THAT
 05:40:16 THESE ADDITIONAL PLANTINGS WOULD NOT BE A CHALLENGE.
 05:40:20 AND SO WE'VE ADDED LANDSCAPING.
 05:40:22 YOU CAN SEE PROBABLY BETTER ON YOUR SCREENS THE AREAS THAT
 05:40:26 ARE CIRCLED IN RED.
 05:40:29 THOSE ARE AREAS WHERE WE HAVE ADDED PALM TREES OF VARYING
 05:40:34 SIZES.
 05:40:36 SO WE'VE TRIED TO ADD THEM AT KEY VIEWPOINTS.

 05:40:41 SO ALONG THREE OAKS PARKWAY YOU'LL HAVE THE OAK TREES THAT
 05:40:46 ARE ALONG THE FRONT ALONG THREE OAKS.
 05:40:50 AND THEN WE'VE ADDED ANOTHER ROW OF PALM TREES THAT IF
 05:40:55 YOU'RE LOOKING THROUGH, YOU'LL BE LOOKING AT THOSE PALM
 05:40:57 TREES ALSO.
 05:40:59 IF YOU'RE AT THE INTERSECTION LOOKING DOWN THE ENTRANCE
 05:41:01 ROAD, YOU'LL SEE A GROUPING OF LANDSCAPE PALMS ON THE LEFT
 05:41:08 SIDE, NORTH SIDE, AND THEN YOU'LL SEE SOME OTHER CLUMPINGS
 05:41:11 OF LANDSCAPE PALMS WITHIN THE SITE.
 05:41:15 WE'VE ALSO ADDED A LOT OF PALM TREES UP AGAINST THE BUILDING
 05:41:21 TO TRY AND BREAK UP THE FACES OF THE BUILDING.
 05:41:25 SO WE'VE ADDED A TOTAL OF 58 -- I'M SORRY, 51 ADDITIONAL
 05:41:30 PALMS.
 05:41:31 THEY RANGE IN SIZE 20 TO 24 FEET.
 05:41:34 THERE'S NINE OF THOSE THAT ARE UP AGAINST THE BUILDING.
 05:41:37 AND THEN WE'VE GOT 17 14 TO 16-FOOT HEIGHT PALM TREES.
 05:41:43 AGAIN, WHAT WE'RE TRYING TO DO IS BREAK UP THE VIEWPOINTS
 05:41:46 WITH EVERYTHING.

05:41:47 ONE THING I DO WANT TO POINT OUT IS WHERE THE SCHOOL IS
 05:41:52 LOCATED AT ON THE SITE.
 05:41:54 AS WE TALKED ABOUT LAST TIME, THE SCHOOL SITS BACK FROM
 05:41:57 THREE OAKS PARKWAY ABOUT 1400 FEET, WHICH IS ABOUT A QUARTER
 05:42:02 OF A MILE OR FOUR FOOTBALL FIELDS.
 05:42:05 IF YOU LINE FOUR FOOTBALL FIELDS UP, THAT'S WHERE THE SCHOOL
 05:42:08 SITS FROM THREE OAKS PARKWAY.

05:42:10 WHEN WE'RE LOOKING AT THE SCHOOL FROM I-75, IT'S ABOUT --
 05:42:14 THE GYM, WHICH IS THE CLOSEST PART OF THE BUILDING THAT IS
 05:42:19 TO I-75, THAT'S 750 FEET AWAY FROM I-75, WHICH IS ABOUT TWO
 05:42:26 FOOTBALL FIELDS IN LINE.
 05:42:29 WE'VE ALSO GOT A NATURAL BUFFER THAT EXISTS -- LET ME FLIP
 05:42:37 TO THE NEXT SLIDE.
 05:42:38 SO THERE'S A NATURAL BUFFER THAT EXISTS ALONG I-75 TODAY
 05:42:43 THAT IS WITHIN THE RIGHT-OF-WAY OF I-75, BUT IT IS A BUFFER
 05:42:49 THAT WILL ALSO IMPEDE THE VIEW OF THE BUILDING AND WHATNOT.
 05:42:56 THERE'S ALSO TWO FENCES THAT ARE ALONG I-75.
 05:43:02 F.D.O.T. ALWAYS HAS THEIR BARBED WIRE FENCE SO EVERYBODY
 05:43:05 TRYING TO CLIMB OVER IT GETS HUNG UP AND SKEWERED.
 05:43:09 THEN WE'LL HAVE A SIX-FOOT-HIGH FENCE THAT WILL BE ALONG THE
 05:43:13 TOP OF OUR BERM WITHIN THE PROJECT.
 05:43:17 SO WITH THAT, I'M GOING TO DO MY BEST ATTEMPT AT GOING
 05:43:24 THROUGH THE ARCHITECTURE AND, OF COURSE, STEVE AND MIKE ARE
 05:43:28 HERE TO ANSWER ANY DETAILED QUESTIONS THAT YOU MAY HAVE.
 05:43:31 SO ONE OF THE THINGS WE HEARD AT THE LAST MEETING WAS TRYING
 05:43:34 TO ADD SOME MORE DEFINITION TO THE BUILDING.
 05:43:38 SO WHAT WE'VE DONE IS WE'VE GONE IN AND WE'VE CREATED THESE
 05:43:41 PARAPETS, AND WE'RE PROVIDING ARCHES ON ALL OF THE PARAPETS,
 05:43:49 WHICH IS SOMETHING THAT IS NEW FROM THE LAST TIME THAT WE
 05:43:52 WERE HERE WITH YOU.
 05:43:55 ALSO, THE CANOPIES WHERE THE KIDS GET DROPPED OFF, WE HAVE,
 05:44:01 AND WE DISCUSSED AT THE LAST HEARING, WE HAVE CHANGED THE

05:44:04 ELEVATION SO THAT, AGAIN, WE'RE TRYING TO BREAK UP THAT
 05:44:07 VIEWPOINT.
 05:44:10 THIS IS WHAT IT WILL LOOK LIKE WITH THE TREES IN FRONT OF
 05:44:14 IT.
 05:44:16 SO, AGAIN, JUST TRYING TO BREAK UP THE VIEW AS WE GO ALONG.
 05:44:22 THIS IS THE OTHER SIDE OF THE SAME BUILDING, THE SOUTH SIDE
 05:44:25 OF IT.
 05:44:25 AND HERE YOU CAN SEE IT WITHOUT ANY PALMS TREES OR ANYTHING
 05:44:28 ON IT.
 05:44:29 YOU CAN SEE THE ARCHED PARAPETS, THE DIFFERENCE IN ELEVATION
 05:44:33 OF THE CANOPIES.
 05:44:34 AND THEN WHEN YOU ADD -- I KNEW THAT WAS GOING TO HAPPEN --
 05:44:38 THEN WHEN YOU ADD THE TREES IN, THE PALM TREES INTO IT,
 05:44:42 AGAIN 20 TO 24-FOOT HIGH.

05:44:44 AND THESE ARE WHAT WE'RE PLANNING ON PLANTING DAY ONE.
 05:44:49 SO THOSE WILL BE UP AGAINST THE BUILDING, AND THEN WE'LL
 05:44:52 HAVE SOME PALM TREES THAT ARE ABOUT 15 FEET SET FARTHER
 05:44:56 TOWARDS THE CANOPY.
 05:44:59 THOSE ARE GOING TO BE THE 14 TO 16-FOOT HIGH PALM TREES.
 05:45:04 AND THEN THIS IS THE VIEW AGAIN OF THE BUS AREA.
 05:45:16 THIS DOES NOT SHOW THE ACTUAL VIEW FROM THE ADJACENT
 05:45:21 RESIDENTIAL COMMUNITY WHERE WE HAVE THE ENHANCED BUFFER THAT
 05:45:25 WE'RE PLANTING ALONG WITH THE NATURAL AREA THAT WE'RE
 05:45:31 PLANTING THE EXTRA 50 TREES.
 05:45:33 THOSE DO NOT SHOW UP IN THIS VIEW.

05:45:37 THIS IS JUST STANDING WHERE THE BUS PARKING IS AT, LOOKING
 05:45:40 AT THE BUILDING.
 05:45:41 AND THEN, AGAIN, AS WE SWING OUR WAY AROUND, THIS WOULD BE
 05:45:45 THE VIEW COMING FROM I-75.
 05:45:47 AGAIN, YOU DON'T SEE THE BUFFERING FROM I-75.
 05:45:53 BUT THIS IS WHAT IT WILL LOOK LIKE AT THE BACK OF THE
 05:45:56 BUILDING.
 05:45:57 AND THEN HERE AGAIN IS THE RENDERED SITE.
 05:46:01 YOU CAN SEE AGAIN HOW WE TRIED TO PLACE THE BUILDING NOT
 05:46:04 ONLY IN THE BEST PLACE THAT WE THOUGHT FOR THE BUILDING
 05:46:10 ITSELF, SET BACK A QUARTER OF A MILE FROM THREE OAKS, 750
 05:46:15 FEET FROM I-75.
 05:46:18 THIS ALLOWED US TO DO OUR CAR STACKING THAT WE TALKED ABOUT
 05:46:23 AT LENGTH AT THE LAST MEETING, WHICH, AGAIN, WE HEARD
 05:46:30 THROUGH THE ENTIRE PLANNING AND ZONING PROCEEDINGS AND ALSO
 05:46:36 THROUGHOUT ALL OF OUR MEETINGS AND DISCUSSIONS WITH LEE
 05:46:39 COUNTY D.O.T., THAT THEY DO NOT WANT ANY STACKING OUT ON
 05:46:43 THREE OAKS PARKWAY.
 05:46:44 SO THE NEXT SLIDE, THIS SLIDE IS THE COLORS THAT THE
 05:46:54 BUILDING WILL BE.
 05:46:57 AND THEN WHEN I GO TO THE RENDERINGS, UNFORTUNATELY I CAN'T
 05:47:01 BLOW THIS UP, BUT YOU CAN SEE HOW MIKE AND STEVE HAVE VARIED
 05:47:07 THE COLORS THROUGHOUT THE FACADES.
 05:47:11 AND THESE ARE THE DIFFERENT ELEVATIONS.
 05:47:14 STARTING DOWN AT THE BOTTOM, WE'VE GOT THE NORTH ELEVATION

05:47:19 AND THE GYM.
 05:47:20 AND THEN AS WE'RE WORKING OUR WAY UP, THAT'S THE EAST
 05:47:23 ELEVATION, AND THEN THE WEST ELEVATION, AND THEN THE VERY
 05:47:26 TOP ONE IS THE WEST ELEVATION OF THE ADMINISTRATION AND WEST
 05:47:31 WING OF THE CLASSROOMS.
 05:47:35 AGAIN, WANTED TO SHOW YOU THE MONUMENT SIGN THAT'S GOING TO
 05:47:42 BE OUT FRONT.
 05:47:48 AND THE COLORS AGAIN, I DON'T BELIEVE WE'RE GOING TO BE
 05:47:53 CALLING THIS AT THE END OF THE DAY QUADRUPLE A, BUT WE HAD
 05:47:57 TO HAVE A PLACE HOLDER.

05:47:59 BUT THIS IS WHAT IT WILL LOOK LIKE, AND IT DOES MEET ALL OF
 05:48:04 THE CODE.
 05:48:05 SO LET'S TALK TRAFFIC FOR A MINUTE.
 05:48:09 THESE ARE ALL POINTS THAT HAVE BEEN DISCUSSED THROUGHOUT THE
 05:48:15 DIFFERENT HEARINGS THAT WE'VE HAD.
 05:48:20 WHEN WE LOOK AT TRAFFIC, THE IUTT MANUAL, WE USE THE
 05:48:26 ELEMENTARY SCHOOL NUMBERS BECAUSE THOSE ARE THE MOST STRICT
 05:48:31 OR RESTRICTIVE CASE THAT YOU WOULD HAVE.
 05:48:36 AND SO EVEN THOUGH WE HAVE AN ELEMENTARY SCHOOL AND A MIDDLE
 05:48:39 SCHOOL, WE DID EVERYTHING BASED ON ELEMENTARY SCHOOL
 05:48:43 NUMBERS.
 05:48:45 SO THE TRIP GENERATIONS FOR THE 2350 STUDENTS, AGAIN, AS I
 05:48:52 POINTED OUT AT THE LAST MEETING, THE SCHOOL IS OPENING UP
 05:48:54 WITH 1800 STUDENTS.
 05:48:57 WHEN THE 2350 STUDENTS BUILD-OUT WILL COME, WE REALLY DON'T

 05:49:03 KNOW.
 05:49:04 TIME WILL TELL.
 05:49:05 BUT WE ARE STARTING OUT WITH 1800 STUDENTS.
 05:49:09 THE SCHOOL HOURS, AGAIN, WERE CHOSEN TO BE DURING OFF-PEAK
 05:49:15 HOURS.
 05:49:17 SO STUDENTS WILL ARRIVE AT -- I SHOULD SAY CLASS BELL RINGS
 05:49:21 AT 8:55 AND THEN CLASS IS OVER AT 3:55.
 05:49:26 THE SCHOOL DISTRICT LOOKED AT THAT INTENTIONALLY TO TRY AND
 05:49:31 MINIMIZE THE TRAFFIC AT PEAK HOUR.
 05:49:38 AND THEN THERE'S ALSO A VERY HIGH GROWTH RATE FOR THREE OAKS
 05:49:43 PARKWAY FOR THE 2025 VOLUME, WHICH IS 7%.
 05:49:47 NORMALLY, FROM WHAT I'VE BEEN TOLD -- I'M NOT A TRAFFIC
 05:49:51 ENGINEER, SO I RELY ON MY TRAFFIC ENGINEERS THAT WORK WITH
 05:49:54 ME -- THEY SAID NORMALLY THAT'S A 3% GROWTH RATE.
 05:50:00 BUT FOR THREE OAKS, FOR THIS AREA, KNOWING WHAT'S GOING ON
 05:50:05 IN THE VILLAGE OF ESTERO, YOU KNOW, THEY HAVE CHOSEN A MUCH
 05:50:09 HIGHER GROWTH RATE, WHICH IS PROBABLY VERY APPROPRIATE.
 05:50:12 SO WHAT'S THE SCHOOL DISTRICT DOING TO MITIGATE WHAT THEY
 05:50:20 CAN FOR THE TRAFFIC THAT IS BEING CAUSED BY THE SCHOOL?
 05:50:25 SO ALONG WITH SIGNALIZING THE INTERSECTION AND CREATING
 05:50:31 CROSSWALKS ON ALL FOUR CORNERS, WE'LL ALSO HAVE 700-FOOT
 05:50:39 LONG DUAL LEFT-TURN LANES INTO THE SITE, AND WE'RE ALSO
 05:50:44 BUILDING A 300-FOOT NORTHBOUND RIGHT-TURN LANE INTO THE
 05:50:48 SITE.
 05:50:49 THOSE ARE ALL COSTS THAT ARE SCHOOL DISTRICT IS BEARING 100%

 05:50:54 OF THOSE COSTS.
 05:50:55 LOOKING AT WHAT IS ALSO GOING ON WITH LEE COUNTY AND LEE
 05:51:07 COUNTY D.O.T. AND SOME OF THE THINGS THAT THEY HAVE GOING
 05:51:09 ON, AND NOT ONLY LEE COUNTY D.O.T. BUT ALSO F.D.O.T., SO LEE
 05:51:16 COUNTY HAS ON THE HORIZON CORKSCREW ROAD FROM 41 TO BEN HILL
 05:51:21 WHERE THEY ARE GOING TO WIDEN IT FROM FOUR TO SIX LANES.

05:51:24 CORKSCREW ROAD FROM BEN HILL TO ALICO ROAD WHERE IT'S GOING
 05:51:29 TO BE WIDENED FROM TWO TO FOUR LANES.
 05:51:31 AND THAT HAS -- PHASE ONE OF THAT IS BEING LET THIS MONTH.
 05:51:38 SO THEY'LL ACTUALLY GET STARTED.
 05:51:39 AND THEN THERE ARE ALREADY IN THE DESIGN TO DO THE OTHER
 05:51:43 WIDENING PORTIONS.
 05:51:45 SOME OF THE OTHER THINGS THAT LEE COUNTY D.O.T. IS LOOKING
 05:51:48 AT, THEY ARE LOOKING AT THE CORKSCREW ROAD AND THREE OAKS
 05:51:51 PARKWAY INTERSECTION IMPROVEMENTS, WHICH WOULD INCLUDE
 05:51:55 EXTENDING THE EASTBOUND LEFT-TURN LANES, EXTENDING THE
 05:51:59 NORTHBOUND RIGHT-TURN LANE AND ADDING SECONDARY NORTHBOUND
 05:52:04 RIGHT-TURN LANE.
 05:52:05 SO THAT'S AT CORKSCREW AND THREE OAKS.
 05:52:08 AND THEN AT CORKSCREW AND U.S. 41, THOSE INTERSECTION
 05:52:12 IMPROVEMENTS INCLUDE CONSTRUCTING SECONDARY NORTHBOUND
 05:52:16 RIGHT-TURN LANES.
 05:52:20 ONE OF THE THINGS THAT F.D.O.T. IS DOING RIGHT NOW, WHICH WE
 05:52:24 ALL HAVE TO DRIVE THROUGH THE INTERSECTION AT LEAST ONCE A
 05:52:27 WEEK, IS I-75 AT CORKSCREW.

 05:52:30 SO THAT'S BEING IMPROVED CURRENTLY RIGHT NOW.
 05:52:32 SO WITH THAT, I WANT TO MOVE ON TO WHAT ARE SOME OF THE
 05:52:44 COSTS THAT THE SCHOOL DISTRICT IS BEARING TO DO OUR BEST IN
 05:52:50 MEETING THE LAND DEVELOPMENT CODE FOR THE VILLAGE.
 05:52:55 SO WHEN WE LOOK AT THE LANDSCAPING THAT WE TALKED ABOUT IN
 05:52:58 THE PAST, WE'RE DOING THE DRY DETENTION PLANTINGS, LITTORAL
 05:53:04 PLANTINGS, WHICH, AND ALL OF THE OTHER SCHOOLS, WE DON'T DO
 05:53:08 THAT.
 05:53:09 THE BUILDING PERIMETER PLANTINGS, WE'RE DOING THE NATURAL
 05:53:13 AREA THAT WE AGREED WITH THE VILLAGE STAFF TO DO, AND THEN
 05:53:19 THE ADDITIONAL PALMS THAT I MENTIONED EARLIER.
 05:53:22 SO THAT'S ABOUT \$73,000.
 05:53:26 AS WE GET INTO THE VARIATIONS, ONE OF THE VARIATIONS THAT
 05:53:29 WE'RE ASKING FOR, IF ALLOWED, WILL SAVE THE SCHOOL DISTRICT
 05:53:35 OVER \$38,000.
 05:53:38 AND THEN SOME OF THE ARCHITECTURAL ENHANCEMENTS THAT WE'VE
 05:53:46 SHOWN TODAY, THOSE ADD UP TO ABOUT \$44,000.
 05:53:51 SO TO TRY AND MEET THE VILLAGE CODE VERSUS A PROTOTYPE
 05:53:57 SCHOOL THAT WOULD BE DONE ANYWHERE ELSE IN THE COUNTY IS
 05:54:01 APPROXIMATELY \$156,000 MORE.
 05:54:08 SO, WITH THAT, WHAT I'D LIKE TO START WITH IS GOING OVER,
 05:54:18 USING NANCY'S TERMINOLOGY, THE VARIATION REQUESTS.
 05:54:23 SO I WANT TO START WITH THE ELECTRICAL VEHICLES, SECTION
 05:54:28 5-204.B.5.C.
 05:54:34 LAND DEVELOPMENT CODE REQUIRES THAT FOR MORE THAN 150 SPACES

 05:54:39 WE'VE GOT TO HAVE THREE ELECTRICAL CHARGING STATIONS.
 05:54:43 IN TALKING WITH STAFF ABOUT THIS A LOT, WE FEEL THAT THIS

05:54:53 WAS REALLY INTENDED FOR A COMMERCIAL-TYPE USE AND NOT AN
 05:54:58 INSTITUTIONAL TYPE USE THAT WE HAVE BEFORE YOU TODAY.
 05:55:04 SOME OF THE THINGS, TRYING TO PLUG IN ELECTRICAL VEHICLES
 05:55:09 ONTO THE SITE, WHAT IT DOES TO THEM IS IT DOESN'T WORK.
 05:55:17 WE'LL HAVE A THIRD PARTY ADMINISTERING IT.
 05:55:21 IT'S A LIABILITY FOR THE SCHOOL DISTRICT.
 05:55:25 WHOEVER WOULD BE ADMINISTERING THIS PROGRAM WOULD HAVE TO
 05:55:29 FOLLOW THE JESSICA LUNSFORD ACT, WHICH IS A SAFETY ISSUE.
 05:55:34 AND THEY HAVE OVER 130 SCHOOLS IN THE COUNTY RIGHT NOW, AND
 05:55:40 SO ONE OF THE THINGS THAT ALWAYS HAPPENS IS WHEN A NEW
 05:55:44 SCHOOL COMES ALONG, AND THE PRINCIPALS AND STAFF AND
 05:55:49 EVERYBODY, THEY SEE WHAT'S BEING BUILT THERE, THEY WANT IT
 05:55:54 AT THEIR LOCATION.
 05:55:55 AND SO TO TRY AND PUT ELECTRIC CHARGING STATIONS AT ALL OF
 05:55:59 THE DIFFERENT SCHOOLS WOULD BE VERY COST PROHIBITIVE.
 05:56:03 THE SCHOOL DISTRICT ALSO DOES NOT PROVIDE ANY TYPE OF
 05:56:08 FUELING FACILITIES, WHETHER IT BE DIESEL, GAS, OR ELECTRIC
 05:56:14 IN ANY OF THEIR SCHOOLS.
 05:56:16 AND SO THIS WOULD BE SETTING A PRECEDENT.
 05:56:20 SO THE SCHOOL DISTRICT IS REQUESTING THAT THEY BE ALLOWED TO
 05:56:25 PROVIDE ZERO ELECTRIC CHARGING STATIONS FOR ALL OF THOSE
 05:56:32 REASONS.
 05:56:32 THE NEXT VARIATION IS FROM SECTION 5-407.C, THE BUILDING

 05:56:41 PERIMETER PLANTING STANDARDS.
 05:56:43 AGAIN, THE CODE READS THAT WE'VE GOT TO HAVE BUILDING
 05:56:47 PERIMETER PLANTINGS AROUND THREE SIDES OF THE BUILDING.
 05:56:54 AGAIN, FOR SECURITY REASONS, WE HAVE AGREED TO PUT IT ON THE
 05:56:59 WEST FACE, WHICH WOULD BE FACING THREE OAKS.
 05:57:03 WHEN YOU LOOK ON THE NORTH SIDE OF THE SITE, YOU'RE FACING
 05:57:06 THE BUS AREA.
 05:57:09 SO WE REALLY DON'T SEE A BENEFIT TO THAT SIDE.
 05:57:13 ON THE EAST SIDE, WE'RE LOOKING AT I-75.
 05:57:15 WHEN YOU LOOK ON THE SOUTH SIDE, THE SOUTH SIDE OF THE
 05:57:18 BUILDING AS YOU GO ACROSS THE PROPERTY LINE IS A GREAT BIG
 05:57:24 CONSERVATION EASEMENT.
 05:57:25 SO WE REALLY DON'T SEE A BENEFIT OF PUTTING ALL THOSE AROUND
 05:57:29 -- THE PLANTINGS AROUND THERE ON TWO OTHER SIDES BECAUSE WE
 05:57:33 HAVE AGREED TO DO IT ON THE WEST FACE.
 05:57:36 AND THE OTHER CHALLENGE THAT WE HAVE IS, AGAIN, GOING BACK
 05:57:40 TO THE SECURITY, IF WE HAVE BUSHES ALL OVER THE PLACE,
 05:57:43 THAT'S JUST ANOTHER PLACE FOR PEOPLE TO HIDE, KIDS TO HIDE,
 05:57:47 PEOPLE TO DROP BAGS THAT HAVE ALL KINDS OF STUFF IN IT.
 05:57:52 WE'VE ALL READ THE NEWS AND HEARD THE NEWS LATELY OF WHAT'S
 05:57:57 BEEN GOING ON WITH THE SCHOOL DISTRICT.
 05:57:58 SO WE WOULD RESPECTFULLY REQUEST THAT WE BE ALLOWED TO DO
 05:58:02 THE BUILDING PERIMETER PLANTINGS ALONG THE WEST SIDE OF THE
 05:58:06 BUILDING, WHICH IS THE SIDE FACING THREE OAKS.

05:58:08 THE NEXT SIDE VARIATION THAT WE'RE REQUESTING IS FROM

05:58:16 SECTION 5-408.1.4, THE DETENTION, SLASH, LAKE AMENITIES.

05:58:24 HERE AGAIN, WE HAVE A REAL CHALLENGE WITH THIS ONE, AND WE

05:58:28 HAVE, SINCE DAY ONE, FROM A SECURITY STANDPOINT.

05:58:33 THIS SECTION OF THE CODE IS WHERE ANYTIME YOU HAVE A

05:58:38 DETENTION AREA, A LAKE OF A CERTAIN SIZE WITHIN A CERTAIN

05:58:43 DISTANCE TO A PUBLIC RIGHT-OF-WAY, TO PROVIDE -- OH, I'M NOT

05:58:49 FOLLOWING THE PAGES.

05:58:50 I'M SORRY.

05:58:51 I APOLOGIZE FOR THAT.

05:58:57 TO PROVIDE TWO OF THE DIFFERENT ATTRACTORS TO BRING THE

05:59:03 PUBLIC UP INTO YOUR PROPERTY.

05:59:07 SOME OF YOU MAY RECALL I WAS IN FRONT OF YOU WHEN WE DID THE

05:59:10 LEE HEALTH COCONUT POINT.

05:59:13 AND WE BROUGHT ALL THOSE ATTRACTORS UP INTO THE SITE,

05:59:17 BENCHES, GAZEBO, ALL OF THOSE KIND OF THINGS.

05:59:20 SO WE WERE TRYING TO DRAW THE PUBLIC IN TO THAT FACILITY.

05:59:25 THIS IS A PUBLIC SCHOOL, AND THAT'S THE LAST THING THAT WE

05:59:29 WANT TO DO IS TRY AND DRAW THE PUBLIC INTO THE SITE.

05:59:33 THE OTHER THING IS, IS ACCORDING TO SREF, ANYTIME YOU HAVE A

05:59:41 DETENTION AREA, AN AREA THAT WILL HOLD WATER POTENTIALLY FOR

05:59:45 24 HOURS OR LONGER, WE HAVE TO PUT A FENCE AROUND IT.

05:59:48 SO THE DETENTION AREA THAT IS LOCATED UP TOWARDS THREE OAKS

05:59:52 PARKWAY WILL HAVE A FOUR-FOOT FENCE AROUND IT.

05:59:54 SO IT JUST DOESN'T MAKE ANY SENSE TO TRY AND ATTRACT THE

06:00:03 PUBLIC TO COME INTO IT TO VIEW IT WHEN IT'S FACED OFF.

06:00:07 AND IT'S ALSO, MORE IMPORTANTLY, IT'S THE SECURITY CHALLENGE

06:00:10 THAT WE HAVE WHEN WE TRY AND BRING THE PUBLIC INTO THE AREA.

06:00:15 SO THE SCHOOL DISTRICT IS RESPECTFULLY REQUESTING THAT WE

06:00:21 NOT BE REQUIRED TO DO ANY OF THOSE FEATURES THAT ARE

06:00:27 REQUIRED PER THE CODE.

06:00:28 THE NEXT VARIATION REQUEST IS FROM SECTION 5-409,

06:00:35 LANDSCAPING OF PARKING AREAS AND VEHICULAR ACCESSES.

06:00:39 THIS IS THE STANDARD TREES, PARKING LOT TREES, AND THOSE

06:00:46 TYPES OF LANDSCAPING FEATURES.

06:00:50 AND, AGAIN, YOU KNOW, WAS WE'VE TALKED BEFORE, THESE ARE

06:00:56 REAL CHALLENGES WHEN YOU TRY AND MEET THE CODE BECAUSE IT

06:00:59 JUST PROVIDES THAT MUCH MORE OF HIDING PLACES FOR PEOPLE

06:01:05 WHEN WE'RE TRYING TO KEEP OUR CHILDREN SAFE.

06:01:08 SO AS WE PROVIDE MORE LANDSCAPING, WE'RE PROVIDING MORE AND

06:01:13 MORE PLACES FOR THEM TO HIDE.

06:01:15 WE'RE ALSO BLOCKING CAMERA VIEWS FROM BEING ABLE TO PICK UP

06:01:20 THE PUBLIC AS THEY COME ONTO THE SITE.

06:01:24 SO WE TRIED TO ADD THOSE ADDITIONAL PLANTINGS THAT I SHOWED

06:01:28 AT THE VERY BEGINNING IN THOSE STRATEGIC AREAS WHERE THEY

06:01:34 ARE NOT GOING TO INTERFERE WITH THE CAMERAS, AND THEY DO

06:01:39 PROVIDE, YOU KNOW, AS BEST AS WE CAN, SOME ADDITIONAL
 06:01:43 PLANTINGS.
 06:01:44 BUT WE RESPECTFULLY REQUEST THAT THE VILLAGE APPROVE OR LET
 06:01:51 MS. GIBBS APPROVE THE ALTERNATE LANDSCAPE BETTERMENT PLAN
 06:01:55 THAT WE HAVE PROVIDED AS PART OF OUR SUBMITTAL.

06:01:58 SO CONTINUING ON, AND HOWARD IS PROBABLY WONDERING WHY HE
 06:02:06 REQUESTED THIS AT THE LAST MEETING.
 06:02:08 BUT WE DO HAVE SOME ARCHITECTURAL VARIATIONS THAT WE WOULD
 06:02:15 ALSO RESPECTFULLY REQUEST.
 06:02:16 WE'RE GOING TO START WITH SECTION 5-703.A, ARCHITECTURAL
 06:02:21 STYLE VARIATIONS.
 06:02:22 AS WE TALKED AT THE LAST MEETING, TRYING TO MEET THE
 06:02:29 ARCHITECTURAL STYLES THAT ARE WITHIN THE VILLAGE ARE JUST
 06:02:34 NOT -- THEY ARE COST PROHIBITIVE FROM A SCHOOL STANDPOINT.
 06:02:39 AS NANCY WAS SPEAKING, THEY ARE REALLY RESTRICTED ON THEIR
 06:02:45 FUNDS AND HOW THEY GET THEIR FUNDS, SO THEY HAVE TO SPEND
 06:02:48 THEM AS WISELY AS POSSIBLE.
 06:02:51 SO BECAUSE OF THAT, WE'RE PROPOSING TO USE CONCRETE TILT-UP
 06:02:57 WALLS, WHICH HAVE A LONG LIFE SPAN.
 06:03:01 IT'S QUALITY CONSTRUCTION.
 06:03:02 IT WILL SAVE THE TAXPAYERS MONEY, PROVIDES LOW-SLOPED ROOFS,
 06:03:11 STEEL FRAME AND INTERIORS AND FUTURE FLEXIBILITY.
 06:03:15 SO WE'VE AGREED TO ENHANCE THE WESTERN ELEVATION WITH THE
 06:03:20 ARCHES ON THE PARAPETS, THE ADDITIONAL PLANTINGS, AND THE
 06:03:24 VARIATIONS IN ELEVATION OF THE CANOPIES, AND, AGAIN, WE
 06:03:32 RESPECTFULLY REQUEST THAT YOU APPROVE THAT VARIATION.
 06:03:40 THE NEXT ONE IS RELATED TO SECTION 5-703.1.D.
 06:03:46 AND IT'S RELATED TO SLOPED ROOFS.
 06:03:51 AGAIN, THIS IS A COST THING THAT WE GET BACK TO WITH THE
 06:04:00 SCHOOL DISTRICT.

06:04:01 SLOPED ROOFS ARE NOT AS VULNERABLE TO HURRICANE DAMAGE.
 06:04:07 MINIMIZING THE MAINTENANCE AND COSTS.
 06:04:11 SO, AGAIN, WE'RE RESPECTFULLY REQUESTING THAT THAT BE
 06:04:14 APPROVED, THAT WE DEVIATE FROM THAT WITH WHAT WE ARE
 06:04:18 PROPOSING CURRENTLY BECAUSE OF THE COST ASSOCIATED WITH THE
 06:04:21 OTHER TYPES OF ROOFS.
 06:04:23 THE NEXT ONE IS RELATED TO SECTION 5-706.C.6.C.
 06:04:34 HORIZONTAL PLANE OFFSETS.
 06:04:38 WE'VE GONE THROUGH THIS.
 06:04:41 I'VE POINTED OUT SEVERAL TIMES ALREADY THE VARIATIONS THAT
 06:04:45 WE'VE TRIED TO DO.
 06:04:46 THEY TRIED TO BREAK UP THE FACE OF THE BUILDING WITH COLORS.
 06:04:51 WE'VE ADDED THE LANDSCAPING AND UTILIZED THE ARCH PARAPETS
 06:04:59 TO TRY AND BREAK UP THE FACADES.
 06:05:02 AGAIN, WE ARE RESPECTFULLY REQUESTING THAT WE BE ALLOWED TO
 06:05:07 DO THOSE THINGS ALONG THE WESTERN FACE OF THE BUILDING

06:05:10 FACING THREE OAKS.
 06:05:11 WITH YOUR APPROVAL.
 06:05:15 THE NEXT ONE IS SECTION 5-706.F.2, AND IT DEALS WITH ROOF
 06:05:26 TREATMENTS.
 06:05:26 WE ARE ABLE TO MEET TWO OF THE FIVE REQUIREMENTS, ACCORDING
 06:05:30 TO THE LAND DEVELOPMENT CODE, WE'RE SUPPOSED TO -- SORRY,
 06:05:34 MARY.
 06:05:35 JUST AS SOON AS I SEE YOU STAND UP, I KNOW WHAT I'M NOT
 06:05:38 DOING.

06:05:39 SO WE ARE ABLE TO MEET TWO OF THE FIVE REQUIREMENTS.
 06:05:46 WITH THE SLOPED ROOFS, THAT'S AS BEST AS WE CAN DO AS FAR AS
 06:05:52 MEETING THE DIFFERENT CRITERIA THAT WE HAVE DOWN.
 06:05:57 AND WE'VE DONE OUR BEST TO TRY AND MEET THIS SECTION OF THE
 06:06:02 CODE.
 06:06:02 SO ONCE AGAIN, WE WOULD RESPECTFULLY REQUEST THAT WE BE
 06:06:07 ALLOWED TO JUST UTILIZE TWO OF THE FIVE AS OUTLINED ALONG
 06:06:13 THE WESTERN FACE OF THE BUILDING FOR THAT.
 06:06:15 SO THE NEXT VARIATIONS THAT I WANT TO TALK ABOUT ARE RELATED
 06:06:25 TO THE EXTERIOR LIGHTING STANDARDS.
 06:06:27 SO WITH THE ZONING OF OUR PROPERTY, WE'RE ONLY ALLOWED TO
 06:06:35 HAVE 15-FOOT-TALL LIGHT POLES BECAUSE WE'RE IN AG ZONING.
 06:06:42 IF THIS WAS IN ANY OTHER KIND OF ZONING, INSTITUTIONAL
 06:06:46 ZONING, WE WOULD BE ALLOWED TO HAVE 25-FOOT-TALL LIGHT
 06:06:50 POLES.
 06:06:55 SO WHAT WE HAVE AGREED TO DO, IN TALKING WITH STAFF, IS TO
 06:07:03 KEEP THE 15-FOOT-TALL LIGHT POLES ALONG THE COMMERCIAL --
 06:07:08 I'M SORRY -- ALONG THE RESIDENTIAL PROPERTY TO THE NORTH OF
 06:07:12 US, WHICH WOULD BE ALL ALONG THE BUS ENTRANCE WAY.
 06:07:16 AND THEN THE REST OF THE SITE BE ALLOWED TO UTILIZE THE
 06:07:21 25-FOOT-TALL LIGHT POLES.
 06:07:26 AND THERE'S A BIG COST SAVINGS THERE TO THE SCHOOL IN DOING
 06:07:30 THAT OF OVER \$38,000.
 06:07:33 AT THE END OF THE DAY, IT'S PROBABLY GOING TO BE MORE THAN
 06:07:35 THAT IF WE HAD TO DO THE WHOLE SITE AT 15-FOOT-TALL POLES.

06:07:39 BUT WE REASON THE NUMBERS, AND SO WE'LL HAVE A SAVINGS BY
 06:07:45 UTILIZING THOSE 25-FOOT POLES THROUGHOUT THE REMAINDER OF
 06:07:48 THE CAMPUS, 15-FOOT-TALL POLES ALONG THE RESIDENTIAL OR THE
 06:07:53 NORTH PROPERTY, AND SO WE RESPECTFULLY REQUEST THAT YOU
 06:08:00 APPROVE THAT.
 06:08:01 THEN THE LAST ONE IS SECTION 5-604.E LIGHTING STANDARDS.
 06:08:13 I AM NOT AN ELECTRICAL ENGINEER, BUT I HAVE SPOKEN WITH THE
 06:08:20 TEAM'S ELECTRICAL ENGINEER, AND I SPOKE WITH JIM HART LATE
 06:08:25 THIS AFTERNOON ABOUT THIS DEVIATION.
 06:08:29 AND SO IN LIEU OF REQUESTING -- I'M JUST GOING TO GET TO THE
 06:08:38 REQUEST.
 06:08:38 ORIGINALLY, WE WERE REQUESTING TO USE 4000K LED LAMPS ALONG

06:08:48 WITH THE BUG RATING OF A 3-0-3.
 06:08:52 IN TALKING WITH JIM AND WITH OUR ELECTRICAL ENGINEER, WE ARE
 06:08:57 GOING TO MEET ALL OF THE LAND DEVELOPMENT CODE STANDARDS,
 06:09:02 EXCEPT FOR THE GLARE, THE G IN THE BUG.
 06:09:07 JIM SAID THAT HE WAS COMFORTABLE WITH US UTILIZING A VALUE
 06:09:10 OF 2 FOR THAT.
 06:09:12 WE WOULD USE THE 3000K LAMPS.
 06:09:18 THEN THE BUG RATING WOULD BE A 1-0-2 INSTEAD OF A 1-0-1,
 06:09:24 WHICH IS WHAT THE CODE CALLS FOR.
 06:09:26 SO WE WOULD RESPECTFULLY REQUEST THAT WE BE ALLOWED TO DO
 06:09:31 THAT ALSO.
 06:09:32 I HAVE ALSO ATTACHED THE DIFFERENT LIGHTING PLANS WITH THE
 06:09:41 15-FOOT AND THEN THE 25-FOOT POLES WITH THAT, I WANT TO

 06:09:48 STATE THAT WE HAVE REVIEWED THE STAFF REPORT AND THE
 06:09:55 CONDITIONS IN THE STAFF -- AND THE CONDITIONS IN THE STAFF
 06:09:59 REPORT, AND WE FIND THEM ALL ACCEPTABLE AND HAVE NO ISSUES
 06:10:06 RELATED TO THE STAFF REPORT AND THINK THAT MARY DID A VERY
 06:10:08 GOOD JOB ON THAT.
 06:10:09 WITH THAT, WE WILL OPEN IT UP TO QUESTIONS.
 06:10:12 >>Michael Sheeley: COULD YOU CLARIFY THAT LIGHTING ONE MORE
 06:10:14 TIME?
 06:10:15 IT'S WRITTEN THAT YOU'LL GO TO 4000, BUT YOU'LL STAY WITH
 06:10:18 THE 3000.
 06:10:19 >>Dana Hume: YES, SIR.
 06:10:20 SO THIS HAPPENED, LIKE I SAID, THIS AFTERNOON, 2:00.
 06:10:24 SO WE ARE GOING TO STAY WITH THE 3000 LUMES AND BUG RATING
 06:10:33 OF 1-0-2.
 06:10:35 CODE CALLS FOR 1-0-1 BUG RATING.
 06:10:38 WE'LL UP THE GLARE TO 2 IS ALL.
 06:10:41 AND MR. HART WAS FINE WITH THAT.
 06:10:44 IN FACT, THAT'S WHAT HE RECOMMENDED.
 06:10:50 >>Howard Levitan: ANYBODY ELSE ON THE PANEL HAVE ANY
 06:10:52 QUESTIONS THAT THEY WOULD LIKE TO ASK AT THIS TIME BEFORE WE
 06:10:55 OPEN IT UP TO THE PUBLIC?
 06:10:57 IF NOT --
 06:11:02 >>Jim Wallace: HOWARD, I HAVE ONE QUESTION.
 06:11:04 THE PROPERTY TO THE SOUTH OF -- THE PROPERTY TO THE
 06:11:08 IMMEDIATE SOUTH, YOUR SOUTHERN NEIGHBOR, I WANT LIKE

 06:11:14 CLARIFICATION.
 06:11:14 IS THAT -- YOU KEEP REFERRING TO IT AS A CONSERVATION AREA.
 06:11:20 IS IT A DESIGNATED CONSERVATION AREA OR IS IT JUST VACANT
 06:11:24 LAND THAT MAY BE DEVELOPED SOME DAY.
 06:11:29 >>Dana Hume: I'M SORRY.
 06:11:31 I'LL LET YOU FINISH.
 06:11:32 I APOLOGIZE.
 06:11:33 >>Jim Wallace: THAT'S FINE.

06:11:34 >>Dana Hume: TO THE SOUTH OF US WE HAVE THE CALVARY CHURCH
 06:11:37 WHICH IS RIGHT AT THREE OAKS, AND THEN AS WE HEAD EAST, IT
 06:11:41 IS CALVARY CHURCH AND THEN A BIG CONSERVATION EASEMENT THAT
 06:11:44 IS UNDER A CONSERVATION EASEMENT WITH THE WATER MANAGEMENT
 06:11:48 DISTRICT, AND THEN COMMERCIAL DEVELOPMENT MORE TOWARDS I-75.
 06:11:54 >>Jim Wallace: SO THAT WILL NEVER BE DEVELOPED.
 06:11:55 >>Dana Hume: THAT IS CORRECT.
 06:11:56 I SHOULD HAVE CLARIFIED THAT.
 06:11:59 SO THAT CONSERVATION EASEMENT IS RIGHT THERE WHERE THE
 06:12:02 BUILDING IS AT.
 06:12:04 >>Jim Wallace: THAT'S WHY I'M ASKING.
 06:12:06 THANK YOU.
 06:12:06 >>Dana Hume: ABSOLUTELY.
 06:12:07 ANY OTHER QUESTIONS?
 06:12:25 >>Howard Levitan: CAN YOU HEAR ME NOW?
 06:12:29 >> YES.
 06:12:29 >>Howard Levitan: WE HAD SEVERAL COMMENTS THAT WE RECEIVED

 06:12:35 ABOUT SECOND FORM OF EGRESS.
 06:12:41 I JUST WANTED TO ASK DANA, THERE IS NO ABILITY TO DO ANY
 06:12:50 TYPE OF A SECOND FORM OF ACCESS OR EGRESS FROM THE AREAS TO
 06:12:54 THE SOUTH BECAUSE OF THAT CONSERVATION EASEMENT?
 06:12:56 AM I CORRECT ABOUT THAT?
 06:12:58 >>Dana Hume: WE HAVE ACTUALLY LOOKED AT PROVIDING A
 06:13:01 SECONDARY ACCESS.
 06:13:02 IT WOULD BE FOR EMERGENCY ONLY.
 06:13:05 WE'VE REACHED OUT TO THE CALVARY CHURCH.
 06:13:08 WE HAD SOME CHALLENGES AND SOME REQUESTS THAT THEY HAD.
 06:13:12 WE ARE CERTAINLY WILLING TO LOOK INTO THAT ALONG WITH
 06:13:16 LOOKING AT PROVIDING A SECONDARY, AGAIN, EMERGENCY ACCESS
 06:13:22 ONLY, THAT WOULD GO TO THE WEST AND TIE IN VIA THE LIFT
 06:13:28 STATION ALONG THREE OAKS.
 06:13:30 WE WOULD RESPECTFULLY REQUEST THERE IS THAT -- WE HAVEN'T
 06:13:38 HAD TIME TO LOOK INTO IT.
 06:13:40 MARY AND I JUST HAD THE DISCUSSIONS IN THE LAST COUPLE OF
 06:13:44 DAYS ABOUT THAT.
 06:13:44 SO WE WOULD RESPECTFULLY REQUEST THAT IF YOU WANTED THAT TO
 06:13:49 BE A STIPULATION OF THE DEVELOPMENT ORDER, TO GIVE US TIME
 06:13:52 TO FURTHER INVESTIGATE THAT AND WORK WITH STAFF ON THAT.
 06:13:57 APPROVE THE D.O. AND THEN JUST MAKE THAT A STIPULATION OF
 06:14:00 IT.
 06:14:00 WE WOULD BE OKAY WITH THAT.
 06:14:02 >>Howard Levitan: OKAY.

 06:14:03 I WOULD LIKE TO DO THAT, IF YOU COULD.
 06:14:07 >>Dana Hume: ABSOLUTELY.
 06:14:08 >>Howard Levitan: IF THERE IS A WAY TO GET A SECOND -- EVEN
 06:14:11 IF IT'S AN EMERGENCY EXIT THAT YOU HAVE CONTROL OVER --

06:14:15 >>Dana Hume: YES.
 06:14:15 >>Howard Levitan: WE'VE DONE THAT IN THE PAST IN SEVERAL
 06:14:18 OTHER DEVELOPMENTS WHERE WE'VE CREATED A GATE IN THE
 06:14:24 CHAIN-LINK FENCE TO ALLOW FOR EMERGENCY ACCESS IN THE EVENT
 06:14:29 THERE WAS A PROBLEM WITH THE OTHER ACCESS.
 06:14:32 I THINK THAT'S SOMETHING THAT SHOULD BE DONE.
 06:14:34 >>Dana Hume: KEEPING IN MIND, WE DON'T HAVE A FENCE ALONG
 06:14:38 THREE OAKS PARKWAY.
 06:14:40 WE DID THAT INTENTIONALLY.
 06:14:44 STAFF HAD SOME ISSUES WITH THAT, AND THAT WOULD NOT BE VERY
 06:14:48 AESTHETICALLY PLEASING TO SEE A SIX-FOOT-HIGH CHAIN-LINK
 06:14:52 FENCE ALONG THERE.
 06:14:53 BUT WE WILL WORK WITH STAFF ON CREATING A DEDICATED
 06:14:57 EMERGENCY ACCESS.
 06:14:58 IT WILL HAVE SOME TYPE OF A GATE ASSOCIATED WITH IT, AND
 06:15:03 WOULD ONLY BE UTILIZED DURING AN EMERGENCY SITUATION WHERE
 06:15:07 OUR MAIN ENTRANCE FOR SOME UNFORTUNATE, UNFORESEEN REASON,
 06:15:12 WOULD BE BLOCKED.
 06:15:13 AND I THINK THAT'S VERY PRUDENT.
 06:15:17 >>Howard Levitan: OKAY.
 06:15:18 SOUNDS GOOD.

 06:15:18 DOES ANYBODY ELSE HAVE ANY QUESTIONS OF THE APPLICANT?
 06:15:23 HEARING NONE, MADAM CLERK, DO WE HAVE ANY CARDS FROM THE
 06:15:30 PUBLIC?
 06:15:31 >>Tammy Duran: YES, WE DO.
 06:15:33 WE HAVE ONE.
 06:15:34 MARK STALINSKI.
 06:15:44 >> THANK YOU FOR THE OPPORTUNITY.
 06:15:46 I JUST WANTED TO SAY THAT WE'RE ONE OF THE APPROXIMATELY TEN
 06:15:51 HOMES THAT BASICALLY BACK UP AGAINST THE WEST SIDE OF THREE
 06:15:58 OAKS PARKWAY.
 06:15:59 WE JUST MOVED IN ABOUT FIVE OR SIX MONTHS AGO.
 06:16:02 SO THIS WAS KIND OF OUR DREAM HOME.
 06:16:04 AND WE DO HAVE A POOL IN THE BACKYARD.
 06:16:06 IT'S KIND OF OUR SANCTUARY.
 06:16:08 SO WE'RE VERY CONCERNED, I SHOULD SAY, ABOUT THE NOISE LEVEL
 06:16:12 THAT WE THINK THAT WE'RE GOING TO PROBABLY HAVE.
 06:16:15 IT'S ALREADY PRETTY LOUD WHEN YOU SIT OUT IN THE BACKYARD.
 06:16:18 WE HAVE OTHER NEIGHBORS THAT ARE COMPLAINING AS WELL, AND
 06:16:21 THEY ARE ALSO CONCERNED.
 06:16:22 I THINK THEY COULDN'T BE HERE.
 06:16:23 I'M KIND OF HERE ON THEIR BEHALF AS WELL.
 06:16:26 WE'RE JUST CONCERNED IF THERE IS ANY POSSIBILITY OR IF
 06:16:31 THERE'S ANY KIND OF PLAN OR CONCERN ABOUT THE NOISE LEVEL,
 06:16:36 AND WE DO FEEL LIKE THERE'S GOING TO BE A LOT MORE TRAFFIC.
 06:16:39 WITH 1800 STUDENTS, WE'RE JUST VERY CONCERNED THAT THE NOISE

06:16:44 LEVELS FOR ALL OF US WHO ARE IN THE BACKYARDS AND, AGAIN,
 06:16:48 THAT'S KIND OF OUR PLACE TO FIND PEACE.
 06:16:52 AND IT IS KIND OF A LITTLE BIT OF A WOODED -- THERE IS A
 06:16:56 TREE LINE ANYWAY, AND THAT IS JUST NOT VERY EFFECTIVE AT
 06:17:00 FILTERING THE NOISE.
 06:17:01 SO WE JUST WONDER IF THERE'S ANY POSSIBLE WAY THAT WE COULD
 06:17:04 ASK THE DEVELOPERS OR THE CITY TO LOOK INTO MAYBE SOUND
 06:17:10 BARRIER WALLS OR SOME TYPE -- WHETHER IT'S CONSTRUCTION OR
 06:17:14 SOMETHING NATURAL.
 06:17:16 I'M NOT REALLY SURE WHAT THE POSSIBILITIES ARE.
 06:17:20 MAYBE JUST MOVING AROUND SOME EARTH AND PUTTING TREES OR
 06:17:28 SHRUBS OR SOMETHING ADDITIONALLY UP.
 06:17:30 THERE IS A BIT OF A WOODED AREA.
 06:17:32 THIS IS JUST NORTH OF THE LIBRARY.
 06:17:33 SO WE'RE ONE OF THOSE TEN HOMES.
 06:17:35 AGAIN, WE JUST KIND OF MOVED HERE, AND WE'RE NOT EXPECTING
 06:17:39 TO HAVE THIS LEVEL OF TRAFFIC.
 06:17:41 IT IS ALREADY VERY NOISY.
 06:17:43 PLENTY OF CARS GOING BY THAT ARE VERY LOUD.
 06:17:45 IT SEEMS LIKE THEY ARE REALLY SPEEDING MOST OF THE TIME.
 06:17:48 AND, UNFORTUNATELY, DON'T SEE MUCH BEING DONE WITH THAT
 06:17:52 EITHER TO CONTROL SOME OF THE SPEEDING GOING NORTH AND SOUTH
 06:17:55 THERE IN FRONT OF THE LIBRARY.
 06:17:57 SO IT IS VERY CONCERNING TO US IF WE'RE JUST GOING TO HAVE A
 06:18:00 MUCH MORE TRAFFIC THERE AS WELL.

06:18:02 JUST WORRIED ABOUT NOT JUST OUR PROPERTY AND OUR KIND OF
 06:18:11 PEACE THAT WE HAVE OUTSIDE AT THIS POINT, BUT OUR NEIGHBORS
 06:18:14 AS WELL, AND POSSIBLY, YOU KNOW, NOT JUST THE QUALITY OF
 06:18:18 LIFE, BUT MAYBE EVEN THE NEGATIVE IMPACT ON HOME VALUES.
 06:18:24 AGAIN, THERE'S NOT VERY MANY HOMES.
 06:18:26 WE'RE JUST ONE OF TEN, BUT WE JUST FEEL LIKE WE NEED TO GO
 06:18:31 ON RECORD AND SAY THAT WE'RE CONCERNED ABOUT THE NOISE LEVEL
 06:18:33 AND IF THERE'S ANYTHING THAT CAN POSSIBLY BE DONE OR
 06:18:39 DISCUSSED TO HELP REDUCE THE NOISE LEVEL THAT WE FEEL LIKE
 06:18:41 IS GOING TO BE CONSIDERABLY MORE, JUST ALONG THAT PARTICULAR
 06:18:45 AREA.
 06:18:45 I KNOW THAT THE SCHOOL IS GOING TO BE BACK MORE TOWARDS EAST
 06:18:49 OF THERE.
 06:18:50 THAT'S OUR BACKYARD, BASICALLY.
 06:18:53 WE FEEL LIKE THERE'S GOING TO BE A TON OF TRAFFIC THROUGH
 06:18:55 THERE THAT NORMALLY IT'S KIND OF BAD ENOUGH.
 06:18:57 BUT, AGAIN, WE MAY NOT HAVE MADE THAT DECISION TO MOVE THERE
 06:19:00 IF WE HAD SEEN WHAT WE FEEL IS GOING TO BE MUCH MORE
 06:19:04 TRAFFIC.
 06:19:04 AND I THINK OTHER PEOPLE ARE ALSO KIND OF THE SAME MINDSET.
 06:19:11 CONCERNED ABOUT THAT.
 06:19:12 AGAIN, WE GO OUT THERE TO ENJOY OUR POOL.

06:19:15 WHETHER WE HAVE A POOL OR NOT, IT'S A PLACE WE CAN KIND OF
06:19:18 SIT AND JUST, YOU KNOW, GET AWAY FROM SOME OF THE NOISE OF
06:19:22 LIFE AND THEN NOW WE'RE GOING TO BE BRINGING MUCH MORE

06:19:26 TRAFFIC DIRECTLY BEHIND.
06:19:27 AND WE'RE TALKING ABOUT 50 FEET AWAY FROM OUR POOL.
06:19:33 THIS IS VERY CLOSE, AND IT'S ALREADY KIND OF AN ECHO CHAMBER
06:19:38 AS IT IS.
06:19:39 SO WE WANTED TO BE ON RECORD.
06:19:43 THIS IS SEVERAL NEIGHBORS THAT WANTED TO COME, AND THEY ARE
06:19:46 VERY CONCERNED AS WELL.
06:19:47 THEY JUST COULDN'T BE HERE.
06:19:49 THAT'S ALL I WANTED TO SAY.
06:19:51 THANK YOU FOR THE TIME.
06:19:53 >>Howard Levitan: THANK YOU.
06:19:53 >>Mary Gibbs: MAY I ASK A QUESTION, THOUGH.
06:19:56 I AM CONFUSED.
06:19:57 ARE YOU IN COPPER OAKS OR COUNTRY OAKS?
06:20:00 >> VILLAGE OF COUNTRY CREEK.
06:20:02 >>Mary Gibbs: COUNTRY CREEK, THAT'S WHAT I MEANT.
06:20:03 YOU'RE ON THE OTHER SIDE OF THREE OAKS PARKWAY.
06:20:06 >> ON THE WEST SIDE OF THREE OAKS, BUT WE GET ALL -- SEEMS
06:20:09 LIKE NOISE IS ECHOED RIGHT THERE.
06:20:13 YEAH, JUST CONCERNED WITH THE PEOPLE WHO SHARE A BACKYARD
06:20:16 THAT FACES WHERE THE SCHOOL IS BASICALLY I BELIEVE THE
06:20:20 ENTRANCE AND THE EXIT FROM WHAT IT LOOKED LIKE ON THE MAPS
06:20:22 IS GOING TO BE RIGHT THERE.
06:20:26 THE EVENTS, NOT JUST THE DAILY TRAFFIC, BUT THE EVENTS, THE
06:20:32 SPORTS, THINGS LIKE THAT, THAT MIGHT JUST BRING A LOT MORE

06:20:36 NOISE, ESPECIALLY IN THE EVENINGS, PERHAPS, AND THOSE ARE
06:20:40 TIMES WHERE WE LIKE TO -- PART OF THE REASON WHY WE LOVE
06:20:43 THAT NEIGHBORHOOD, THAT AREA, THAT HOUSE WAS THE BACK WAS
06:20:47 KIND OF A SANCTUARY.
06:20:48 I KNOW IT'S UP AGAINST A FAIRLY BUSY STREET, BUT NOW IT
06:20:51 SEEMS LIKE IT'S GOING TO BE A LOT BUSIER.
06:20:53 WE JUST WONDERED IF THERE WAS ANYTHING.
06:20:58 >>Jim Wallace: IS THE HOUSE IN COPPER OAKS OR COUNTRY CREEK?
06:21:00 >>Mary Gibbs: COUNTRY CREEK.
06:21:02 >> COUNTRY CREEK.
06:21:04 >>Mary Gibbs: THAT'S WHY I WAS CONFUSED.
06:21:05 >>Jim Wallace: YOU'RE ON THE WEST SIDE OF THREE OAKS
06:21:08 PARKWAY.
06:21:10 >>Mary Gibbs: I JUST WAS GOING TO SAY WHEN COPPER OAKS, WHEN
06:21:13 THIS CAME BEFORE WHEN WE WERE DOING THE COMPREHENSIVE PLAN
06:21:17 ITEM, THE QUESTION CAME UP FROM COPPER OAKS THAT PEOPLE THAT
06:21:20 WERE ADJACENT TO, COULD THERE BE A WALL.
06:21:22 WE BROUGHT THAT ISSUE UP.

06:21:24 WE HAD A LONG DISCUSSION WITH THE SCHOOL.
 06:21:26 THE SCHOOL DISTRICT STAFF.
 06:21:28 BUT BECAUSE OF SECURITY REASONS, THEY DON'T DO -- WE TALKED
 06:21:31 ABOUT A BERM AND A WALL, AND THEY ARE LIKE WE CAN'T DO THAT
 06:21:34 BECAUSE OF SECURITY REASONS.
 06:21:35 ACTIVE SHOOTERS, THINGS LIKE THAT.
 06:21:38 SO COPPER OAKS, WE HAVE KIND OF THE STAGGERED HEIGHTS OF THE

 06:21:42 TREES BECAUSE THEY ARE IMMEDIATELY ADJACENT TO THE BUS LOOP.
 06:21:47 YOU'RE ON THE OTHER SIDE, SO YOU'VE GOT REALLY THE NOISE OF
 06:21:49 THE ROAD.
 06:21:51 >> YEAH, THIS WAS MORE THE TRAFFIC, THE INCREASED TRAFFIC
 06:21:53 THAN IT WAS THE ACTIVITIES, THE EVENTS, THE GAMES, STUFF
 06:21:57 LIKE THAT, YEAH.
 06:22:01 >>Howard Levitan: THANK YOU.
 06:22:02 >>Tammy Duran: THAT'S ALL WE HAVE.
 06:22:03 >>Howard Levitan: THANK YOU VERY MUCH.
 06:22:04 I'LL ASK, AGAIN, DOES ANYBODY ELSE FROM THE PUBLIC WANT TO
 06:22:09 SPEAK ON THIS MATTER?
 06:22:10 HEARING NONE, I WILL CLOSE THE PUBLIC HEARING.
 06:22:15 SINCE THIS HAS SOME COMPLEXITY TO IT, PERHAPS WE SHOULD GO
 06:22:22 AROUND AND I'LL CALL ON ANTHONY FIRST, AND WE'LL GO AROUND
 06:22:26 AND HAVE EVERYBODY MAKE WHATEVER COMMENTS THEY WOULD LIKE TO
 06:22:30 THE WAY WE ARE ON THIS.
 06:22:31 ANTHONY, WOULD YOU LIKE TO START OFF, PLEASE?
 06:22:36 >>Anthony Gargano: SURE.
 06:22:36 WHEN THIS MATTER ORIGINALLY CAME BEFORE THE PLANNING AND
 06:22:40 ZONING BOARD, I WAS THE LONE VOTE AGAINST IT.
 06:22:45 I SAID AT THE TIME I THOUGHT THIS WAS GOING TO CREATE A
 06:22:50 TRAFFIC NIGHTMARE IN THAT AREA, AND WAS GOING TO BE A
 06:22:55 DISSERVICE TO THE RESIDENTS OF ESTERO.
 06:22:57 MY VIEW HASN'T CHANGED.
 06:23:01 I'M NOT ANTI-SCHOOL.

 06:23:03 I'M IN FAVOR OF SCHOOLS PROPERLY SITED AND IN THE CORRECT
 06:23:09 LOCATIONS.
 06:23:10 I APPRECIATE THE EFFORTS THAT THE SCHOOL BOARD HAS TAKEN TO
 06:23:14 TRY AND MITIGATE EVEN THE PROBLEM THAT THEY PERCEIVE, WHICH
 06:23:19 IS GOING TO BE A TRAFFIC PROBLEM.
 06:23:24 LET'S BE REALISTIC.
 06:23:25 AN 8:55 STARTING TIME TO GET THE KIDS THERE IN TIME FOR THE
 06:23:31 STARTING TIME IS GOING TO MEAN CARS IN PEAK TRAFFIC ALONG
 06:23:37 THREE OAKS.
 06:23:39 AND THE 3:55 CLOSING TIME, REALISTICALLY, BY THE TIME THE
 06:23:45 KIDS ARE COLLECTED, PICKED UP WILL DUMP TRAFFIC DURING PEAK
 06:23:49 HOUR ONTO THREE OAKS.
 06:23:50 IS MY POSITION HAS BEEN CONSISTENT ALL ALONG.
 06:23:55 I THINK THIS IS POOR PLANNING.

06:23:58 AND I CANNOT SUPPORT WHAT'S BEING PROPOSED HERE.
 06:24:05 >>Howard Levitan: THANK YOU, ANTHONY.
 06:24:06 KRISTIN.
 06:24:09 >>Kristin Jeannin: I DON'T HAVE ANY COMMENTS RIGHT NOW.
 06:24:10 >>Howard Levitan: OKAY.
 06:24:11 MARLENE.
 06:24:13 >>Marlene Naratil: YES, I HAVE COMMENTS ON THE VARIATIONS
 06:24:17 THAT DANA SPOKE OF.
 06:24:19 I AGREE THAT SOME OF THEM REALLY ARE NOT PERTINENT TO THE
 06:24:25 NEEDS OF THE SCHOOL.
 06:24:27 FOR EXAMPLE, THESE ELECTRONIC -- ELECTRIC FILLING STATIONS.

 06:24:35 IF TEACHERS OR STAFF AT THAT SCHOOL HAVE MANY PLACES THEY
 06:24:39 CAN GET THEIR CAR CHARGED.
 06:24:40 THEY ARE NOT GOING TO NECESSARILY -- AND WHY SHOULD THE
 06:24:43 TAXPAYERS PROVIDE THAT FOR THEM?
 06:24:47 AND I THINK SOME OF THE OTHER ARCHITECTURAL THINGS THAT DANA
 06:24:51 BROUGHT UP REALLY ARE NOT JUSTIFIED TO FORCE YOU TO DO IT.
 06:25:00 I WOULD LIKE TO SEE SOME CHANGES IN THAT.
 06:25:02 >>Howard Levitan: THANK YOU.
 06:25:03 MICHAEL.
 06:25:06 >>Michael Sheeley: THANK YOU.
 06:25:06 I THINK THAT THE SCHOOL DISTRICT HAS DONE ABOUT ALL WE CAN
 06:25:13 ASK THEM TO DO ON THIS PROJECT.
 06:25:16 AND I APPRECIATE THE EFFORTS THAT THEY HAVE MADE IN REGARDS
 06:25:18 TO THE ARCHITECTURE OF THE BUILDING AND THERE ARE ATTEMPTS
 06:25:25 TO MEET THE CODE AND STILL KEEP THE BUILDING ECONOMICAL AND
 06:25:29 ALSO GIVEN THE FACT THAT IT IS 1400 FEET OFF OF THREE OAKS.
 06:25:35 I THINK IT'S FINE.
 06:25:36 IT'S SATISFACTORY.
 06:25:37 I DO APPRECIATE ANTHONY'S COMMENTS REGARDING TRAFFIC,
 06:25:41 ET CETERA, AND I THINK THAT IS AN ISSUE BUT I STILL WOULD
 06:25:45 SUPPORT THIS PROJECT.
 06:25:47 >>Howard Levitan: THANK YOU.
 06:25:48 JIM TATOOLES.
 06:25:49 >>James Tatooles: I ALSO THINK THAT THERE'S GOING TO BE SOME
 06:25:53 PROBLEMS WITH THE TRAFFIC WITH THAT MANY CARS, WITH THAT

 06:25:57 MANY STUDENTS, THAT'S INEVITABLE AND THERE'S NOT MUCH YOU
 06:26:02 CAN DO ABOUT IT.
 06:26:03 I DO THINK, THOUGH, THEY HAVE REALLY WORKED HARD TO TRY TO
 06:26:06 ALLEVIATE THAT BY HAVING DROP-OFF LANES ON THE SCHOOL
 06:26:12 PROPERTY RATHER THAN HAVING IT ON THE SIDE OF THE ROAD.
 06:26:15 SO I THINK THAT THEY MADE AS GOOD AN EFFORT AS THEY POSSIBLY
 06:26:20 CAN TO ALLEVIATE THE SITUATION.
 06:26:22 I WAS ALSO IMPRESSED WITH THE DEVIATIONS THAT WERE MADE AND
 06:26:27 THE REASONS THAT THEY WERE MADE.
 06:26:29 SO I THINK THAT THERE'S A LOT OF EFFORT TO TRY TO MAKE THIS

06:26:34 AS -- AS NANCY SAID, CONFORMING WITH THE TWO DIFFERENT
 06:26:40 REQUIREMENTS.
 06:26:41 AND I THINK THEY'VE DONE A GREAT JOB FOR THAT.
 06:26:44 >>Howard Levitan: THANK YOU, JIM.
 06:26:45 JIM WALLACE.
 06:26:49 >>Jim Wallace: MAYBE I TAKE A DIFFERENT SLANT THAN EVERYBODY
 06:26:53 ELSE ON THE ELECTRICAL VEHICLES.
 06:26:54 BUT IF I WAS A NORMAL EMPLOYER, AND I WAS GOING TO BUILD A
 06:27:00 BUILDING, I WOULD, I THINK, BE EXPECTED TO PROVIDE CHARGING
 06:27:08 STATIONS FOR MY STAFF.
 06:27:10 SO I DON'T THINK THAT THAT DEVIATION SHOULD BE GIVEN TO THE
 06:27:14 SCHOOL.
 06:27:15 I THINK THEY SHOULD BE TREATED LIKE A REGULAR EMPLOYER.
 06:27:20 I HAVE TO COMPLIMENT THE SCHOOL BOARD ON EMBRACING SOME OF
 06:27:28 THE THINGS WE ASKED FOR LANDSCAPING AND EVERYTHING ELSE.

 06:27:33 HOWEVER, I MUST SAY THAT EVEN THOUGH I'M ENCOURAGED THAT YOU
 06:27:38 MADE SOME CHANGES, I'M DISAPPOINTED IN THE ARCHITECTURE.
 06:27:41 IT'S STILL JUST A BIG BOX.
 06:27:45 THE PARAPET WAS NOT -- I THINK THE ENHANCEMENTS OF THE
 06:27:48 PARAPET WERE NOT REALLY CREATIVE.
 06:27:51 IT REMINDS ME, UNFORTUNATELY, OF A BUILDING ON WILLIAMS
 06:27:55 ROAD, A HIGH SCHOOL THAT TO ME IS AN EYESORE FOR ESTERO, AND
 06:28:00 IT HAS SOME OF THE SAME CREATIVE ELEMENTS, AND IT -- AND
 06:28:07 IT'S TO ME A DISAPPOINTMENT FOR ESTERO.
 06:28:09 I THINK WE COULD DO BETTER.
 06:28:10 I KNOW WE COULD DO BETTER.
 06:28:12 THE ARTICULATION OF THE WALLS, THEY ARE ASKING A HUNDRED
 06:28:17 FEET, 150 FEET.
 06:28:18 THERE ARE COUNTIES IN FLORIDA THAT HAVE -- THAT REQUIRE THAT
 06:28:21 ARTICULATION EVERY 50 FEET.
 06:28:23 SO I DON'T THINK THAT ESTERO HAS BEEN OVERLY DEMANDING TO
 06:28:27 HAVE DONE IT A COUPLE OF TIMES TO SAY, WELL, WE'RE GOING TO
 06:28:30 DO IT ON THE WESTERN ELEVATIONS, BUT THE OTHER ELEVATIONS
 06:28:35 DON'T REQUIRE OR WE'RE NOT GOING TO DO IT BECAUSE IT'S A
 06:28:38 COST ELEMENT.
 06:28:39 I DON'T KNOW WHAT THE TOTAL COST OF THIS SCHOOL IS, BUT I
 06:28:41 THINK IT'S PROBABLY FAIRLY SUBSTANTIAL.
 06:28:44 AND I THINK ARCHITECTURALLY, YOU COULD HAVE GONE MUCH
 06:28:48 FURTHER, AND I WOULD LIKE TO HAVE SEEN THAT.
 06:28:53 >>Howard Levitan: THANK YOU, JIM.

 06:28:53 BARRY JONES.
 06:28:55 BARRY, ARE YOU HERE?
 06:29:01 >>Barry Jones: YES.
 06:29:02 I UNDERSTAND HOW CHALLENGING SITING CAN BE, AND WITH WHAT
 06:29:08 THEY HAVE TO WORK WITH AND THE LAND AVAILABILITY WITHIN
 06:29:12 PROXIMITY OF THE DEMAND, I THINK THAT IS A GOOD LOCATION FOR

06:29:15 THE SCHOOL.
 06:29:16 SOMETIMES IT'S A MATTER OF LESSER EVILS, AND I THINK THEY
 06:29:21 HAVE DONE A GOOD JOB OF SETTING THE PROJECT BACK TO ALLOW
 06:29:25 THE STACKING TO GET THE PEOPLE OUT OF THREE OAKS.
 06:29:30 IT WILL BE INTERESTING TO SEE IF IT WORKS AS PLANNED.
 06:29:32 I HAVE NO OBJECTION TO THE PROJECT.
 06:29:36 I WISH THAT WE HAD BETTER CONTROL OVER THE ARCHITECTURAL,
 06:29:41 AND I AGREE WITH JIM THAT THE OVERALL DIFFERENTIAL IN PRICE
 06:29:46 TO CREATE SOME OF THE COLOR AND OFFSETS THAT WE TYPICALLY
 06:29:52 REQUIRE FROM A DEVELOPER WOULD BE INSIGNIFICANT TO THE TOTAL
 06:29:55 COST.
 06:29:57 IT WOULD BE INTERESTING TO KNOW WHAT THAT PERCENTAGE IS.
 06:30:02 I DON'T KNOW THAT IT'S GOING TO MATTER BECAUSE I THINK NANCY
 06:30:05 SAID WE DON'T HAVE ABILITY TO ENFORCE THAT SORT OF CONTROL.
 06:30:09 THOSE ARE MY THOUGHTS.
 06:30:12 >>Howard Levitan: THANK YOU.
 06:30:12 SCOTTY, WOULD YOU LIKE TO WEIGH IN?
 06:30:17 >>Scotty Wood: YES, I WOULD.
 06:30:18 THANK YOU.

 06:30:18 I THINK MOST OTHER MEMBERS OF THE BOARD HAVE COVERED VARIOUS
 06:30:28 POINTS.
 06:30:29 ANTHONY'S POINT REGARDING TRAFFIC, YES, I'M ALSO CONCERNED.
 06:30:33 BUT HE MADE THE POINT ABOUT ANOTHER SITE, AND I JUST DON'T
 06:30:38 KNOW OF ANOTHER SITE.
 06:30:39 WE LOOKED LONG AND HARD AT SITING IT NEAR ESTERO HIGH
 06:30:44 SCHOOL, AND CLEARLY THAT AVAILABLE LAND WAS INSUFFICIENT BY
 06:30:49 A WIDE MARGIN FOR THIS PROJECT.
 06:30:52 SO, UNFORTUNATELY, I THINK WE JUST HAVE TO LIVE WITH WHAT WE
 06:30:57 HAVE.
 06:30:58 AND I THINK THE SCHOOL BOARD HAS DONE A PRETTY GOOD JOB OF
 06:31:03 GETTING A LONG QUEUEING ROADWAY, IF YOU WILL, TO TRY AND
 06:31:09 HANDLE THE TRAFFIC THAT WILL INEVITABLY OCCUR.
 06:31:15 I ALSO SHARE THE OPINION THAT THERE'S A LIMITED AMOUNT OF
 06:31:20 REQUIREMENTS THAT WE CAN IMPOSE UPON THE SCHOOL DISTRICT
 06:31:24 BECAUSE OF THE STATUTES AND THE DIFFERENTIALS THAT NANCY HAS
 06:31:29 DESCRIBED.
 06:31:30 I SUPPORT THE PROJECT, BUT I WOULD LIKE TO HAVE THE
 06:31:35 EMERGENCY ACCESS STIPULATION AS PART OF THE MOTION TO
 06:31:40 APPROVE THIS BECAUSE I THINK THAT EMERGENCY ACCESS FOR A
 06:31:45 SITE THIS SIZE, IT IS POTENTIALLY A TARGET RISK DOWN THE
 06:31:52 ROAD.
 06:31:52 AND I THINK IT'S IMPERATIVE THAT WORK BE DONE WHILE THE
 06:31:57 SCHOOL IS BEING BUILT TO IDENTIFY AN EMERGENCY SITE --
 06:32:03 EMERGENCY ACCESS SITE, AND THE VILLAGE SHOULD DO WHATEVER IT

 06:32:08 CAN TO ASSIST THE SCHOOL DISTRICT IN FINDING SUCH EMERGENCY
 06:32:13 ACCESS.

06:32:14 I THINK IT'S A HIGH PRIORITY.
 06:32:15 THAT'S ALL I HAVE.
 06:32:19 >>Howard Levitan: THANK YOU, SCOTTY.
 06:32:20 I HAVE A FEW COMMENTS.
 06:32:24 FIRST, THE SCHOOL HAS PLANNED FOR THIS SITE FOR AS LONG AS I
 06:32:29 HAVE BEEN IN ESTERO, WHICH IS A LOT OF YEARS.
 06:32:31 SO WHILE I SYMPATHIZE WITH THE FOLKS THAT ARE IN BOTH
 06:32:38 COUNTRY CREEK AND THE OTHER NEARBY COMMUNITY, EVERYBODY SORT
 06:32:45 OF KNEW THAT THERE WAS A GOOD CHANCE THAT THIS WAS GOING TO
 06:32:48 BE A SCHOOL SITE.
 06:32:49 SCOTTY IS ABSOLUTELY CORRECT THAT WHEN COUNCIL LOOKED AT
 06:32:56 SITING THIS AT THE WILLIAMS ROAD SITE WITH A HIGH SCHOOL,
 06:33:01 CAN YOU IMAGINE THE TRAFFIC ON THAT ROAD WHICH WOULD NEVER
 06:33:07 HAVE BEEN ABLE TO HANDLE AN ADDITIONAL 2,000 KIDS A DAY.
 06:33:15 SO I THINK WE'RE WELL PAST THAT.
 06:33:18 COUNCIL HAS ASKED THAT IT BE HERE AT THIS SITE, IF IT'S
 06:33:22 GOING TO BE ANYWHERE.
 06:33:23 AND THEN I GET TO THE AREAS OF THE REQUESTED VARIATIONS FROM
 06:33:30 OUR LAND DEVELOPMENT CODE.
 06:33:33 ONE OF THE THINGS THAT NANCY DID MENTION, BUT IF YOU LOOK
 06:33:38 CAREFULLY AT WHAT THE STATE STATUTE SAYS, IT REQUIRES THE
 06:33:40 SCHOOL DEPARTMENT TO BUILD, TO MAKE -- AND THIS IS A QUOTE
 06:33:46 -- FRUGAL PRODUCTION OF HIGH-QUALITY PRODUCTS.

 06:33:50 FRUGAL PRODUCTION.
 06:33:52 I DON'T KNOW WHAT THAT MEANS, BUT I WILL SAY THIS.
 06:33:56 I THINK THE STATE LEGISLATURE HAS CLEARLY SAID TO US THAT
 06:34:01 MONEY IS A FACTOR, AND THAT WE ARE REQUIRED UNDER THE STATE
 06:34:07 STATUTES AND THE RULES TO MAKE REASONABLE ACCOMMODATIONS TO
 06:34:10 THE SCHOOL DEPARTMENT, PARTICULARLY IN THE AREA OF SAFETY.
 06:34:15 SO OF ALL OF THESE VARIATIONS, SOME LIKE THE LANDSCAPING
 06:34:21 WILL BE DEALT WITH ADMINISTRATIVELY BY MARY WITHIN HER
 06:34:25 POWERS.
 06:34:29 SAFETY RELATED.
 06:34:30 A LOT OF THEM ARE SAFETY RELATED.
 06:34:32 AND EVEN SOME OF THE ARCHITECTURAL CONCERNS ARE, IF YOU LOOK
 06:34:35 AT THE STATUTE, ARE SAFETY RELATED.
 06:34:37 THEY ARE ALMOST REQUIRED TO HAVE TILT-UP CONCRETE WALLS FOR
 06:34:42 SAFETY PURPOSES AS WELL.
 06:34:44 IT SAYS, FOR EXAMPLE, THAT YOU CAN'T ALLOW FOOT HOLDS OR
 06:34:50 HAND HOLDS IN THE EXTERIOR WALLS, AND YOU CAN'T ALLOW
 06:34:54 ANYBODY TO HAVE ACCESS TO THE ROOF.
 06:34:58 SO I THINK WE'VE BEEN PRETTY WELL PREEMPTED FROM THE THINGS
 06:35:03 THAT WE NORMALLY ASK FOR IN OUR CODE.
 06:35:08 I THINK THE SCHOOL DEPARTMENT HAS MADE GOOD ACCOMMODATIONS
 06:35:12 AND HAVE GIVEN US THE THINGS THAT WE ABSOLUTELY HAVE ASKED
 06:35:16 FOR AND NEEDED.
 06:35:18 I'M DISAPPOINTED WITH THE ARCHITECTURE.

06:35:21 IT LOOKS VERY MUCH LIKE AN INSTITUTIONAL BUILDING.

06:35:23 IT IS NOT WITHIN OUR ARCHITECTURAL GUIDELINES.

06:35:25 THE COLORS WILL BE A HELP.

06:35:28 I THINK THE SCHOOL DEPARTMENT COULD HAVE DONE MORE ABOUT IT,

06:35:31 BUT I THINK WE'RE OBLIGATED TO MAKE REASONABLE ACCOMMODATION

06:35:35 HERE, AND I THINK THAT WE SHOULD DO THAT.

06:35:38 AND I AGREE WITH SCOTTY THAT THE EMERGENCY EXIT OR ENTRANCE

06:35:45 IS VERY IMPORTANT.

06:35:47 SO I WOULD ASK THAT THAT BE IN THE FINAL VOTE.

06:35:51 SO IF THERE IS NOTHING FURTHER, I WILL ACCEPT A MOTION TO

06:35:55 APPROVE THIS SUBJECT TO THE MATTERS THAT WE'VE DISCUSSED AND

06:36:01 THE SCHOOL COMMITTEE, THAT DANA HAS ADDED, PARTICULARLY THE

06:36:04 LIGHT FIXTURE ASPECTS.

06:36:07 >>Mary Gibbs: MAY I ADD ONE THING?

06:36:09 >>Howard Levitan: SURE.

06:36:09 >>Mary Gibbs: IN THE STAFF REPORT, IN THE CONDITIONS THAT

06:36:12 DANA HUME REFERRED TO THAT THEY AGREE WITH, THAT WE HAVE

06:36:16 THREE STIPULATIONS.

06:36:19 ONE OF THEM IS THAT THEY HAVE TO DO CONSTRUCTION ACTIVITY

06:36:22 MANAGEMENT PLAN SO THAT ONCE THEY START BUILDING, WE WILL

06:36:27 HAVE A LIAISON PERSON.

06:36:28 AND THEY DO THIS -- THIS IS A STANDARD THING THAT THEY DO

06:36:31 ALL THE TIME ANYWAY.

06:36:32 BUT WE WANT TO MAKE SURE FOR THE NEIGHBORS THAT WE HAVE --

06:36:35 WE KNOW WHO TO CALL WHEN THERE ARE ISSUES.

06:36:37 SO WE'VE PUT A STIPULATION IN THAT THEY HAVE TO DO THAT

06:36:40 CONSTRUCTION ACTIVITY MANAGEMENT PLAN FOR US.

06:36:44 AND IT'S IN OUR CODE AS WELL.

06:36:46 THEN WE ALSO PUT, EVEN THOUGH IT'S IN THE CODE, ELECTRONIC

06:36:49 SIGNS ARE NOT ALLOWED, BUT WE WANTED TO MAKE SURE THAT THAT

06:36:53 IS VERY OBVIOUS BECAUSE THE COUNTY DOES ALLOW SOME.

06:36:57 AND THEN NO SIGNAGE -- I THINK MAYBE BARRY JONES BROUGHT

06:37:02 THIS UP AT A PRIOR MEETING -- NO SIGNAGE ON THE FENCES THAT

06:37:05 ARE VISIBLE.

06:37:06 SO YOU DON'T WANT TO BE DRIVING DOWN, LIKE IF YOU DRIVE UP

06:37:09 THREE OAKS AND YOU SEE THREE OAKS MIDDLE SCHOOL ALL THE

06:37:12 ADVERTISING ON THE CHAIN-LINK FENCE.

06:37:14 SO WE HAVE NO SIGNAGE ON THE FENCE THAT'S VISIBLE.

06:37:17 >>Howard Levitan: MAYBE THEY CAN AGREE TO TAKE THOSE DOWN

06:37:21 TOO.

06:37:22 WILLIAMS ROAD WOULD LOVE IT.

06:37:26 OKAY.

06:37:27 WITH THAT -- WITH THOSE STIPULATIONS, PLUS THE EMERGENCY

06:37:34 EXIT CONDITION, MAY I HAVE A MOTION TO APPROVE.

06:37:40 >>Jim Wallace: HOWARD IS THIS A MOTION TO APPROVE ALL OF THE

06:37:42 DEVIATIONS?

06:37:46 >>Howard Levitan: THE MOTION IS TO APPROVE THE DEVELOPMENT
 06:37:48 ORDER AS HAS BEEN PRESENTED WITH THE CONDITIONS THAT THE
 06:37:53 STAFF AND WE HAVE RAISED, YES.
 06:38:00 >>Michael Sheeley: MR. CHAIRMAN, I'LL MAKE THAT MOTION WITH
 06:38:02 THE STIPULATIONS THAT MARY TALKED ABOUT AND THE VARIATIONS

 06:38:06 AND THE EMERGENCY ACCESS.
 06:38:06 >>Howard Levitan: THANK YOU.
 06:38:07 IS THERE A SECOND?
 06:38:09 >>Kristin Jeannin: I'LL SECOND.
 06:38:10 >>Howard Levitan: OKAY.
 06:38:11 MADAM CLERK, WOULD YOU CALL THE ROLL?
 06:38:15 >>Anthony Gargano: NO.
 06:38:18 >>Kristin Jeannin: YES.
 06:38:20 >>Barry Jones: YES.
 06:38:22 >>Marlene Naratil: YES.
 06:38:24 >>Michael Sheeley: YES.
 06:38:26 >>James Tatoes: YES.
 06:38:28 >>Jim Wallace: NO.
 06:38:31 >>Howard Levitan: YES.
 06:38:33 >>Scotty Wood: YES.
 06:38:36 >>Howard Levitan: THE MOTION CARRIES.
 06:38:37 THANK YOU VERY MUCH, DANA, AND YOUR WHOLE TEAM.
 06:38:40 APPRECIATE THAT.
 06:38:41 OKAY.
 06:38:44 LET'S MOVE ON, IF WE CAN.
 06:38:46 >>Dana Hume: THANK YOU FOR YOUR TIME TONIGHT, AND THANK YOU
 06:38:48 TO STAFF FOR HELPING US ALONG THROUGH THIS CHALLENGE.
 06:38:52 WE REALLY APPRECIATE IT.
 06:38:54 THANK YOU.
 06:38:54 >>Howard Levitan: THANK YOU.

 06:38:54 NOW IS THE OPPORTUNITY FOR ANYBODY IN THE PUBLIC TO TALK TO
 06:39:01 US ABOUT NON-AGENDA ITEMS.
 06:39:04 IS THERE ANYBODY THAT HAS A CARD IN OR WOULD LIKE TO SPEAK?
 06:39:10 >>Tammy Duran: WE DON'T HAVE ANYONE.
 06:39:12 >>Howard Levitan: IT LOOKS LIKE EVERYONE IS LEAVING.
 06:39:14 >>Tammy Duran: NO, HE DOESN'T WANT TO TALK.
 06:39:16 >>Howard Levitan: OKAY.
 06:39:16 THANK YOU.
 06:39:17 THEN WE'LL MOVE ON TO BOARD COMMUNICATIONS.
 06:39:20 THE NEXT MEETING IS NOVEMBER 9, UNLESS, MARY, IF YOU HAVE
 06:39:24 ENOUGH FOR AN INTERIM MEETING.
 06:39:26 >>Mary Gibbs: NO.
 06:39:28 NOVEMBER 9, AT THE MOMENT, WE HAVE, I THINK, ONE INFORMATION
 06:39:32 MEETING AND ONE DEVELOPMENT ORDER FOR SURE.
 06:39:34 WE MAY HAVE -- WE MAY HAVE ONE OR TWO OTHER THINGS.
 06:39:38 >>Howard Levitan: OKAY.

06:39:38 DOES ANYBODY ELSE HAVE ANYTHING THEY WOULD LIKE TO ADDRESS
06:39:42 THE BOARD?
06:39:42 IF NOT, I'LL ACCEPT A MOTION TO ADJOURN AND THANK YOU,
06:39:47 EVERYBODY.
06:39:49 >>Michael Sheeley: SO MOVED.
06:39:51 >>Kristin Jeannin: THANK YOU.
06:39:51 SECOND.
06:39:52 >>Howard Levitan: ALL IN FAVOR?
06:39:55 [SOUNDING GAVEL]
06:39:55 WE'RE ADJOURNED.
06:39:56

DISCLAIMER:
THIS FILE REPRESENTS AN UNEDITED VERSION OF REALTIME
CAPTIONING WHICH SHOULD NEITHER BE RELIED UPON FOR COMPLETE
ACCURACY NOR USED AS A VERBATIM TRANSCRIPT.
ANY PERSON WHO NEEDS A VERBATIM TRANSCRIPT OF THE
PROCEEDINGS MAY NEED TO HIRE A COURT REPORTER.



APPLICATION REQUEST FOR PLANNING ZONING AND DESIGN BOARD PUBLIC INFORMATION MEETING IN THE VILLAGE OF ESTERO

REQUEST IS FOR: Public Information Meeting pursuant to Land Development Code.

1. Applicant/Project Name: TRUIST Bank
2. Address: 20280 GRAND OAKS SHOPPES BLVD
3. Strap Number: 25-46-25-E4-10000.001
4. Application Number: _____

5. Type of Application (check appropriate type(s)):

- | | |
|--|---|
| ☐ Comprehensive Plan Amendment | ☐ Planned Development Zoning |
| ☐ Planned Development –Amendment or Final Plan Approved | ☐ Variance |
| ☐ Conventional Rezoning | ☐ Special Exception |
| ☐ Plat | ☐ Vacation |
| ☒ Other <u>Sign approval</u> | ☐ Development Order |
- (Specify)

6. Project Description (Brief description of project and need for application.)

BANK NAME CHANGE / REMOVE ALL EXISTING SIGNAGE /
INSTALL (1) NEW MONUMENT SIGN / (2) NEW WALL SIGNS /
(4) NEW DIRECTIONAL SIGNS

7. Application shall be accompanied by an electronic copy of the site plans drawn to scale, illustrating a detailed overview of the project. The plans shall define what is being requested and the deviation or change from the permitted and/or existing conditions.

Signature [Signature]
Printed Name LANCE O'IS

Date 9/30/21
Email/Phone lance@signpermitsplus.com
941-219-9062

THE VILLAGE OF ESTERO
DEPARTMENT OF COMMUNITY DEVELOPMENT
9401 CORKSCREW PALMS CIRCLE
ESTERO, FLORIDA 33928
PHONE (239) 221-5036

SITE PLAN

Key	Existing Sign	Recommended Sign
E01	Monument Sign	Custom Monument
E02	Wall Sign	LILPFTC24
E03	Wall Sign	LILPFTC24
E04	Directional	D4
E05	Directional	D4
E06	Directional	D4
E07	Directional	D4
E08	DOT - Stop Sign	Leave As Is
E09	Handicap Parking	Leave As Is
E10	Clearance	C2
E11	ATM-EMC	LD1
E12	Bollards	Bc460
E13	Bollards	Bc660
E14	ATM	Topper DT
E15	Door Vinyl	V-1 Double, V-1C, V-2, V-1a, V-7, V-10
E16	Branded Banner	Remove Insert
E17	Wall Banner	Remove

*E08 - E17 NO PERMIT
REQUIRED*






 COPYRIGHT © This drawing is the property of Perimeter Group of Companies. No part of this drawing may be reproduced or transmitted in any form or by any means electronic or mechanical, including photocopying and recording, or by any information storage or retrieval system, without the prior written permission of Perimeter Group of Companies.

2035 Lakeside Centre Dr Suite 250
 Knoxville, TN 37922
 T+865 692 4058 F+865 692 4104

TRUIST 

Site ID: 100991	Drawn By: AKW
Client: Truist	Checked By: N/A
Project: Re-brand	Scale: N/A
Title: 20280 Grande Oak Shoppes Blvd	Revision: Permit
Date: 09/30/21	Page: 5

LOCATION - E01
PROPOSED



Action:	Remove and replace monument as per code
Sign Type:	Custom Monument
Description:	Architectural monument with purple alum. faces & lit 3" deep channel letters
Repair Action:	Sleeve onto existing steel
Signage Text:	Truist with Monogram and Address Numerals
Comments:	Monument required to have 25% architectural features per code 4" address numerals required on base

EXISTING	Quantity:	1 D/S
Height:	8' 1 1/2"	Available Height: 8' 8 1/2"
Width:	8'	Available Width: 11' 3"


COPYRIGHT © The details shown on this drawing are confidential and are the exclusive property of Truist Group of Companies. No use, copy or disclosure for other purposes without the written consent of Truist Group of Companies is permitted. All rights reserved.
2035 Lakeside Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4058 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper fit and illumination prior to install.



Site ID:	100991	Drawn By:	AKW
Client:	Truist	Checked By:	N/A
Project:	Re-brand	Scale:	N/A
Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
Date:	09/30/21	Page:	6

LOCATION - E02
PROPOSED



Action:	Remove and replace letterset
Sign Type:	LILPFTC24
Description:	Linear Purple Letterset
Repair Action:	Patch and Paint SW 7757
Signage Text:	Truist with monogram logo
Comments:	Existing sign non-illuminated - Electrician required to run circuit Existing Wall 26' 0" x 43' 5"

EXISTING	Quantity:	1
----------	-----------	---




Height:	4'-3"	Available Height:	7' 0"
Width:	12'-8 3/8"	Available Width:	43' 5"


COPYRIGHT © The details shown on this drawing are confidential and are the exclusive property of Truist Group of Companies. No part, copy or disclosure of this information or its content may be made without written permission and a fee for electronic reproduction. All rights reserved.
2035 Lakeside Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4458 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper t and illumination prior to install.

	Site ID:	100991	Drawn By:	AKW
	Client:	Truist	Checked By:	N/A
	Project:	Re-brand	Scale:	N/A
	Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
	Date:	09/30/21	Page:	7

LOCATION - E03
PROPOSED



Action:	Remove and replace letterset
Sign Type:	LILPFTC24
Description:	Linear Purple Letterset
Repair Action:	Patch and Paint SW 7757
Signage Text:	Truist with monogram logo
Comments:	Existing sign non-illuminated - Electrician required to run circuit Existing Wall 25' 8" x 33' 2"

EXISTING	Quantity:	1
----------	-----------	---



Height:	4'-3"	Available Height:	7' 0"
Width:	12'-8 3/8"	Available Width:	33' 2"



COPYRIGHT © The publicly shown architectural drawings are confidential and are the property of the City of Knoxville. No part of this drawing may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without prior written permission from the City of Knoxville. All rights reserved.

2035 Lakeside Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4058 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper fit and illumination prior to install.

TRUIST 	Site ID:	100991	Drawn By:	AKW
	Client:	Truist	Checked By:	N/A
	Project:	Re-brand	Scale:	N/A
	Title:	20280 Grande Oak Shoppes Fld	Revision:	Permit
	Date:	09/30/21	Page:	8

LOCATION - E04
PROPOSED



Action:	Remove and replace directional
Sign Type:	Custom Directional
Description:	Purple face, white copy
Repair Action:	Fill in ground after install
Signage Text:	Side A: Drive-Thru → Parking ← Side B: Drive-Thru ↑ Parking →
Comments:	Allowed 3' Height

EXISTING		Quantity:	1 D/S
Height:	1'-3"	Available Height:	3'
Width:	2'-6"	Available Width:	2'


2035 Lakesich Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4058 F+865 692 4104

NOTE:

All measurements and required electrical details to be verified by supplier for proper fit and illumination prior to install.

Site ID:	100991	Drawn By:	AKW
Client:	Truist	Checked By:	N/A
Project:	Re-brand	Scale:	N/A
Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
Date:	09/30/21	Page:	9

LOCATION - E05
PROPOSED



Side A Side B	
Action:	Remove and replace directional
Sign Type:	Custom Directional
Description:	Purple face, white copy
Repair Action:	Fill in ground after install
Signage Text:	Side A: Drive-Thru ↑ Side B: Exit ↑
Comments:	Allowed 3' Height


EXISTING		Quantity:	1 D/S
Side A Side B			
Height:	1'-3"	Available Height:	3'
Width:	2'-6"	Available Width:	2'

2035 Lakeside Centre Dr Suite 250
Knoxville, TN 37922
T+865 692 4058 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper fit and illumination prior to install.

		Site ID:	100991	Drawn By:	AKW
		Client:	Truist	Checked By:	N/A
		Project:	Re-brand	Scale:	N/A
		Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
		Date:	09/30/21	Page:	10

LOCATION - E06
PROPOSED



Action:	Remove and replace directional
Sign Type:	Custom Directional
Description:	Purple face, white copy
Repair Action:	Fill in ground after install
Signage Text:	Side A: Entrance ← Side B: Entrance →
Comments:	Allowed 3' Height



EXISTING		Quantity:	1 D/S
		Height:	1'-3"
		Available Height:	3'
		Width:	2'-6"
		Available Width:	2'

COPYRIGHT © The details shown on this drawing are confidential and are the exclusive property of Truist Bank of Georgia. No use, copy or disclosure of this drawing or its contents may be made without the prior written permission of Truist Bank of Georgia. All rights reserved.
2035 Lakeside Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4658 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper fit and illumination prior to install.

TRUIST		Site ID:	100991	Drawn By:	AKW
		Client:	Truist	Checked By:	N/A
		Project:	Re-brand	Scale:	N/A
		Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
		Date:	09/30/21	Page:	11

LOCATION - E07
PROPOSED



Action:	Remove and replace directional
Sign Type:	Custom Directional
Description:	Purple face, white copy
Repair Action:	Fill in ground after install
Signage Text:	Side A: Parking Exit Side B: N/A
Comments:	Allowed 3' Height

EXISTING	Quantity:	1 D/S	
			
Height:	1'-3"	Available Height:	3'
Width:	2'-6"	Available Width:	2'

2035 Lakewood Centre Dr. Suite 250
Knoxville, TN 37922
T+865 692 4058 F+865 692 4104

NOTE:
All measurements and required electrical details to be verified by supplier for proper t and illumination prior to install.

Site ID:	100991	Drawn By:	AKW
Client:	Truist	Checked By:	N/A
Project:	Re-brand	Scale:	N/A
Title:	20280 Grande Oak Shoppes Blvd	Revision:	Permit
Date:	09/30/21	Page:	12



Planning, Zoning and Design Board
Staff Report

PROJECT NAME
Christ Community Ministries
CASE NUMBER
DOS2021-E001
MEETING DATE
October 12, 2021
REQUEST
Development Order to expand the existing church building by approximately 3,000 square feet.
APPLICANT
Mark T. Goodman, Christ Community Ministries
LOCATION
20810 Highlands Ave
PROPERTY SIZE
2.33 acres
ZONING
Mixed Use Planned Development (Lee County Resolution Z-07-021)
PUBLIC INFORMATION MEETING DATES
The DRB conducted a Public Information Meeting on February 24, 2021

Staff Recommendation

Staff recommends approval of the Development Order with conditions. Staff believes with conditions the request meets the technical requirements of the Land Development Code.

Background

There is an existing older church on this property located on Highlands Avenue, east of US 41.

The applicant is requesting approval of a Development Order to remove existing temporary modular buildings and expand the existing church building by approximately 3,000 square feet. The property is 2.33 acres. The property was acquired in a land exchange transaction with the Village of Estero in January, 2019.

The project was reviewed by the DRB at a Public Information Meeting on February 24, 2021. Staff has also reviewed the plans in detail. Staff includes Village Staff as well as Lee County Utilities, Lee

County Department of Transportation, Estero Fire District, Lee Tran and Lee County Solid Waste Division.

Surrounding Uses

The existing church is older and nondescript. The project is bounded by a utility, Embarq Florida, to the north, Estero Court to the west, Highlands Ave to the east, and County Road to the south. The Village of Estero acquired property to the south and east for future use.

Architecture

The proposed addition and renovation is of the Florida Vernacular style of architecture. Many of the Florida Vernacular Style characteristics are included in the proposed structure including:

Roof shape	Gabled
Roof slope	Between 6:12 and 12:12
Roofing materials	Standing seam or "V" crimp metal
Roof overhangs	Deep, between two and four feet
Exterior	Stucco finishes
Openings, windows, and doors	Vertically proportioned with surrounds and sills. Horizontally proportioned openings are made of a grouping of vertical windows

The existing church does not have a "style," but the proposed building adds many of the Florida Vernacular style characteristics which is a significant improvement architecturally. The proposed Florida Vernacular architecture blends with the adjacent properties, including building colors, and architectural features. **However, staff recommends the roof color be an earth tone color versus gray to comply with the LDC.** An exterior building paint color schematic and materials are provided in the applicant's plans along with elevations and perspectives.

Transportation

Highlands Avenue is a Village-maintained local road. The posted speed limit is thirty (30) miles per hour. Estero Court is a private local road. The posted speed limit is twenty-five (25) miles per hour. Based on the Turn Lane Policy, a deceleration and left turn lane is not required. Average daily trips on Sunday would total 298.

There are no sidewalks proposed to be constructed along Estero Court to the west, Highlands Avenue to the east, and County Road to the south, due to conflicts with the drainage swales and site constraints. Review by staff indicates it would be more appropriate to place the future sidewalks on the south side of County Road and east side of Highlands Avenue for pedestrian access.

Stormwater

The surface water management system for the property consists of catch basins, pipes and swales to capture stormwater runoff and convey to the dry detention system for water quality treatment and attenuation prior to outfall into the Estero Court swale from the control structure.

The proposed surface water management system design and calculations have been reviewed by Village staff, and a South Florida Water Management District permit modification (Permit # 36-08730-P) has been approved. The lowest proposed elevation of the finished floor is 20.85 feet NAVD88.

Lighting

Site lighting is provided by LED luminaire full cut-off fixtures mounted at 25-foot poles within the site, all textured black color, which produce an average of 0.8 footcandles (fc) illumination. The project will have a maximum 0.2 fc measured at the property line onto the adjacent properties. All LED luminaires meet the requirement of the LDC. Details of the light poles and fixtures are provided with the applicant's documents.

Landscape Buffers

There is a 10-foot wide buffer required on the north property line, with a 20-foot buffer on the east, south and west sides of the property.

Environmental Issues

The property is currently served by an on-site disposal system (septic tank) and Lee County Utilities (LCU) water service. The sanitary sewer is greater than 2,000 feet away from the subject site. The Florida Department of Health has issued a letter approving the building expansion and continued use of the existing septic system including the expansion. LCU has approved the water use for the expansion. The Village has identified several areas for future utility expansion, including this area. In the future, this property will need to connect to central sewer.

There are existing seven (7) Sabal Palms and one (1) Live Oak that are to remain and be protected from construction activities.

There were gopher tortoises and habitat identified on the site which will require relocation per the Florida Department of Natural Resources.

1
2
3
4
5
6
7
8
9
10
11
12
13





Digitally signed
by Thomas
Dean Martin
Date:
2021.09.23
12:14:32 -04'00'


THOMAS DEAN MARTIN
LICENSE
No. 52022
STATE OF
FLORIDA
PROFESSIONAL ENGINEER


THOMAS DEAN MARTIN
FLORIDA P.E. #52022


This item has been digitally signed and sealed by Thomas Martin on the date indicated in the time stamp. The digital signature and seal are intended to verify the identity of the signer and the date of signing. The digital signature and seal are not intended to be used as a substitute for a physical signature and seal. The digital signature and seal are not intended to be used as a substitute for a physical signature and seal. The digital signature and seal are not intended to be used as a substitute for a physical signature and seal.






























Design Standard - Signs										Design Standard - Commercial Buildings										Design Standard - Architectural									
Requirement Section										Requirement Section										Requirement Section									









20810 Highlands Ave. ESTERO, FLORIDA Christ Community Ministries


Design Review Board
for Final Approval

Civil Engineering Plans

TDM Consulting, Inc.



Vicinity Map



Area Location Map



East View of the Existing Church



South View of the Existing Church




West View of the Existing Church



AS-BUILT SURVEY OF
**LOT 9 THROUGH 14,
 MARSHALL'S
 ESTERO RIVER GROVE,
 UNIT 1**
 AND PORTION OF LAND
 LYING IN SECTION 28-46-25

(PLAT BOOK 12, PAGE 133)
 INSTRUMENT NO. 2020000052143
 SECTION 28, TOWNSHIP 46 SOUTH, RANGE 25 EAST
 ESTERO, LEE COUNTY, FLORIDA



DESCRIPTION: (PER TITLE COMMITMENT)

LOT 9 THROUGH 14, MARSHALL'S ESTERO RIVER GROVES, UNIT 1, ACCORDING TO THE PLAT THEREOF AS RECORDED IN PLAT BOOK 12, PAGE 133, PUBLIC RECORDS OF LEE COUNTY, FLORIDA, AND THAT PARCEL SOUTH OF LOTS 11 AND 12, MARSHALL'S ESTERO RIVER GROVES, UNIT 1, AS RECORDED IN PLAT BOOK 12, PAGE 131, PUBLIC RECORDS OF LEE COUNTY, FLORIDA, WEST OF HIGHLAND AVENUE, NORTH OF COUNTY ROAD AND EAST OF ESTERO COURT, LEE COUNTY, FLORIDA.

ALSO DESCRIBED AS:

BEGINNING AT NORTHWEST CORNER OF LOT 9 AS SHOWN ON THE RECORD PLAT OF MARSHALL'S ESTERO RIVER GROVES, UNIT 1, AS RECORDED IN PLAT BOOK 12, PAGE 131, PUBLIC RECORDS OF LEE COUNTY, FLORIDA, RUN NORTH 89°12'51" EAST ALONG THE NORTHERLY LINE OF LOT 9 AND LOT 14 OF SAID RECORD PLAT FOR 240.00 FEET TO AN INTERSECTION WITH THE WESTERLY RIGHT OF WAY LINE OF HIGHLAND AVENUE; THENCE RUN SOUTH 00°37'09" EAST ALONG SAID WESTERLY RIGHT OF WAY LINE FOR 419.88 FEET TO AN INTERSECTION WITH THE NORTHERLY RIGHT OF WAY LINE OF COUNTY ROAD (50 FEET WIDE) AS SHOWN ON SAID RECORD PLAT; THENCE RUN SOUTH 88°12'14" WEST ALONG SAID RIGHT OF WAY LINE FOR 240.05 FEET TO AN INTERSECTION WITH THE EASTERLY RIGHT OF WAY LINE OF ESTERO COURT (50 FEET WIDE) AS SHOWN ON SAID RECORD PLAT; THENCE RUN NORTH 00°37'09" WEST ALONG SAID EASTERLY RIGHT OF WAY LINE FOR 424.82 FEET TO THE POINT OF BEGINNING.

MATTERS PERTAINING TO TITLE COMMITMENT

BY FIRST AMERICAN TITLE INSURANCE COMPANY
 FILE NO. NC5-921555-LA2, DATED AUGUST 03, 2018
 ITEMS 1, 2, 4, 5, 6, 7, 9, 10, 11, 12, 13, ARE NOT SURVEY RELATED
 ITEM 3 REFERENCES THIS SURVEY, AS SHOWN HEREON
 ITEM 8 PLAT OF MARSHALL'S ESTERO RIVER GROVES, UNIT 1, AS RECORDED IN PLAT BOOK 12, PAGE 131, PUBLIC RECORDS OF LEE COUNTY, FLORIDA, AS SHOWN HEREON.

SURVEY NOTES:


1. BASIS OF BEARING SHOWN HEREON TAKEN FROM THE WEST RIGHT-OF-WAY LINE OF HIGHLAND AVENUE, AS BEING PER DEED S.003709°E.
2. FIELD NOTES IN MARSHALL'S ESTERO RIVER GROVES, UNIT 1, THIS CERTIFICATION IS ONLY FOR LANDS DESCRIBED HEREON. IT IS NOT A CERTIFICATION OF TITLE, ZONING OR FREEDOM OF ENCUMBRANCES.
3. THIS SURVEY IS BASED ON OWNERS POLICY, BY D.D. REPUBLIC NATIONAL TITLE INSURANCE COMPANY, POLICY NO. DFC-8815536, DATED JULY 13, 2020.
4. UNDERGROUND STRUCTURES AND UTILITIES, IF ANY, ARE NOT INCLUDED.
5. THIS MAP/PLAT IS CONSIDERED SIGNED USING A DIGITAL SEAL IN ACCORDANCE WITH THE APPLICABLE STATE LAWS AND STATUTES (FS 668.001-006); FS 668.003; FS 672.002; 5-171065, FLORIDA ADMINISTRATIVE CODE, STATE OF FLORIDA.
6. THIS MAP/PLAT IS CONSIDERED SIGNED USING A DIGITAL SEAL IN ACCORDANCE WITH THE APPLICABLE STATE LAWS AND STATUTES (FS 668.001-006); FS 668.003; FS 672.002; 5-171065, FLORIDA ADMINISTRATIVE CODE, STATE OF FLORIDA.
7. ALL BEARINGS AND DISTANCES ARE PLAT AND MEASURED, UNLESS OTHERWISE SHOWN.
8. THIS SURVEY IS INTENDED TO BE VIEWED AS AN AS-BUILT SURVEY.
9. BENCHMARK DERIVED FROM GPS RTK NETWORK FROM 0003, ELEVATION 35.72 NAVD83.
10. ELEVATIONS ARE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD83).
11. FLOOD ZONE: "A" - FLOOD ZONE UNINCORPORATED AREAS ELEVATION 13.5 NAVD83 AS SCALED COMMUNITY NO. 125124 PANEL NO. 0583 SUFFIX --- F REVISION DATE: 8/28/08 MAP NUMBER 1207100583F
12. FLOOD ZONE: VILLAGE OF ESTERO COMMUNITY NO. 120260 PANEL NO. 0591 SUFFIX --- G REVISION DATE: 12/7/18 MAP NUMBER 1207100591G

THIS SURVEY IS CERTIFIED TO
 TDM CONSULTING, INC.

LEGEND:

- SET #4 IRON ROD (CAP LS #6515)
- FOUND IRON ROD (I.R.)
- CONCRETE MONUMENT (C.M.)
- PRM PERMANENT REFERENCE MONUMENT
- P.C.P. PERMANENT CONTROL POINT
- P.U.E. PUBLIC UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- L.M.E. LAKE MAINTENANCE EASEMENT
- P.C. POINT OF CURVATURE
- P.T. POINT OF TANGENCY
- OR. OFFICIAL RECORDS BOOK
- (S) AS PER SURVEY
- (M) AS MEASURED
- (P) AS PER PLAT
- (D) AS PER DEED
- (C) CURVE NUMBER
- L1 LINE NUMBER
- R/W RIGHT-OF-WAY
- CL CENTERLINE
- R.W.B. RECLAIM WATER BOX
- WM WATER METER
- W.V. WATER VALVE
- F.H. FIRE HYDRANT
- O/H OVERHEAD POWER
- P.P. POWER POLE
- GA&W. GUY ANCHOR & WIRE
- E.B. ELECTRIC BOX
- CT.B. CABLE TELEVISION BOX
- T.S.B. TELEPHONE SERVICE BOX
- N/D NAIL & DISK
- N/T.T. NAIL & TINTAB
- ELEV. ELEVATION
- B.M. BENCHMARK
- S. TYPICAL ELEVATION
- A/C AIR CONDITIONER
- W.S. WATER SYSTEM
- P.E. POOL EQUIPMENT
- CONCRETE CONCRETE
- P.O.B. POINT OF BEGINNING
- M.B. MAIL BOX
- B.C. BURIED CABLE
- M.E.S. MITERED END SECTION

Boundary Survey




Site Dimension Plan



LEGEND

R	RADIUS (5' UNLESS OTHERWISE NOTED)
EX.	EXISTING
R/W	RIGHT-OF-WAY
E.O.P.	EDGE OF PAVEMENT
CONC.	CONCRETE
TYP.	TYPICAL
PROP.	PROPOSED
SF	SQUARE FEET
LF	LINEAR FEET
E.O.P.	EDGE OF PAVEMENT
P.U.E.	PUBLIC UTILITY EASEMENT
D.E.	DRAINAGE EASEMENT

L.P.	LIGHT POLE
CLF	EXISTING CHAIN LINK FENCE
10SP	NUMBER OF PARKING SPACES IN LOT
[Solid Grey Box]	PROPOSED PAVEMENT
[Patterned Box]	PROPOSED CONCRETE
LDC	LAND DEVELOPMENT CODE
N.T.S.	NOT TO SCALE
C.P.	CONCRETE PAD





Parking Requirements



PARKING REQUIREMENTS

PER SECTION 34-2020(B) VILLAGE OF ESTERO LAND DEVELOPMENT CODE.
9,015 SF CHURCH (247 SEATS)

= 1.0 SPACES PER 3 SEATS

= 247 TOTAL SEATS/3 SEATS PER SPACE = 82.33 SPACES

REQUIRED PARKING = 83 SPACES (INCLUDING 4 SPACE FOR HC)

PROVIDED PARKING = 84 SPACES (INCLUDING 4 SPACES FOR HC AND 42 GRASS PARKING)

BICYCLE PARKING REQUIREMENTS

PER SECTION 10-610(D)3 VILLAGE OF ESTERO LAND DEVELOPMENT CODE.
THE NUMBER OF SAFE AND SECURE BICYCLE PARKING SPACES MUST BE FIVE PERCENT OF THE NUMBER OF REQUIRED VEHICLE PARKING SPACES.


REQUIRED AUTOMOBILE PARKING SPACES = 83


= 83 AUTOMOBILE PARKING SPACES * 0.05 = 4.15

= MIN. 5 BICYCLE SPACES REQUIRED

= 1 BICYCLE RACK REQUIRED (ASSUME 5 BICYCLES PER RACK)

PROVIDED = 1 (4' X 6') BICYCLE RACK AREA





Stormwater Calculations



STORMWATER CALCULATIONS

TOTAL DETENTION REQUIRED:

$$= 1" \times \text{TOTAL PARCEL AREA} \times 1'/12"$$

$$= 1" \times 101,363 \text{ SF} \times 1'/12"$$

$$= 8,447 \text{ CF}$$

OR $2.5" \times (\text{TOTAL IMPERVIOUS AREA} - \text{ROOF AREA}) /$

$$(\text{TOTAL PARCEL AREA} - \text{ROOF AREA}) \times \text{TOTAL PARCEL AREA} \times 1'/12"$$

$$= 2.5" \times (43,233 \text{ SF} - 9,015 \text{ SF}) / (101,363 \text{ SF} - 9,015 \text{ SF})$$

$$\times 101,363 \text{ SF} \times 1'/12" = 7,825 \text{ CF}$$


$$= 8,447 \text{ CF} \times 0.75 (\text{DRY DETENTION}) = 6,335 \text{ CF}$$


TOTAL DETENTION PROVIDED:

$$= \text{VOLUME IN DDA \#1}$$

$$= 1.5' (19,796 \text{ SF}) + 1.5' [(22,750 \text{ SF} - 19,796 \text{ SF})/2]$$

$$= 31,909 \text{ CF}$$







Lighting

[illegible]

Anchor Base Poles

SSA

SQUARE STRAIGHT ALUMINUM



Traffic Impact Statement




Table 5. Raw Trip Generation – Proposed Church (LUC 560)

247 Seats:

- A. Daily Average Vehicle Trip Ends (Sunday)
 $T = 1.21 (247) = 298$ (149 entering, 149 exiting)
- B. Sunday Peak Hour Average Vehicle Trip Ends (Generator)
 $T = 0.54 (247) = 133$ (65 entering, 68 exiting)

Source: TDM, 2020




Architectural Plans

Robert L. Massengale







Sherwin Williams Colors




SW6091
Reliable White



SW6086
Sand Dune





SW7705
Nuthatch




Galvalume Metal Roofing










Landscape Architectural Plans

Landesco, PLLC



VILLAGE OF ESTERO LANDSCAPE REQUIREMENTS

	Required:	Provided:
Commercial Development abutting the following uses: North Property Boundary: MPD <---> AG-2 Type 'A' Buffer (5' min. width; 4 Trees / 100 LF) ▶ 240.00 LF = 10 Trees $240 / 100 = 2.40 \times 4 = 9.60$ Trees East Property Boundary: WOR <---> ROW (HIGHLANDS AVE) Type 'D' Buffer (20' min. width; 5 Trees + 66 Shrubs / 100 LF) ▶ 419.85 LF = 21 Trees + 297 Shrubs $420 / 100 = 4.20 \times 5 = 21.00$ Trees $420 / 100 = 4.20 \times 66 = 277.20$ Shrubs South Property Boundary: WOR <---> ROW (COUNTY RD) Type 'D' Buffer (20' min. width; 5 Trees + 66 Shrubs / 100 LF) ▶ 240.00 LF = 12 Trees + 159 Shrubs $240 / 100 = 2.40 \times 5 = 12.00$ Trees $240 / 100 = 2.40 \times 66 = 158.40$ Shrubs West Property Boundary: WOR <---> ROW (ESTERO CT) Type 'D' Buffer (20' min. width; 5 Trees + 66 Shrubs / 100 LF) ▶ 424.82 LF = 22 Trees + 281 Shrubs $425 / 100 = 4.25 \times 5 = 21.25$ Trees $425 / 100 = 4.25 \times 66 = 280.50$ Shrubs	10 21 297 12 159 22 281	10 21 297 12 159 22 281
Open Space Calculations: Commercial 20% of development area must be provided as open space ▶ Open Space: $96,015 \text{ SF} \times 0.20 = 19,203.00 \text{ SF}$	19,203 SF	35,943 SF
General Trees. (GEN) All other developments. One tree must be provided per each 3,500 square feet of development area. ▶ GEN: $96,015 \text{ SF} / 3,500 = 27.43$ Trees	28	28
Building perimeter plantings. (BPP) Building Perimeter Plantings equal to ten percent of the proposed building gross ground level floor area must be provided. ▶ BPP: $9,015 \text{ SF} \times 0.10 = 901.50 \text{ SF}$ ▶ BPP: $(902 \text{ SF} / 2) / 9 = 50.11$ Shrubs	902 SF 51	990 SF 55
Landscaping of parking and vehicle use areas. (VUA) Internal landscaping. At least one canopy tree or a cluster of three sabal palms must be planted or retained for every 250 square feet of required internal planting area, and no parking space may be more than 200 feet from a tree planted in a permeable island, peninsula or median. ▶ VUA: $2,304 \text{ SF} / 250 = 9.22$ Trees Landscaped areas on the parking area perimeter or internal islands must equal or exceed a minimum of ten percent of the total paved surface area. ▶ VUA: $23,033 \text{ SF} \times 0.10 = 2,303.30 \text{ SF}$ ▶ VUA: $2,304 \text{ SF} / 9 = 256.00$ Shrubs	10 2,304 SF 256	10 2,395 SF 282
TOTALS TREES SHRUBS LANDSCAPE AREA	103 1,044 3,206 SF	103 1,074 3,385 SF



Trees



Orange Geiger
Cordia Sebestena



Pigeon Plum
Coccoloba Diversifolia



Cabbage Palm
Sabal Palmetto



Crape Myrtle
Lagerstroemia Indica



Shady Lady Black Olive
Ilex Bucida Buceras 'Shady Lady'



Sweetbay Magnolia
Magnolia Virginiana



Southern Slash Pine
Pinus Elliottii Var. Densa



Southern Live Oak
Quercus Virginiana

PLANT SCHEDULE						
KEY	SYMBOL	QTY	SPECIES	PLANT TYPE	CATEGORY	NATIVE STATUS
PROPOSED TREES						
Bb		6	SHADY LADY BLACK OLIVE, <i>Bucida buceras 'Shady Lady'</i>	CANOPY	BUF	NO
Cd		6	PIGEON PLUM, <i>Coccoloba diversifolia</i>	CANOPY	VUA	YES
Cs		20	ORANGE GEIGER TREE, <i>Cordia sebestena</i>	CANOPY	BUF	YES
Li		4	CRAPEMYRTLE, <i>Lagerstroemia indica</i>	CANOPY	GEN	NO
Mv		15	SWEETBAY MAGNOLIA, <i>Magnolia virginiana</i>	CANOPY	GEN	YES
Pe		37	Southern Slash Pine, <i>Pinus elliotii var. densa</i>	CANOPY	BUF	YES
		4			GEN	
Sp		6	Cabbage Palm, <i>Sabal palmetto</i>	PALM	BUF	YES
		12			VUA	
EXISTING TREES						
Qv		1	SOUTHERN LIVE OAK, <i>Quercus virginiana</i>	CANOPY	EX	YES
TOTAL TREES		111	REVIEW: 92 + 18 @ 3:1 + 1 @ 1:5 = 103			



Shrubs



Red Tip Cocoplum
Chrysobalanus Icaco





Clusia
Clusia Guttifera



Emerald Blanket
Carissa Marcocarpa



Orange Bird
Strelitzia Reginae





Seagrape
Coccoloba Uvifera



Parson's Juniper
Juniperus Davurica



Muhly Grass
Muhlenbergia Capillaris



Silver Saw Palmetto
Serenoa Repens



Floratam Grass
Stenotaphrum Secundatum

PLANT SCHEDULE									
PROPOSED SHRUBS									
Ci		35	Red Tip Cocoplum, <i>Chrysobalanus icaco</i> 'Red Tip'	SHRUB	BPP	YES			
Cg		279	CLUSIA (AUTOGRAPH PLANT), <i>Clusia guttifera</i>	SHRUB	BUF	YES			
Cm		74	EMERALD BLANKET NATAL PLUM, <i>Carissa macrocarpa</i> 'Emerald Blanket'	SHRUB	BUF	YES			
Cu		97	SEAGRAPE, <i>Coccoloba uvifera</i>	SHRUB	VUA	YES			
Jd		26 100	Parson's Juniper, <i>Juniperus davurica</i> 'Parsonii'	SHRUB	BUF GEN	YES			
Mc		20 233 85	Muhly Grass, <i>Muhlenbergia capillaris</i>	GRASS	BPP BUF VUA	YES			
Sr		51	Silver Saw Palmetto, <i>Serenoa repens</i>	SHRUB	BUF	YES			
Str		74	ORANGE BIRD OF PARADISE, <i>Strelitzia reginae</i>	SHRUB	GEN	YES			
TOTAL SHRUBS		1,074							
DRY DETENTION PLANTING									
Sb		2,528	Sandcord Grass, <i>Spartina bakerii</i>	SHRUB	VUA	YES			
SOD									
---		---	Floratam Grass, <i>Stenotaphrum secundatum</i> 'Floratam'	LAWN	THROUGHOUT	YES			



Existing Tree Survey





**Planning, Zoning and Design Board
Staff Report**

PROJECT NAME
Elementary School "K" & Middle School "NN" (now known as AAAA Pre-K through 8 School)
CASE NUMBER
DOS2021-E004
MEETING DATE
October 12, 2021
REQUEST
Development Order to construct combined elementary and middle school with related facilities
APPLICANT
Lee County District School Board
LOCATION
20897 Three Oaks Parkway
PROPERTY SIZE
68.49 acres
ZONING
Agriculture
PUBLIC INFORMATION MEETING DATES
The PZDB conducted a Public Information Meeting on September 14, 2021

Staff Recommendation

Staff recommends approval of the Development Order with conditions, and the monument sign design. Staff believes with conditions and if deviations are granted by the PZDB, the request will comply with the Land Development Code.

Background

The applicant is requesting approval of a Development Order to construct a combined kindergarten through 8th grade school, playing fields, parking lots, bus ramps, stormwater management areas and related infrastructure. The total project area is 68.49 acres. The project was reviewed by the PZDB at a Public Information Meeting on September 14, 2021. Staff has also reviewed the plans in detail. Staff includes Village Staff as well as Lee County Utilities, Lee County Department of Transportation, Estero Fire District, Lee Tran and Lee County Solid Waste Division.

Surrounding Uses

This site is zoned Agriculture (AG) which allows public schools. A Comprehensive Plan Amendment was approved by Village Council which categorizes the site as "Public Facilities". The project is bounded by US Post Office and Copper Oaks subdivision to the north, Villages at Country Creek to the west across Three Oaks Parkway, I-75 to the east, and Calvary Chapel church, a preserve area, and Gerber Collision, an automotive repair facility, to the south.

Architecture

The building structure is tilt-up concrete for long-term durability. The style is somewhat plain. The staff has been working with the applicant to add variation to the canopies. Additionally, at the Public Information Meeting, the Planning, Zoning and Design Board made several suggestions to enhance the architecture, understanding the financial constraints of the School District. The plans have been revised to add architectural treatments on the western elevation to break up the flat roof, and also add trees to soften the look of the building. The building will be set back from both Three Oaks Parkway and I-75 and will be partially obscured.

The colors are earth tones and are compliant with the Land Development Code.

The applicant has requested architectural deviations as suggested by the PZDB. The deviations and justifications are attached.

Transportation

This project has access on the east side of Three Oaks Parkway, a north-south Lee County maintained arterial. Three Oaks Parkway is a four-lane divided roadway with a 45-mph posted speed limit. Corkscrew Road, south of the project site, is an east-west Lee County maintained arterial. In the project vicinity, Corkscrew Road is a four-lane divided roadway with a 45-mph posted speed limit. Estero Parkway, north of the project site is an east-west arterial, Lee County maintained east of Three Oaks Parkway and Village maintained west of Three Oaks Parkway. In the project vicinity, Estero Parkway is a four-lane divided roadway with a 45-mph posted speed limit.

A traffic signal will be required at the project's access point onto Three Oaks Parkway, to be paid by the School District as it is considered site-related. Because Three Oaks Parkway is county-maintained, the applicant must receive Limited Development Order approval for the project. This application is currently under review by the County. One of the items that will need to be addressed is synchronization of traffic lights to avoid traffic signal delays and other operational issues. The County will also evaluate the turn lanes, vehicle stacking and queueing, and road links.

The school is planned to open in August, 2023 with 1,800 students. Based on the County's concurrency report, the projected Level of Service would be E, which is considered acceptable.

The combined school with 2,350 students will generate 4,961 average daily trips at buildout. When background traffic is included, there could be level of service issues on Three Oaks Parkway, and on Corkscrew Road between I-75 and Three Oaks Parkway according to the applicant's traffic analysis submitted with the Development Order. This was based on using a worst case scenario and a high growth rate of 7%. Signal timing and turn lanes should mitigate this issue, along with the delayed school opening times after peak hour. Regardless, traffic will need to be closely monitored because projections can vary based upon general economic factors.

When a roadway exceeds capacity, it creates a level of service issue. However, transportation concurrency is no longer mandatory by State law. The traffic analysis is used instead to identify these problem areas so that solutions can be identified in capital improvement plans. The school proposes staggered start and end times for the school day (8:55 a.m. and 3:55 p.m.) to avoid peak hour traffic, substantial on-site stacking of vehicles dropping off and picking up students, turn lanes and a traffic signal to mitigate traffic impacts.

Stormwater Management

The surface water management system for the property consists of catch basins, pipes and swales to capture stormwater runoff and convey to the dry detention system and lakes for water quality treatment and attenuation prior to outfall into the Three Oaks storm sewer/swale from the control structures. From there, water flows to Corkscrew Road and to the Estero River.

The proposed surface water management system design and calculations have been reviewed by the Village staff, and a permit modification (Permit # SFWMD 85-00149-S) has been submitted to the water management district. The lowest proposed elevation of the finished floor is 20.00 feet NAVD88.

Lighting

The applicant has requested a deviation for lighting and light pole height. The deviation is explained in the attached document. The light pole height will comply with the Code, adjacent to Copper Oaks residential development, and no glare or illumination will extend onto adjacent properties.

Landscaping and Buffers

It should be noted that the Land Development Code does not contain any buffer requirements for schools. However, the School District is proposing an enhanced buffer along the north property line adjacent to Copper Oaks residential development, as well as trees along Three Oaks Parkway, and a natural retention area with 50 trees. Deviations are requested and are on the attached document.

The site will meet the 30% open space requirement.

Off-Street Parking, Bicycle Parking, and Loading Standard

The LDC [5-204.B.5.C.] requires sites with an off-street parking area with 150 or more parking spaces to provide at least three Electric Vehicle (EV) charging stations. Staff believes this was intended for commercial projects and not intended for public schools; however, the Code does not distinguish. The applicant's justification is attached.

Environmental Issues

The property will be served by Lee County Utilities for sanitary sewer and potable water service.

The Protected Species Survey indicates that there were no "protected species" identified on the site. There were other more common species found on the site that are not protected.

A large portion of the site is wetland, primarily low quality with exotic infestation. The wetlands were permitted by the SFWMD and US Army Corps of Engineers to be filled several years ago, with required purchase of mitigation credits. During the review of the Comprehensive Plan Amendment, policy language was added to allow consideration of schools in wetlands with appropriate mitigation and provision of a public benefit, such as provision of additional open space or onsite recreational facilities that are available for use by the public. The Village is currently working with the School District on an interlocal agreement for shared facilities.

Deviations

The Planning, Zoning and Design Board requested that the applicant identify where they could not comply with the Land Development Code and would need deviations. The attached list identifies those deviations needed for the site (including landscape), architecture, and exterior lighting. The list explains the applicant's justification for each.

Approval Conditions

Staff suggests in addition to the standard stipulations of approval for development orders, that the following conditions be included:

1. Prior to the start of construction, a construction traffic activity management plan will be submitted for review and approval, with contact names and numbers, indicating details of how construction activity will be managed to avoid adverse offsite impacts to the road and surrounding properties.
2. Electronic signs are prohibited.
3. No signage is allowed on any fences which are visible from the adjacent properties or roadways.

Attachment:

1. Deviation Requests



SINCE 1946



AAAA PreK-8 School - DEVIATION REQUESTS

SITE:

SECTION 5-204.B.5.C – Electric Vehicles - An off-street parking area with 150 or more parking spaces shall provide at least three EV charging stations.

JUSTIFICATION - We believe this was intended for commercial projects and not intended for a public school. We believe EV stations are for the public's use and even though payment for such a service may be collected through a third-party service the initial cost to the school was not budgeted. The third-party administering the EV stations would also be required to follow the Jessica Lunsford Act for security reasons. **The School District requests that no EV stations be required for the proposed school.**

SECTION 5-407.C – Building Perimeter Planting Standards - The planting areas for building perimeter plantings shall be located abutting three sides of a building, with emphasis on the sides most visible to the public (not including the loading area).

JUSTIFICATION - The front of the proposed school will have the required building plantings. However, two of the other three sides will not have the required plantings because the east side faces I-75, the north side has the bus access to the buildings and the south side faces a preserve area on the adjacent property. **The School District request they be required to do the building perimeter plantings only on the west side/front of the building for the reasons stated.**

SECTION 5-408.1.4 – Detention/Lake Amenity - Wet and dry detention areas exceeding 20,000 square feet in cumulative area and located adjacent to a public right-of-way are considered park areas and an attractor for pedestrian activity. These areas shall incorporate into the overall design of the project at least two of the following elements:

A five-foot wide walkway with trees an average of 50 feet on center, and shaded benches a minimum of six feet in length located on average every 150 feet or A public access pier with a covered structure and seating or An intermittent shaded plaza/courtyard, a minimum of 200 square feet in area, with benches and/or picnic tables adjacent to the water body or A permanent fountain structure or A continuous pedestrian way around the waterbody.

JUSTIFICATION – The dry detention area adjacent to the public ROW is required to have a 48" high chain link fence around the perimeter per SREF requirements, consequently the dry detention area will not be available to the public. Also, the school district discourages the public accessing any of their schools for security reasons. **The School District request they be required to do none of the features for the reasons stated.**

SECTION 5-409 – Landscaping of Parking areas, and vehicular access - The purpose of this subsection is to establish standards for the landscaping of parking areas to provide visual relief and cooling effects, and to channelize and define logical areas for pedestrian and vehicular circulation.

JUSTIFICATION – Although the school district cannot meet the requirement of this section for security reasons, the applicant has added clusters of palm trees in strategic areas to minimize the security risk from the added palms. **The School District request the Village of Estero approve the Alternate Landscape Betterment Plan.**

ARCHITECTURAL:

SECTION 5-703.A -Architectural Style Variation - Mediterranean Revival (Mission, Italian Renaissance, Italian Countryside) and Florida Vernacular styles are designated as the Village's primary architectural styles. The application of these styles is dependent on the context of the intended development.

JUSTIFICATION – The required styles are cost prohibitive to meet both, the Florida Statutes and SREF cost caps at the same time. Responsible use of taxpayer dollars, and quality construction, is concrete tilt-up walls, with low-slope roofs and steel framed interior that provides 50+ year life span and future flexibility. **The School District agrees to enhance the western elevation to align with the LDC more closely as it is the only side visible from Three Oaks Parkway.**

SECTION 5-703.1.D – Sloped Roofs - Mediterranean Revival Style architecture includes the key characteristics identified in Table 5-703.A.1.D: Mediterranean Revival Style Characteristics. See also Figure 5-703.A.1.D: Mediterranean Revival Defining Elements.

Roof slopes are shallow and are sloped between 3:12 and 6:12.

JUSTIFICATION - Sloped roofs are expensive, more vulnerable to hurricane damage, and increase maintenance cost/time. The extra ridges, valleys, copings, etc. all lead to potential leaks which impact both the exterior envelope and interior environmental air quality.

SECTION 5-706.C.6.C - Horizontal Plane Offsets – For buildings with a gross ground floor area over 35,000 SF, horizontal wall planes shall be interrupted with an offset dimension of at least two feet to change the horizontal plane at the following maximum intervals: every 100 linear feet for facades facing roads or providing primary entrances, and every 150 linear feet for all other.

JUSTIFICATION - Horizontal projections, especially for concrete tilt wall construction, creates multiple vertical joints and additional roof flashing conditions that lead to potential leaks which impact both the exterior envelope and interior environmental air quality. **The School District agrees to enhance the western elevation to more closely align with the LDC as it is the only side visible from Three Oaks Parkway.**

SECTION 5-706.F.2 – Roof Treatments – Roofs shall be designed to also meet three or more of the following requirements.

- A. Parapets used to conceal rooftop equipment and flat roofs.
- B. Three or more roof slope planes per primary façade.
- C. Sloping roofs, which do not exceed the average height of the supporting walls, that have an average slope equal to or greater than 4V:12H but not greater than 12V:12H.
- D. Additional vertical roof changes with a minimum change in elevation of two feet (flat roofs shall have a minimum of two changes)
- E. Three-dimensional cornice treatments which are a minimum of ten inches in height with a minimum of three reliefs.

JUSTIFICATION - With flat roof construction, the applicant can meet 2 of the required 3 requirements, 2.A and 2.E. The other 3 requirements relate primarily to sloped roofs. **The School District requests to only meet 2 of the 5 requirements due to the proposed flat roof on the building. The School District also agrees to enhance the western elevation to align with the LDC more closely as it is the only side visible from Three Oaks Parkway**

EXTERIOR LIGHTING STANDARDS:

SECTION 5-604.C – Light Pole Height - Maximum Mounting Height – Except for street lighting, the height of exterior light fixtures, whether mounted on poles, walls, or by other means, shall comply with the standards in Table 5-604.C.


JUSTIFICATION – The subject property is zoned AG-2 which requires 15’ maximum height for light poles. The property is being used in an institutional manner where the maximum light pole height would be 25’ per the LDC. **The School District requests the 15’ pole height along the residential community and 25’ pole height in the rest of the proposed school. The plan meets all the photometric requirements in both scenarios..**

SECTION 5-604.E – Lighting Standards - Standards for LED Luminaries – All exterior luminaries that include LED light sources shall comply with the following Illuminating Engineering Society of North America (IES) standards.

1. The Correlated Color Temperature (CCT) shall not exceed 3000K **to allow 4000K.**
2. Backlight (B) shall not exceed 1 **to allow 3**
3. Uplight (U) shall be 0 – comply with code
4. Glare (G) shall not exceed 1 **to allow 3**

JUSTIFICATION - Security is at the forefront of every discussion when building a school. The proper level of lighting and color temperature is critical for security cameras to identify threats during and after an event. The 3000K temperature light will be more in the red, yellow and orange spectrum giving everything an orangish/brown haze look, making it more difficult to identify with a security camera. **The School District is proposing to use 4000K temperature LED’s, natural daylight color temperature, to better identify color and movement.** This will create a safer environment while a more deterrent type of color to any threat on campus. The 4000K temperature LED lamp is an industry standard for all school campuses.

The State Requirements for Educational Facilities (SREF) has certain footcandle levels the School District must maintain throughout the school campuses for security and safety reasons. To meet the SREF criteria. The School District must use higher lumen packages to accomplish the levels which in turn increases the BUG ratings (specifically the B and G Ratings). Using the BUG rating of 1-0-1 does not allow the use of higher lumen packages thus not meeting the SREF footcandle levels. **The School District is proposing to allow multiple BUG ratings comply with SREF and provide the proposer security lighting for the proposed school.** Any light pole that is located on or near a property line is fitted with an internal and external house shield to reduce any light or glare at the property line. With the proposed deviations to the code, the School District will comply with the Village of Estero footcandle requirements at the property line and at 10’ and 50’ beyond the property line. **The School District is requesting to use 4000K temperature LED’s, and multiple BUG ratings to comply with SREF requirements and for the security of the school.**



SCHOOL BOARD OF LEE COUNTY AAAA PREK-8 SCHOOL (F.K.A. ELEMENTARY SCHOOL K AND MIDDLE SCHOOL NN) DEVELOPMENT ORDER (DOS2021-E004)


Village of Estero
PZDB Board Public Hearing
October 12, 2021



Applicant

Kathie Ebaugh, AICP
Director Facilities Planning & Development
School District of Lee County

Tina Silcox
Construction Services Project Manager
School District of Lee County



Representative


Dana L. Hume, P.E.
Principal
Johnson Engineering, Inc.

RESPONSE TO PZDB PUBLIC MEETING SEPTEMBER 14, 2021

- **LANDSCAPE DISCUSSION**
- **ARCHITECTURAL DISCUSSION**
- **TRAFFIC DISCUSSION**
- **DEVIATIONS DISCUSSION**
- **VILLAGE CODE vs TYPICAL SCHOOL**

UPDATED ALTERNATE LANDSCAPE BETTERMENT PLAN

- ADDED PALMS TO DIFFERENT AREAS OF THE SITE – 48 ADDITIONAL PALMS
- ADDED 20' - 24' HEIGHT PALMS ALONG BUILDING FACE – 9 TOTAL
- ALSO ADDED 14' – 16' HEIGHT PALMS ALONG BUILDING FACE – 17 TOTAL



ARCHITECTURE

RENDERED SITE PLAN



**SCHOOL
ENTRANCE
WITHOUT
LANDSCAPING**



**SCHOOL
ENTRANCE
WITH
LANDSCAPING**



**SOUTHERN
PORTION OF
FRONT OF SCHOOL
WITHOUT
LANDSCAPING**



**SOUTHERN
PORTION OF
FRONT OF
SCHOOL WITH
LANDSCAPING**



**VIEW OF GYM
ENTRANCE FROM
BUS AREA**





**VIEW OF
BUILDING
FROM I-75**



**RENDERED
AERIAL VIEW**








ARCHITECTURE
INTERIOR DESIGN
LANDSCAPE ARCHITECTURE
AR 001340

HARVARD • JOLLY
ARCHITECTURE

1000 N. 10th St., Suite 100
Phoenix, AZ 85004
Phone: (602) 944-1111
Fax: (602) 944-1112
www.harvardjolly.com



ARCHITECTURE
INTERIOR DESIGN
LANDSCAPE ARCHITECTURE
AR 0013140

HARVARD • JOLLY
ARCHITECTURE

1000 N. W. 10th Ave., Suite 100
Fort Lauderdale, FL 33304
Phone: 954.561.1000
Fax: 954.561.1001
www.harvardjolly.com

TRAFFIC

- Land Use Code for Elementary School used as worst-case scenario, higher trip generator
- Trip Generation based off a maximum of 2,350 students. **Initial student population is 1,800 students**
 - 1,800 students are anticipated to generate 369 LESS AM trips, 187 LESS PM trips, and 1,171 LESS daily trips than 2,350 students.
- School hours to occur at **off-peak** roadway hours (8:55am-3:55pm)
- Maximum trip generation for 2,350 students were applied to the peak hour of the roadway to assess roadway concurrency at peak hour, although actual volumes to occur at off peak hours
- Growth rate used for Three Oaks Parkway for 2025 volumes was 7%
- Volumes in 2025, prior to the addition of project traffic are anticipated to be within 94 trips of capacity.
- **Proposed traffic mitigation improvements as part of the proposed School to include:**
 - Approximate 700-ft dual southbound left turn lane
 - Approximate 300-ft northbound right turn lane
 - Signalized intersection at Three Oaks and School Entrance/Laurel Oak Drive with cross walks

TRAFFIC (continued)

Lee County Identified Projects

Lee County Projects and Improvements:

- Corkscrew Road from US 41 to east of Ben Hill Griffin Parkway - Widen from 4 to 6 lanes
- Corkscrew Road from Ben Hill Griffin Parkway to Alico Road - Widen from 2 to 4 lanes

Lee County Intersection Improvements:

- Corkscrew Road & Three Oaks Parkway Intersection Improvements include extending eastbound left turn lanes, extend northbound right turn lane & add secondary northbound right turn lane
- Corkscrew Road & US41 intersection improvements include constructing secondary northbound right turn lane.

State Funded Project: I-75 and Corkscrew Road Interchange

VILLAGE CODE vs TYPICAL SCHOOL

Landscape Requirements

Dry detention plantings: 4,470 spartina plants = \$22,300

Littoral Plantings: 8,345 plants = \$16,700

Building Plantings: 126 plants = \$4,400

Natural Area Plantings: 50 trees = \$11,300

Additional Palm Trees: 51 palms = \$18,700

Total Cost = \$73,400

Lighting Requirements (with approved deviations)

Code required 15' height poles vs. 25' high poles = \$38,000

Architectural Requirements

Parapet "pop-up aches" = \$7,500

Canopy "pop ups" (9 canopies total) = \$22,100

Aluminum Canopy = \$15,000

Total = \$44,600

**Total Additional
Costs to Meet
Village Code =
\$156,000**

DEVIATION REQUESTS: SITE

SECTION 5-204.B.5.C – Electric Vehicles - An off-street parking area with 150 or more parking spaces shall provide at least three EV charging stations.

JUSTIFICATION - We believe this was intended for commercial projects and not intended for a public school. We believe EV stations are for the public's use and even though payment for such a service may be collected through a third-party service the initial cost to the school was not budgeted. The third-party administering the EV stations would also be required to follow the Jessica Lunsford Act for security reasons. **The School District requests that no EV stations be required for the proposed school.**

SECTION 5-407.C – Building Perimeter Planting Standards - The planting areas for building perimeter plantings shall be located abutting three sides of a building, with emphasis on the sides most visible to the public (not including the loading area).

JUSTIFICATION - The front of the proposed school will have the required building plantings. However, two of the other three sides will not have the required plantings because the east side faces I-75, the north side has the bus access to the buildings and the south side faces a preserve area on the adjacent property. **The School District request they be required to do the building perimeter plantings only on the west side/front of the building for the reasons stated.**

SITE (CONT.)

SECTION 5-408.I.4 – Detention/Lake Amenity - Wet and dry detention areas exceeding 20,000 square feet in cumulative area and located adjacent to a public right-of-way are considered park areas and an attractor for pedestrian activity. These areas shall incorporate into the overall design of the project at least two of the following elements:

*A five-foot wide walkway with trees an average of 50 feet on center, and shaded benches a minimum of six feet in length located on average every 150 feet **or** A public access pier with a covered structure and seating **or** An intermittent shaded plaza/courtyard, a minimum of 200 square feet in area, with benches and/or picnic tables adjacent to the water body **or** A permanent fountain structure **or** A continuous pedestrian way around the waterbody.*

JUSTIFICATION – The dry detention area adjacent to the public ROW is required to have a 48” high chain link fence around the perimeter per SREF requirements, consequently the dry detention area will not be available to the public. Also, the school district discourages the general public accessing any of their schools for security reasons. **The School District request they be required to do none of the features for the reasons stated.**

SECTION 5-409 – Landscaping of Parking areas, and vehicular access - The purpose of this subsection is to establish standards for the landscaping of parking areas to provide visual relief and cooling effects, and to channelize and define logical areas for pedestrian and vehicular circulation.

JUSTIFICATION – Although the school district cannot meet the requirement of this section for security reasons, the applicant has added clusters of palm trees in strategic areas to minimize the security risk from the added palms. **The School District request the Village of Estero approve the Alternate Landscape Betterment Plan.**

ARCHITECTURAL

SECTION 5-703.A – Architectural Style Variations - Mediterranean Revival (Mission, Italian Renaissance, Italian Countryside) and Florida Vernacular styles are designated as the Village’s primary architectural styles. The application of these styles is dependent on the context of the intended development.

JUSTIFICATION - Response: Required styles are cost prohibitive to meet FI Statues and SREF cost caps. Responsible use of taxpayer dollars, and quality construction, is concrete tilt-up walls, with low-slope roofs and steel framed interior that provides 50+ year life span and future flexibility. **The School District agrees to enhance the western elevation to more closely align with the LDC as it is the only side visible from Three Oaks Parkway.**

SECTION 5-703.1.D – Sloped Roofs -Mediterranean Revival Style architecture includes the key characteristics identified in Table 5-703.A.1.D: Mediterranean Revival Style Characteristics. See also Figure 5-703.A.1.D: Mediterranean Revival Defining Elements. Roof slopes shallow and are sloped between 3:12 and 6:12.

JUSTIFICATION - Sloped roofs are expensive, more vulnerable to hurricane damage, and increase maintenance cost/time. The extra ridges, valleys, copings, etc. all lead to potential leaks which impact both the exterior envelope and interior environmental air quality.

SECTION 5-706.C.6.C - Horizontal Plane Offsets – For buildings with a gross ground floor area over 35,000 SF, horizontal wall planes shall be interrupted with an offset dimension of at least two feet to change the horizontal plane at the following maximum intervals: every 100 linear feet for facades facing roads or providing primary entrances, and every 150 linear feet for all other.

ARCHITECTURAL (CONT.)

JUSTIFICATION - Horizontal projections, especially for concrete tilt wall construction, creates multiple vertical joints and additional roof flashing conditions that lead to potential leaks which impact both the exterior envelope and interior environmental air quality. **The School District agrees to enhance the western elevation to more closely align with the LDC as it is the only side visible from Three Oaks Parkway.**

SECTION 5-706.F.2 – Roof Treatments – Roofs shall be designed to also meet three or more of the following requirements.

- A. Parapets used to conceal rooftop equipment and flat roofs.
- B. Three or more roof slope planes per primary façade.
- C. Sloping roofs, which do not exceed the average height of the supporting walls, that have an average slope equal to or greater than 4V:12H but not greater than 12V:12H.
- D. Additional vertical roof changes with a minimum change in elevation of two feet (flat roofs shall have a minimum of two changes)
- E. Three-dimensional cornice treatments which are a minimum of ten inches in height with a minimum of three reliefs

JUSTIFICATION - With flat roof construction, The School District can meet 2 of the 5 conditions, A. and D. The other 3 relate primarily to sloped roofs. **The School District requests to only meet 2 of the 5 requirements due to the proposed flat roof on the building. The School District also agrees to enhance the western elevation to align with the LDC more closely as it is the only side visible from Three Oaks Parkway.**

EXTERIOR LIGHTING STANDARDS

SECTION 5-604.C – Light Pole Heights - Maximum Mounting Height – Except for street lighting, the height of exterior light fixtures, whether mounted on poles, walls, or by other means, shall comply with the standards in Table 5-604.C.

JUSTIFICATION – The subject property is zoned AG-2 which requires 15' maximum height for light poles. The property is being used in an institutional manner where the maximum light pole height would be 25' per the LDC. **The School District requests the 15' pole height along the residential community and 25' pole height in the rest of the proposed school. The plan meets all the photometric requirements in both scenarios.**

SECTION 5-604.E – Lighting Standards - Standards for LED Luminaries – All exterior luminaries that include LED light sources shall comply with the following Illuminating Engineering Society of North America (IES) standards.

1. The Correlated Color Temperature (CCT) shall not exceed 3000K **to allow 4000K.**
2. Backlight (B) shall not exceed 1 **to allow 3**
3. Uplight (U) shall be 0 – comply with code
4. Glare (G) shall not exceed 1 **to allow 3**

JUSTIFICATION - Security is at the forefront of every discussion when building a school. The proper level of lighting and color temperature is critical for security cameras to identify threats during and after an event. The 3000K temperature light will be more in the red, yellow and orange spectrum giving everything an orangish/brown haze look, making it more difficult to identify with a security camera. **The School District is proposing to use 4000K temperature LED's, natural daylight color temperature, to better identify color and movement.** This will create a safer environment while a more deterrent type color to any threat on campus.


EXTERIOR LIGHTING STANDARDS (CONT.)

SECTION 5-604.E (continued)


JUSTIFICATION - The 4000K temperature LED lamp is an industry standard for all school campuses.

The State Requirements for Educational Facilities (SREF) has certain footcandle levels the School District must maintain throughout the school campuses for security and safety. To meet the SREF criteria, the School District must use higher lumen packages to accomplish the levels which in turn increases the BUG ratings (specifically the B and G Ratings). Using the BUG rating of 1-0-1 does not allow the use of higher lumen packages thus not meeting the SREF footcandle levels. **The School District proposes to allow multiple BUG ratings to comply with SREF and provide the proposer security lighting for the proposed school.** Any light pole that is located and/or near a property line is fitted with an internal and external house shield to reduce any light or glare at the property line. With the proposed deviations to the code, the School District will comply with the Village of Estero footcandle requirements at the property line and at 10' and 50' beyond the property line. **The School District is requesting to use 4000K temperature LED's, and multiple BUG ratings to comply with SREF requirements and for the security of the school. The plan meets all the photometric requirements in both scenarios.**

LIGHTING PLAN with 15' Pole Height



LIGHTING PLAN with 15' and 25' Pole Heights



THANK YOU

SCHOOL BOARD of LEE COUNTY





FLY THROUGH

The following attachment is not a PDF, so a link to the native file format is being provided instead:

[Estero Final Animation-1.m4v \(LINK\)](#)